

# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

CALCULATION NOTE FOR CONTROL VALVE SIZING							
در کننده بسا	نسهيلات صاه	رشته ت	نوع مدرك	سر يال	نسخه		
PEDC	O 120	PR	CN	0006	D03		
	·	. , , , , , ,	. , , , ,	. , , , , , ,			

**7 از** 7 شماره صفحه

# طرح نگهداشت و افزایش تولید 27 مخزن

### CALCULATION NOTE FOR CONTROL VALVE SIZING

نگهداشت و افزایش تولید میدان نفتی بینک

Class. 2	•					
Rev.	Date	Purpose of Issue/Status	Prepared by:	Checked by:	Approved by:	Client Approval
D00	SEP.2021	IFC	M.Aryafar	M.Fakharian	Sh.Ghalikar	
D01	DEC.2021	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D02	APR.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D03	JUL.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	

Class: 2 CLIENT Doc. Number: F0Z-708744

#### Status:

IDC: Inter-Discipline Check
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction
AFP: Approved For Purchase
AFQ: Approved For Quotation
IFI: Issued For Information
AB-R: As-Built for CLIENT Review
AB-A: As-Built —Approved



# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

CALCULATION NOTE FOR CONTROL VALVE SIZING

053 - 073 - 9184

پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	PR	CN	0006	D03

شماره صفحه: 2 از 7

# REVISION RECORD SHEET

					REVIS
PAGE	D00	D01	D02	D03	D04
1	Х	Χ	Х	X	
2	X	X	X	X	
3	X X X	X			
4	X	X			
5	X				
<u>6</u>	X	X	X		
	X	X	X X		
9	Ŷ		Ý		
10	X		X X		
11	X		X		
12	X		X		
13	X		Χ		
14	Χ		Х		
15	X		Χ		
16					
17					
18					
19					
20					
21					
22 23					
23 24					
25 25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40 41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
<u>55</u>					
<u>56</u>					
57 58					
58 59					
59 60					
61					
62					
63					
64					
65					

PAGE	D00	D01	D02	D03	D04
66					
67					
68					
69					
<u>70</u>					
71 72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83			1		
84					
85					
86			1		
87					
88			-		
89 90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					
101					
102					
103					
104					
105					
106					
107					
108 109					
1109					
111					
112					
113					
114					
115					
116					
117					
118					
119					
120					
121			-		
122			1		
123			1		
124			-		
125			-		
126			1		
127 128					
128 129			<del>                                     </del>		
130			t		
130	<u> </u>	1	1		·



# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

	CALCULATION NOTE FOR CONTROL VALVE SIZING							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	PR	CN	0006	D03	
	•							

شماره صفحه: 3 از 7

## **CONTENTS**

1.0	INTRODUCTION	
2.0	SCOPE	
3.0	NORMATIVE REFERENCES	5
3.1	Local Codes and Standard	5
3.2	International Codes and Standards	5
3.3	THE PROJECT DOCUMENTS	5
3.4	ENVIRONMENTAL DATA	5
3.5	Order of Precedence	5
4.0	ABBREVIATIONS	5
5.0	CONTROL VALVE SIZING	6
5.1	Software	6
5.2	CASE STUDY	6
5.3	SIZING	6
5.4	DETAILS OF CALCULATION RESULT	7
ATTA	CHMENT 1	7



## احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

CALCULATION NOTE FOR CONTROL VALVE SIZING								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	PR	CN	0006	D03	

شماره صفحه: 4 از 7

#### 1.0 INTRODUCTION

Binak oilfield in Bushehr province is a part of the southern oilfields of Iran, is located 20 km northwest of Genaveh city.

With the aim of increasing production of oil from Binak oilfield, an EPC/EPD Project has been defined by NIOC/NISOC and awarded to Petro Iran Development Company (PEDCO). Also PEDCO (as General Contractor) has assigned the EPC-packages of the Project to "Hirgan Energy - Design and Inspection" JV.

As a part of the Project, a New Gas Compressor Station (adjacent to existing Binak GCS) shall be constructed to gather of 15 MMSCFD (approx.) associated gases and compress & transfer them to Siahmakan GIS.

#### **GENERAL DEFINITION**

The following terms shall be used in this document.

CLIENT: National Iranian South Oilfields Company (NISOC)

PROJECT: Binak Oilfield Development - Surface Facilities; New

Gas Compressor Station

EPD/EPC CONTRACTOR (GC): Petro Iran Development Company (PEDCO)

EPC CONTRACTOR: Joint Venture of : Hirgan Energy - Design &

Inspection(D&I) Companies

VENDOR: The firm or person who will fabricate the equipment or

material.

EXECUTOR: Executor is the party which carries out all or part of

construction and/or commissioning for the project.

THIRD PARTY INSPECTOR (TPI): The firm appointed by EPC CONTRACTOR and

approved by GC & CLIENT (in writing) for the

inspection of goods.

SHALL: Is used where a provision is mandatory.

SHOULD: Is used where a provision is advisory only.

WILL: Is normally used in connection with the action by

CLIENT rather than by an EPC/EPD CONTRACTOR,

supplier or VENDOR.

MAY: Is used where a provision is completely discretionary.



# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

	CALCULATION NOTE FOR CONTROL VALVE SIZING							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	PR	CN	0006	D03	l
								_

شماره صفحه: 5 از 7

#### 2.0 SCOPE

The purpose of this document is to provide report for sizing of all control valves used in Gas Compressor station of Binak Plant.

#### 3.0 NORMATIVE REFERENCES

#### 3.1 Local Codes and Standard

IPS-E-IN-160 Engineering Standard for Control Valves

IPS-M-IN-160 Material Standard for Control Valves

IPS-E-PR-830 Process design of valves and control valves

#### 3.2 International Codes and Standards

API RP 553 Refinery Valves and Accessories for Control and

Safety Instrumented Systems

#### 3.3 The Project Documents

BK-GCS-PEDCO-120-PR-PF-0001 Process Flow Diagram (PFD)

BK-GNRAL-PEDCO-000-PR-DB-0001 Process Basis of Design

BK-GNRAL-PEDCO-000-PR-DC-0001 Process Design Criteria

#### 3.4 ENVIRONMENTAL DATA

Refer to "Process Basis of Design"; Doc. No. Process Basis of Design BK-00-HD-000-PR-DB-0001

#### 3.5 Order of Precedence

In case of any conflict between the contents of this document or any discrepancy between this document and other project documents or reference standards, this issue must be reported to the CLIENT. The final decision in this situation will be made by CLIENT.

#### 4.0 ABBREVIATIONS

NISOC: National Iranian South Oil Company

PFD: Process Flow Diagram

P&ID: Piping and Instrumentation Diagram



053 - 073 - 9184

# نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض

# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

**CALCULATION NOTE FOR CONTROL VALVE SIZING** رشته بسته کاری صادر کننده تسهيلات نسخه پروژه نوع مدرك سر يال PEDCO PR D03 BK GCS 120 CN 0006

شماره صفحه: 6 از 7

#### 5.0 CONTROL VALVE SIZING

#### 5.1 Software

The software using for sizing Control Valves is Nelprof 5.

#### 5.2 Case Study

Three cases have been considered for control valve sizing:

- Case 1: Minimum operating flow is equal to 30% of normal operating flow (the lowest flow rate between two case,( summer / winter) considered as normal flow).
- Case 2: Normal operating flow.
- Case 3: Maximum operating flow is equal to 110% of normal operating flow. (the highest flow rate between two case (summer / winter) considered as normal flow).

Note: It should be noted that the special conditions, related to each control valve is taken into account.

#### 5.3 SIZING

The below table contains the details sizing for the control vales that installed in GCS.



			Т	able 5.1: Co	ntrol Valve S	izing resul	t	
NO	LINE SIZE	Valve No.	Normal Flow Rate (kg/h)	Normal Upstream Pressure (Barg)	Normal Downstream Pressure (Barg)	CV Calculated	Size (in)	P&ID
1	6	FCV-2101	6564	6.5	5.5	176	4	BK-GCS-PEDCO-120-PR-PI-0002(1/1)
2	8	FCV-2102	11269	6.5	5.5	304	6	BK-GCS-PEDCO-120-PR-PI-0003(1/1)
3	3	FCV-2111	7122	19	18	19	1.5	BK-GCS-PEDCO-120-PR-PI-0004(3/3)
4	Deleted							
5	Deleted							
6	3	PCV-2272	506	5.1	4.9	23	3	BK-GCS-PEDCO-120-PR-PI-0022
7	1.5	PCV-2201	39	9	4.5	0.5	1	BK-GCS-PEDCO-120-PR-PI-0015(1/2)
8	4	PCV-2135	8664	54.1	1.5	16.54	2	BK-GCS-PEDCO-120-PR-PI-0011
9	4	PCV-2152	17605	52.9	2	33.23	3	BK-GCS-PEDCO-120-PR-PI-0013(1/3)
10	6	PCV-2151	17171	52.9	50.92	129	4	BK-GCS-PEDCO-120-PR-PI-0013(1/3)
11	1	PCV-2211	50	8	7.5	1.21	1	BK-GCS-PEDCO-120-PR-PI-0016



# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

---

053 - 073 - 9184

	CALCULATION NOTE FOR CONTROL VALVE SIZING								
پروژه	نسخه سریال نوع مدرک رشته تسهیلات صادر کننده بسته کاری پروژه								
BK	GCS	PEDCO	120	PR	CN	0006	D03		

شماره صفحه: 7 از 7

5.4 DETAILS OF CALCULATION RESULT



# **ATTACHMENT 1**

(SOFTWARE RESULT)