









احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان:

. 24 - . 14 - 9 1 14 +

	HAZOP REPORT FOR PIPELINE							
پروژه	نسخه سربال نوع مدرک رشته تسهیلات صادر کننده بسته کاری							
BK PPL PEDCO 320 GE RT 0004 D00								

شماره صفحه: 1 از 16

طرح نگهداشت و افزایش تولید ۲۷ مخزن

HAZOP REPORT FOR PIPELINE

نگهداشت و افزایش تولید میدان نفتی بینک

D00 Rev.	JUL. 2022 Date	IFI Purpose of Issue/Status	A.Baghaei Prepared by:	M.Fakharian Checked by:	M.Mehrshad Approved by:	CLIENT Approval
D00	JUL. 2022	IFI	A.Baghaei	M.Fakharian	M.Mehrshad	

Status:

IDC: Inter-Discipline Check
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction
AFP: Approved For Purchase
AFQ: Approved For Quotation

IFI: Issued For Information
AB-R: As-Built for CLIENT Review
AB-A: As-Built –Approved







نسخه

D00





ری بینک

احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره صفحه: 2 از 16

شماره پیمان:	HAZOP REPORT FOR PIPELINE						
·۵۳ – ·V۳ – ۹ ۱۸۴	پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال
-	BK	PPL	PEDCO	320	GE	RT	0004

REVISION RECORD SHEET

					REVIS
PAGE	D00	D01	D02	D03	D04
11	X				
2	X				
3	X Y				
<u>4</u> 5	X X X X X				
6	X				
7	Χ				
8	X				
9	X				
10	X				
11 12	\ \ \ \ \				
13	X				
14	X				
15	X				
16	Х				
17	 			 	
<u>18</u>	1			 	
19 20				†	
21					
22					
23					
24					
<u>25</u>					
26 27					
28					
29					
30					
31					
32	1			-	
33 34	1				
35					
36					
37					
38					
39					
40 41					
41					
43					
44					
45	1				
46	<u> </u>				
47	1			-	
<u>48</u>				†	
50					
51					
52					
53	<u> </u>				
<u>54</u>	1			-	
55 56				†	
57					
58					
59					
60	ļ			ļ	
61	1			-	
62	1			-	
63 64	1			t	
65	1			 	

PAGE	D00	D01	D02	D03	D04
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83	<u> </u>		 		
84	<u> </u>		 		
85	 		1		1
86	 		1		1
87	<u> </u>		 		
88	 		1	-	
89	1		1		
90	 		1		1
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					
101					
102					
103			-		
104					
105					
106			-		
107	1		+		1
108	1		+		1
109	 		+		
110	 		+		
111	 		+		
112 113	1		1		1
	1		1		1
114 115	1		1		1
	1		†		
116 117	1		†		
117	1		†		
118	1		†		
119			1		
120			1		
121	1		†		
123	<u> </u>		1		
123 124	1		†		
124 125	1		1		1
125 126	1		†		
126 127	1		†		
127	1		†		
	1		†		
129 130	1		†		
130		l	1	1	1











احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان:

. 24 - . 14 - 4114

	HAZOP REPORT FOR PIPELINE							
پروژه	نسخه سریال نوع مدرک رشته تسهیلات صادر کننده بسته کاری						نسخه	
BK PPL PEDCO 320 GE RT 0004 D00							D00	

شماره صفحه: 3 از 16

CONTENTS

1.0	INTRODUCTION	4
2.0	SCOPE	5
3.0	NORMATIVE REFERENCES	5
3.1	International Codes and Standards	5
3.2	THE PROJECT DOCUMENTS	
4.0	PURPOSE	5
5.0	HAZOP STUDY OVERVIEW	5
6.0	PROCEDURE	6
7.0	HAZOP OUTCOMES	
8.0	ATTACHMENTS	8
8.1	Appendix A –Team Members	8
8.1	Appendix B – Drawings List	10
8.1	APPENDIX C – NODES LIST	11
8.1	APPENDIX D – RECOMMENDATIONS LIST	
8.1	APPENDIX E – HAZOP WORKSHEETS	
8.1	APPENDIX F – MARKED-UP P&IDS	16











احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان:

 $\cdot \Delta \mathtt{T} - \cdot \mathtt{V} \mathtt{T} - \mathtt{9.1} \mathtt{A} \mathtt{F}$

	HAZOP REPORT FOR PIPELINE							
پروژه	نسخه سریال نوع مدر ک رشته تسهیلات صادر کننده بسته کاری							
BK PPL PEDCO 320 GE RT 0004 D00								

شماره صفحه: 4 از 16

1.0 INTRODUCTION

Binak oilfield in Bushehr province is a part of the southern oilfields of Iran, is located 20 km northwest of Genaveh city.

With the aim of increasing production of oil from Binak oilfield, an EPC/EPD Project has been defined by NIOC/NISOC and awarded to Petro Iran Development Company (PEDCO). Also, PEDCO (as General Contractor) has assigned the EPC-packages of the Project to "Hirgan Energy - Design and Inspection" JV.

As a part of the Project, New Gas/Condensate Pipelines (from Binak New GCS to Siahmakan GIS/Binak PU) shall be constructed.

GENERAL DEFINITION

The following terms shall be used in this document.

CLIENT: National Iranian South Oilfields Company (NISOC)

PROJECT: Binak Oilfield Development – Surface Facilities; Gas &

Gas-Condensate Pipelines

EPD/EPC CONTRACTOR (GC): Petro Iran Development Company (PEDCO)

EPC CONTRACTOR: Joint Venture of: Hirgan Energy - Design &

Inspection(D&I) Companies

VENDOR: The firm or person who will fabricate the equipment or

material.

EXECUTOR: Executor is the party which carries out all or part of

construction and/or commissioning for the project.

THIRD PARTY INSPECTOR (TPI): The firm appointed by EPD/EPC CONTRACTOR (GC)

and approved by CLIENT (in writing) for the inspection

of goods.

SHALL: Is used where a provision is mandatory.

SHOULD: Is used where a provision is advisory only.

WILL: Is normally used in connection with the action by

CLIENT rather than by an EPC/EPD CONTRACTOR,

supplier or VENDOR.

MAY: Is used where a provision is completely discretionary.











احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان: ۹۱۸۴ – ۰۷۳ – ۰۵۳

	HAZOP REPORT FOR PIPELINE							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK PPL PEDCO 320 GE RT 0004 D00							D00	

شماره صفحه: 5 از 16

2.0 SCOPE

The scope of HAZOP study covers all P&IDs for Gas & Gas-Condensate Pipelines. The list of P&IDs is presented in appendix B.

3.0 NORMATIVE REFERENCES

3.1 INTERNATIONAL CODES AND STANDARDS

 IEC 61882:2016 Hazard and Operability studies (HAZOP Studies) – Application guide

3.2 THE PROJECT DOCUMENTS

BK-GNRAL-HD-000-PR-DB-0001-D05 Process Basis of Design

4.0 PURPOSE

The purpose of this document is to provide the results of "HAZOP Study" for **Binak Oilfield Development – Surface Facilities; Gas & Gas-Condensate Pipelines**.

The objective of HAZOP study is to perform and achieve the following tasks and goals as far as practicable given the latest piping and instrumentation diagrams (P&ID's) to identify any potential hazards associated with the system and its utility systems:

- To identify any potential operating difficulties,
- Examine the effectiveness of those measures already incorporated in the design to mitigate the frequency and/or consequences of such hazards;
- To raise action items for addressing those hazards that the present design does not satisfactorily address.

5.0 HAZOP STUDY OVERVIEW

Meeting was conducted in one session at June 25, 2022 held in Neyshekar Hotel main meeting hall, Ahvaz.

A team comprising of experts from different disciplines of National Iranian South Oilfields Company (NISOC), Petro Iran Development Company (PEDCO) and Hirgan Energy Company conducted the study with a third-party HAZOP Chairman and Scribe. The list of team members is presented in appendix A.



رکت وریه سروایرا^ن







احداث خطوط انتقال گاز /مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان: ۱۸۲۶ – ۷۷۳ – ۵۳۰

HAZOP REPORT FOR PIPELINE								
پروژه	نسخه سریال نوع مدر ک رشته تسهیلات صادر کننده بسته کاری							
BK	BK PPL PEDCO 320 GE RT 0004 D00							

شماره صفحه: 6 از 16

6.0 PROCEDURE

The review methodology will be the "Guide Word" HAZOP technique and will be performed in accordance with the guidelines published by the Center for Chemical Process Safety (CCPS) of the American Institute of Chemical Engineers (AIChE) and also noted in IEC 61882.

The purpose of the review should not be only to resolve the action items but also to identify credible deviations from the design intent. The method identifies hazards and postulates possible accident sequences resulting from such hazards; Innovative thinking then identifies the consequences of these scenarios. The process demonstrates to the Owner/Management that prudent steps which have been taken to provide a safe installation and operation.

The scope of the HAZOP shall be therefore, on identifying potential process hazards or operability concerns, not on finding solutions to reduce or eliminate these concerns. Attempting to solve problems by the HAZOP team can result in a long and inefficient study process. At the same time, the HAZOP study cannot be intended as a review of Project Design Basis and Operating Philosophies, since these must be considered as resolved when the HAZOP study will be carried out.

Each system or equipment should be divided into subsystems by consensus of the review team. The selected system shall be identified by a study node numbers and for easy reference a color code can also be inserted on the related P&ID prior to the review and worksheet during the review.

List of possible parameters and guidewords

Deviations	Guide Word	Parameter	
No/Less Flow	No/Less	Flow	
More Flow	More	Flow	
Reverse/Misdirected Flow	Reverse/Misdirected	Flow	
High Temperature	High	Temperature	
Low Temperature	Low	Temperature	
High Pressure	High	Pressure	
Low Pressure	Low	Pressure	
High Level	High	Level	
Low Level	Low	Level	
Maintenance Hazards	Other than	Maintenance	
Leakage	As well as	Flow	

















بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک **HAZOP REPORT FOR PIPELINE** صادر کننده تسهيلات نوع مدرك پروژه بسته کاری سريال نسخه ΒK PPL PEDCO 320 GE RT 0004 D00

از 16	7 :	صفحه	شماره
-------	-----	------	-------

Deviations	Guide Word	Parameter
Corrosion	As well as	Operation
Composition	As well as	Composition
Start-up/Shutdown Hazards	Other than	Start-up/Shutdown
Loss of Utilities	Other than	Operation
Miscellaneous	As well as	Operation

7.0 **HAZOP OUTCOMES**

In order to facilitate the study, the process was broken down into 2 nodes. The node list is presented in appendix C. A total of 14 recommendations were obtained which are shown in appendix D. The recommendations are categorized in two groups, namely OPEN and CLOSED.

Closed recommendations are those that the team have arrived at a consensus that it is required to be done. 14 closed recommendation were obtained in the meetings. Open recommendations are those that need more information from vendor for the final decision. Zero open recommendations were proposed during the meetings.

Appendix E consists of detailed HAZOP Worksheets of the study.



· 24 - · 74 - 4 1 1 4

نگهداشت و افزایش تولید میدان نفتی بینک

احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز

سطح الارض







بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک شماره پیمان:

HAZOP REPORT FOR PIPELINE								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	PPL	PEDCO	320	GE	RT	0004	D00	

شماره صفحه: 8 از 16

8.0 **ATTACHMENTS**

8.1 **APPENDIX A -TEAM MEMBERS**

First Name	Last Name	Company	Expertise
S.Mehdi	Ashrafian	NISOC	Project Manager
Shamsolah	Bahadori	NISOC	Construction Manager
Fatemeh	Ghodsi	NISOC	Head of I&C
Mohammad	Torfi	NISOC	Process
Sahar	Saba	NISOC	Process
Niloofar	Rezaei Baba ahmadi	NISOC	Process
Mohammad Reza	Cheraghchi	NISOC	Process
Fazel	Moafi	NISOC	Instrument
Behzad	Zandian	NISOC	Instrument
Peyman	Sarvarian	NISOC	Mechanic
Hojjat	Jafarpour	NISOC	Mechanical
Faride	Parvin	NISOC	Mechanical
Mohammad	Khamisi	NISOC	HSE
Mohammad	Shirali	NISOC	Commissioning
Ali	Hamidan	NISOC	Commissioning
Naji	Hamid	NISOC	Commissioning
Khodadad	Kavosi	NISOC	Commissioning
Reza	Gholgheysari	NISOC	Process Engineer
Mobin	Saeedi	NISOC	Instrument
Mohammad	Bakhshi Mohammadi	Gachsaran NISOC	Production Engineer
Shahram	Valizadeh	Gachsaran NISOC	Production Engineer
Vahid	Mussavi	Gachsaran NISOC	Production Engineer
Mohammad	Fakoor	PEDCO	Process Engineer
Farshid	Amiri	PEDCO	Piping Lead Engineer
Hadi	Mozaffari	PEDCO	Electrical Engineer
Mahdi	Karimi	PEDCO	Head of Electrical Department
Pouria	Bavarsad	PEDCO	Piping Engineering
Sadegh	Gharacheh	PEDCO	Process
Morteza	Taherkhani	PEDCO	Head of I&C
Sepideh	Akbari	PEDCO	I&C Engineer
Sasan	Faramarzpour	PEDCO	Head of Process and Safety Department











احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان:

.04 - .14 - 114

HAZOP REPORT FOR PIPELINE								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
ВК	PPL	PEDCO	320	GE	RT	0004	D00	

شماره صفحه: 9 از 16

First Name	Last Name	Company	Expertise
Pouya	Maleki	PEDCO	Process Engineer
Mehdi	Sadeghian	PEDCO	Surface Manager
Vahid	Abdeshadi	PEDCO	Project Engineer Manager
Masoud	Asgharnejad	Hirgan Energy	Engineering Manager
Mohsen	Aryafar	Hirgan Energy	Process
Saeed	Ghanbari	Hirgan Energy	Process
Parisa	Hajisadeghi	Hirgan Energy	Head of I&C
Mohammad	Fakharian	Hirgan Energy	Project Manager
Ali	Baghaei	HAZOP Consultant	Process Safety
Firoozeh	Khosravi	HAZOP Consultant	Process Safety













شماره پیمان: $\bullet \Delta T = \bullet V T - 91 \Lambda F$

احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

HAZOP REPORT FOR PIPELINE							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	PPL	PEDCO	320	GE	RT	0004	D00

شماره صفحه: 10 از 16

8.1 **APPENDIX B - DRAWINGS LIST**

Drawing No.	Drawing Title	Place(s) Used
_	Gas Pipeline (to Siahmakan G.I. Station) (3 sheets)	Nodes: 1
BK-PPL-PEDCO-320-PR-PI-0002_D03	Condensate Pipeline (to Binak PU)	Nodes: 2











احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

پیمان:	شماره
.0414 - 1146	

HAZOP REPORT FOR PIPELINE								
پروژه	صادر کننده بسته کاری پروژه		تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	PPL	PEDCO	320	GE	RT	0004	D00	

شماره صفحه: 11 از 16

8.1 APPENDIX C - NODES LIST

Nodes	Color	Туре	Drawings	Equipment ID	Date
1. Gas Pipeline (to Siahmaka	n L Blue	Line			1. 06/25/2022
G.I. Station)		Pig Receiver	0001_D03	PR-3201	
		Pig Launcher			
Condensate Pipeline (to Binak PU)	Violet	Line	BK-PPL-PEDCO-320-PR-PI- 0002_D03	-	1. 06/25/2022











احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان: ۹۱۸۴ – ۷۲۰ – ۵۳۰

HAZOP REPORT FOR PIPELINE							
تسهیلات صادر کننده بسته کاری پروژه		تسهيلات	رشته	نوع مدرك	سريال	نسخه	
ВК	PPL	PEDCO	320	GE	RT	0004	D00

شماره صفحه: 12 از 16

8.1 APPENDIX D – RECOMMENDATIONS LIST

Recommendations	Place(s) Used	Responsibility	Status
Proxy limit switch signal of ESDV-3201 should be routed directly to DCS.	Consequences: 1.1.2.2	Contractor	Closed
2. Define high alarm on PIC-2152.	Consequences: 1.1.3.1	Contractor	Closed
Consider startup/backup instrument gas for LBV-3201 and LBV-3202.	Consequences: 1.1.4.1	Contractor	Closed
 Pig signaler ZS-3201 should be changed to local indicator (flag type). 	Consequences: 1.7.1.1	Contractor	Closed
5. Pig receiver barrel should be shown concentric on P&ID.	Consequences: 1.7.1.1	Contractor	Closed
Remove pig launcher/receiver and PL-3201, PR-3201 door position indicator.	Consequences: 1.7.1.1	Contractor	Closed
7. Remove spectacle blind of ESDV-3202.	Consequences: 1.7.1.1	Contractor	Closed
Note on PID that pig launcher and receiver doors are equipped with mechanical interlock to prevent opening before depressurizing.	Consequences: 1.7.1.1	Contractor	Closed
Relocate balance line of PL-3201 to launcher side of kicker line block valve.	Consequences: 1.7.1.1	Contractor	Closed
10. Relocate balance line of PR-3201 to receiver side of kicker line block valve.	Consequences: 1.7.1.1	Contractor	Closed
11. Remove corrosion inhibitor injection, CC and CP from pig launcher P&ID.	Consequences: 1.7.1.1	Contractor	Closed
12. Remove insulation joint of 4" condensate pipeline.	Consequences: 2.1.1.1	Contractor	Closed
13. Check requirement for installation of check valve at tie-in point (TP05) of 4" condensate pipeline.	Consequences: 2.1.1.1	Contractor	Closed
14. Show on PID of 4" condensate pipeline drain and vent connections and spectacle blind.	Consequences: 2.1.1.1	Contractor	Closed



نگهداشت و افزایش تولید میدان نفتی بینک

سطح الارض







احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان: \cdot Δ T - \cdot VT - 9 1 Λ F

HAZOP REPORT FOR PIPELINE							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
ВК	PPL	PEDCO	320	GE	RT	0004	D00

شماره صفحه: 13 از 16

8.1 **APPENDIX E - HAZOP WORKSHEETS**

Node: 1. Gas Pipeline (to Siahmakan G.I. Station)

Deviation: 1. No/Less Flow

Causes	Consequences	Safeguards	Recommendations
Decreased flow of dehydrated gas from upstream	No hazardous consequence		
2. ESDV-3201 closed by	1. Loss of gas to downstream		
failure or error	Increased pressure upstream of valve with possibility of	High pressure protection at compressor discharge	Proxy limit switch signal of ESDV-3201 should be
	damage	2. Limit switch on valve	routed directly to DCS.
Blockage of pipeline during pig	Increased pressure upstream of blocked point with possibility of damage	High pressure protection at compressor discharge	Define high alarm on PIC- 2152.
4. LBV-3201 or LBV-3202 closed by failure	Increased pressure upstream of valve with possibility of damage	High pressure protection at compressor discharge	Consider startup/backup instrument gas for LBV-3201 and LBV-3202.
	Decreased pressure downstream of valve with no hazardous consequence		
5. ESDV-3202 closed by failure or error	Increased pressure upstream of valve with possibility of	High pressure protection at compressor discharge	
	damage	2. Limit switch on valve	
6. Rupture in pipeline due to	1. Severe environmental impact	1. LBV-3201	
corrosion, TPD, landslide, etc		2. LBV-3202	
		3. PALL-3201 that will activate ESD-1 and close ESDV- 3201	

Node: 1. Gas Pipeline (to Siahmakan G.I. Station)

Deviation: 2. More Flow

Causes	Consequences	Safeguards	Recommendations
No issue was identified			

Node: 1. Gas Pipeline (to Siahmakan G.I. Station)

Deviation: 3. Reverse/Misdirected Flow

Causes	Consequences	Safeguards	Recommendations
Check valves are considered where required			









احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان:

.0474 - 1184	

HAZOP REPORT FOR PIPELINE							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
ВК	PPL	PEDCO	320	GE	RT	0004	D00

شماره صفحه: 14 از 16

Node: 1. Gas Pipeline (to Siahmakan G.I. Station)

Deviation: 4. Low Temperature

Causes	Consequences	Safeguards	Recommendations
Depressurizing for maintenance	Possibility of hydrate formation and freezing	Operating procedure to depressurize at defined time length	

Node: 1. Gas Pipeline (to Siahmakan G.I. Station)

Deviation: 5. High Pressure

Causes	Consequences	Safeguards	Recommendations
External fire case for pig launcher	Damage to equipment	1. PSV-3201	
External fire case for pig receiver	Damage to equipment	1. PSV-3202	

Node: 1. Gas Pipeline (to Siahmakan G.I. Station)

Deviation: 6. Low Pressure

Causes	Consequences	Safeguards	Recommendations
No new issue was identified			

Node: 1. Gas Pipeline (to Siahmakan G.I. Station)

Deviation: 7. Miscellaneous

Causes	Consequences	Safeguards	Recommendations
1. See Recommendation			Pig signaler ZS-3201 should be changed to local indicator (flag type).
			Pig receiver barrel should be shown concentric on P&ID.
			6. Remove pig launcher/receiver and PL-3201, PR-3201 door position indicator.
			7. Remove spectacle blind of ESDV-3202.
			8. Note on PID that pig launcher and receiver doors are equipped with mechanical interlock to prevent opening before depressurizing.











احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان: ۹۱۸۴ – ۷۷۳ – ۵۵۰

HAZOP REPORT FOR PIPELINE							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	PPL	PEDCO	320	GE	RT	0004	D00

شماره صفحه: 15 از 16

Node: 1. Gas Pipeline (to Siahmakan G.I. Station)

Deviation: 7. Miscellaneous

Causes	Consequences	Safeguards	Recommendations
			 Relocate balance line of PL-3201 to launcher side of kicker line block valve.
			 Relocate balance line of PR-3201 to receiver side of kicker line block valve.
			 Remove corrosion inhibitor injection, CC and CP from pig launcher P&ID.

Node: 2. Condensate Pipeline (to Binak PU)

Deviation: 1. Miscellaneous

Causes	Consequences	Safeguards	Recommendations
See Recommendation			12. Remove insulation joint of 4" condensate pipeline.
			13. Check requirement for installation of check valve at tie-in point (TP05) of 4" condensate pipeline.
			14. Show on PID of 4" condensate pipeline drain and vent connections and spectacle blind.











احداث خطوط انتقال گاز/مایعات گازی از ایستگاه تقویت فشار گاز بینک تا ایستگاه تزریق گاز سیاهمکان/واحد بهره برداری بینک

شماره پیمان: ۹۱۸۴ – ۷۷۳ – ۰۵۳

HAZOP REPORT FOR PIPELINE									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سر يال	نسخه		
BK	PPL	PEDCO	320	GE	RT	0004	D00		
DIX		. 2500	020	OL		0001	500		

شماره صفحه: 16 از 16

8.1 APPENDIX F - MARKED-UP P&IDS

