



# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

شماره پیمان:

· 24 - · 74 - 9114

	MTO FOR TELECOM EQUIPMENT							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	TE	MT	0003	D01	

شم**اره** صفحه: ۱ از ۶

# طرح نگهداشت و افزایش تولید ۲۷ مخزن

#### MTO FOR TELECOM EQUIPMENT

نگهداشت و افزایش تولید میدان نفتی بینک


Rev.	May. 2022 Date	Purpose of Issue/Status	Prepared by:	Checked by:	Approved by:	CLIENT Approval
D00	•	IFI	H.Shakiba	M.Fakharian	M.Mehrshad	
D01	Sep. 2022	IFI	H.Shakiba	M.Fakharian	M.Mehrshad	

Class:2 CLIENT Doc. Number: F8Z-709095

#### Status:

IDC: Inter-Discipline Check
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction
AFP: Approved For Purchase
AFQ: Approved For Quotation
IFI: Issued For Information
AB-R: As-Built for CLIENT Review
AB-A: As-Built —Approved









#### MTO FOR TELECOM EQUIPMENT شماره پیمان:

 $\cdot$   $\Delta$ T -  $\cdot$   $\vee$ T - 9 1  $\lambda$ F

	-						
پروژه	بسته کاری	صادر كننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	TE	MT	0003	D01

شماره صفحه: ۲ از ۶

# REVISION RECORD SHEET

PAGE	D00	D01	D02	D03	D04
1	X	X			
2	Х	Х			
3	Х	Χ			
4	Х	X			
5	X	X			
6	X	Х			
7	,	,,			
8					
9					
10					
11					
12					
13					
14					
15					
16	1				
17	+				
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39				ļ	
40					
41					
42					
43					
44					
45					
46					
47					
48					
49				1	
50					

PAGE	D00	D01	D02	D03	D04
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98	-				
99					
100					





# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

	شماره پیمان:
۰۵۳ - ۰۷۳ -	- 9 \ A F

	MTO FOR TELECOM EQUIPMENT						
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	TE	MT	0003	D01

شم**اره صفحه: ۳** از ۶

#### **CONTENTS**

1.0	INTRODUCTION	. 4
2.0	GENERAL	.5
3.0	BILL OF MATERIAL LIST	. 5



### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



ره پیمان:	شمار
-----------	------

· 24 - · 74 - 9114

MTO FOR TELECOM EQUIPMENT								
پروژه	بسته کاری	صادر كننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	TE	MT	0003	D01	

شماره صفحه: ۴ از ۶

#### 1.0 INTRODUCTION

Binak oilfield in Bushehr province is a part of the southern oilfields of Iran, is located 20 km northwest of Genaveh city.

With the aim of increasing production of oil from Binak oilfield, an EPC/EPD Project has been defined by NIOC/NISOC and awarded to Petro Iran Development Company (PEDCO). Also PEDCO (as General Contractor) has assigned the EPC-packages of the Project to "Hirgan Energy - Design and Inspection" JV.

As a part of the Project, a New Gas Compressor Station (adjacent to existing Binak GCS) shall be constructed to gather of 15 MMSCFD (approx.) associated gases and compress & transfer them to Siahmakan GIS.

#### **GENERAL DEFINITION**

The following terms shall be used in this document.

CLIENT: National Iranian South Oilfields CLIENT (NISOC)

PROJECT: Binak Oilfield Development - Surface Fcilities; New

**Gas Compressor Station** 

EPD/EPC CONTRACTOR (GC): Petro Iran Development Company (PEDCO)

EPC CONTRACTOR: Joint Venture of : Hirgan Energy – Design & Inspection

(D&I) Companies

VENDOR: The firm or person who will fabricate the equipment or

material.

EXECUTOR: Executor is the party which carries out all or part of

construction and/or commissioning for the project.

THIRD PARTY INSPECTOR (TPI): The firm appointed by EPD/EPC CONTRACTOR (GC)

and approved by CLIENT (in writing) for the inspection

of goods.

SHALL: Is used where a provision is mandatory.

SHOULD: Is used where a provision is advisory only.

WILL: Is normally used in connection with the action by

CLIENT rather than by an EPC/EPD CONTRACTOR,

supplier or VENDOR.

MAY: Is used where a provision is completely discretionary.



## احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



	شماره پیمان:
۰۵۳ - ۲۷۰ -	- 9114

	MTO FOR TELECOM EQUIPMENT						
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	TE	MT	0003	D01

شم**اره صفحه:** ۵ از ۶

#### 2.0 GENERAL

- This document presents the item material requisitions for Contractor's use as appropriate.
- This material requisition covers the requirements for the design, manufacturing, testing and supply of **Telephone & Hotline Set** as listed below.

The supplier shall supply Telephone System. The supplier shall include in the supply, all other equipment/devices/items not listed in the following, but necessary for a good design and a safe operation, taking into account process data and installation conditions such as area classification and climatic conditions.

The grade of shop assembly of the equipment/devices/items supplied shall be at maximum extent to facilitate site erection and pre-commissioning activities.

#### 3.0 BILL OF MATERIAL LIST

Item	Description	Design QTY.	Unit	Remark
1	Analogue extension line :20 Line analogue Extension (Main PABX is Alcatel band That installed in TE Room)	1	Set	Extension of Exist ALCATEL PABX at Telecom building
2	License + Upgrade software of Exist PABX At CGS (if required)	1	Set	
3	3 Bokht , 50 Pairs MDF/IDF Terminal 0.6 mm(building side) +50 pair 0.8 mm filed side	2	Set	For both side
4	Weatherproof Telephone set, IP 65, with keypad and handset + Combined beacon& sounder	4	Set	For outdoor of Electrical Building + CGS Area
5	<b>Explosion-Proof</b> , IP65 Telephone, EEX e -IIB T3 II2 GD, Telephone with handset keypad + EX Combined beacon& sounder	2	Set	
6	H.D.G Telephone Kiosk, 25dB Decrease of noise	6	Set	
7	2.5 Meter H.D.G Pole	7	Set	





# احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

شماره پیمان:

۰۵۳ –	۰۷۳ –	9114	

	MTO FOR TELECOM EQUIPMENT						l	
پروژه	بسته کاری	صادر كننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	l
BK	GCS	PEDCO	120	TE	MT	0003	D01	

شماره صفحه: ۶ از ۶

8	EX Telephone Junction Box (10x10 cm) with 5 Pair Terminal 0.8 mm, , IP 65 , Metallic Body+ 3xM20 Gland	2	Set	
9	Weather Proof Telephone Junction Box (10x10 cm) with 5 Pair Terminal 0.8 mm, , IP 65 , Metallic Body+ 3xM20 Gland	7	Set	
10	EX Telephone Junction Box (10x10 cm) with 2 No Terminal 3x2.5 mm2, , IP 65 , Metallic Body+3xM20 Gland	2	Set	JB For flasher
11	WP Telephone Junction Box (10x10 cm) with 2 Terminal 3x2.5 mm2, , IP 65 , Metallic Body+3xM20 Gland	7	Set	JB For flasher
12	Hotline Telephone Set + Red Kiosk +IP 65 Red Color without keypad	3	Set	
13	Telephone Cable, 50 pair 0.8 mm, CFC Type, Armored	60	Meter	
14	Telephone Cable, 5 pair 0.8 mm , CFC Type , Armored , LS Type	2600	Meter	
15	Power Cable , 3x2.5 mm2 , Armored	1600	Meter	For flash light of telephone set
16	Indoor digital telephone set , Desk mounted Compatible with Alcatel telephone set	15	Set	For CCR and switchgear room
17	RJ 11 Telephone Socket , Flush Mounted	14	Set	For CCR
18	2 Pair 0.6 mm Indoor telephone Cable , LSZH	400	Meter	For CCR

Telephone line in CGS Will be connected to New Telephone MDF of new Control building and then routed to MDF of Exist PABX at Telecom room via 50 pair 0.6 CU/PVC/SWA telephone cable.