

### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره صفحه: ۱ از ۱۱

شماره پیمان:

۹۱۸۴ – ۲۷۰ – ۲۵۰

پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه
BK	GCS	PEDCO	120	ME	SP	0009	D01

## طرح نگهداشت و افزایش تولید ۲۷ مخزن

### SPECIFICATION FOR OVERHEAD TRAVELING CRANES

نگهداشت و افزایش تولید میدان نفتی بینک

D01	OCT. 2022	AFD	M.Asgharnejad	M.Fakharian	M.Mehrshad		
D00	AUG. 2021	IFC	M.Asgharnejad	M.Fakharian	Sh.Ghalikar		
Rev.	Date	Purpose of Issue/Status	Prepared by:	Checked by:	Approved by:	Client Approval	
Class: 2		Client Doc Number: F07-708824					

Client Doc. Number: F0Z-708824

Status: IDC: Inter-Discipline Check IFI: Issued For Information

AB-R: As-Built for Client Review AFP: Approved For Purchase

AB-A: As-Built –Approved
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction



.04 - .74 - 1184

### نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض

### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



پیمان:	شماره
--------	-------

SPECIFICATION FOR OVERHEAD TRAVELING CRANES

 نوع مدر ک
 نوع مدر ک
 رشته سریال
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 ME
 SP
 0009
 D01

شماره صفحه: ۲ از ۱۱

#### **REVISION RECORD SHEET**

PAGE	D00	D01	D02	D03	D04
1	Х	X			
2	Х	Χ			
3	Х				
4	X				
5	X				
6	Х				
7	Χ				
8	X				
9	X				
10	Х				
11	Х				
12					
13					
14					
15					
16					
17					
18	ļ				
19	ļ				
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39	ļ				
40	ļ				
41	ļ				
42					
43	ļ				
44	ļ				
45	ļ				
46	ļ				
47	ļ				
48					
49					
50					
51					
52					
53					
54					
55					

PAGE	D00	D01	D02	D03	D04
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95	1	1	1		
96					
97					
98	<u> </u>		<u> </u>		
99	1		1		
	<del>                                     </del>	<del>                                     </del>	<del>                                     </del>		
100	1	1	1		
101	<b> </b>		-		
102	<del>                                     </del>	<del>                                     </del>	<del>                                     </del>		
103	<b> </b>	1	-		
104			<u> </u>		
105	ļ		ļ		
106	ļ		ļ		
107	ļ				
108					
109					
110					



## احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

 $\textbf{.} \Delta \textbf{r} - \textbf{.} \textbf{V} \textbf{r} - \textbf{9} \textbf{1} \Delta \textbf{f}$ 

SPECIFICATION FOR OVERHEAD TRAVELING CRANES									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدر ک	سر يال	نسخه		
BK	GCS	PEDCO	120	ME	SP	0009	D01		

شماره صفحه: ۳ از ۱۱

### **CONTENTS**

1.0	INTRODUCTION	4
	SCOPE	
	NORMATIVE REFERENCES	
4.0	ORDER OF PRECEDENCE	7
5.0	TECHNICAL SPECIFICATION	8



### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

.04 - . 14 - 4114

SPECIFICATION FOR OVERHEAD TRAVELING CRANES								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه	
BK	GCS	PEDCO	120	ME	SP	0009	D01	

شماره صفحه: ۴ از ۱۱

#### 1.0 INTRODUCTION

Binak oilfield in Bushehr province is a part of the southern oilfields of Iran, is located 20 km northwest of Genaveh city.

With the aim of increasing production of oil from Binak oilfield, an EPC/EPD Project has been defined by NIOC/NISOC and awarded to Petro Iran Development Company (PEDCO). Also PEDCO (as General Contractor) has assigned the EPC-packages of the Project to "Hirgan Energy - Design and Inspection" JV.

As a part of the Project, a New Gas Compressor Station (adjacent to existing Binak GCS) shall be constructed to gather of 15 MMSCFD (approx.) associated gases and compress & transfer them to Siahmakan GIS.

#### **GENERAL DEFINITION**

The following terms shall be used in this document.

CLIENT: National Iranian South Oilfields Company (NISOC)

PROJECT: Binak Oilfield Development – Surface Fcilities; New

Gas Compressor Station

GENERAL CONTRACTOR (GC): Petro Iran Development Company (PEDCO)

EPC CONTRACTOR: Joint Venture of : Hirgan Energy - Design &

Inspection(D&I) Companies

VENDOR: The firm or person who will fabricate the equipment or

material.

EXECUTOR: Executor is the party which carries out all or part of

construction and/or commissioning for the project.

THIRD PARTY INSPECTOR (TPI): The firm appointed by EPD/EPC CONTRACTOR(GC)

and approved by CLIENT (in writing) for the inspection

of goods.



### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

.04 - .74 - 9174

SPECIFICATION FOR OVERHEAD TRAVELING CRANES								
پروژه	بسته کاری	صادركننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه	
BK	GCS	PEDCO	120	ME	SP	0009	D01	

شماره صفحه: ۵ از ۱۱

SHALL: Is used where a provision is mandatory.

SHOULD: Is used where a provision is advisory only.

WILL: Is normally used in connection with the action by Client

rather than by an EPC/EPD CONTRACTOR, supplier

or VENDOR.

MAY: Is used where a provision is completely discretionary.

#### 2.0 SCOPE

This specification outlines the general requirements for the supply of Electrical Motor Driven Overhead Cranes and is intended to supplement the Iranian Petroleum Standard IPS-M-GN-350(2), "Material and Equipment Standard for Overhead and Gantry Cranes", issued Nov. 2008. Works of this section consisting of the design, supply, fabrication, testing, preparation for shipment and guarantee, transportation and installation of electrical motor driven overhead travelling cranes includes but not limited to:

All material necessary for complete installation of the above-mentioned equipment.

- Crane end trucks and hoist runways and runway stops and supporting steel for runway rails. Crane runways shall be proposed and priced as an option (including all of necessary works as erection, welding ...).
- Crane bridges with travel mechanism and drive.
- Electrical parts
- Bumper stop (for trolley and bridge), rails, and fastener.
- All interconnecting cables (power/control) inside the package including festoon cable and relevant fastening facilities, isolating switches including relevant cable gland (battery limit of supply will be the mentioned isolator switch).
- Controls complete with remote controller and safe interlocks.
- Spare parts for pre commissioning, commissioning and two years operation according to vendor recommendation.



# نگهداشت و افزایش تولید میدان نفتی بینک

### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



پیمان:	شماره
--------	-------

.04 - .14 - 4146

SPECIFICATION FOR OVERHEAD TRAVELING CRANES									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه		
BK	GCS	PEDCO	120	MF	SP	0009	D01		

شماره صفحه: ۶ از ۱۱

- One set of special tools required for the maintenance and repairs for cranes.
- Name Plate.
- Earth Connections.

Areas which shall be equipped with overhead cranes are defined and specified in the project's "Access Philosophy".

EPC contractor is responsible for engineering, procurement, installation and commissioning of overhead cranes, wherever they are required within scope of the project at his own expense.

#### 3.0 NORMATIVE REFERENCES

The latest edition of following codes & standards are applicable in this project (unless otherwise mentioned):

#### 3.1 **LOCAL CODES AND STANDARDS**

➤ IPS-M-GN-350(2)	Material and Equipment Standard for Overhead
	and Gantry Cranes.
➢ BS 466	Specification for power driven overhead
	traveling cranes, semi-goliath and goliath cranes for
	general use.
> IPS-E-EL-100	Engineering Standard for Electrical System Design.
➤ IPS-M-EL-161(2) Items.	Material and Equipment Standard for Electrical

#### 3.2 **INTERNATIONAL CODES AND STANDARDS**

> ASTM All related parts.

ASME B30.2 Overhead and Gantry Crane.

Stress Calculations & Design of



### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

.04 - . 14 - 4114

SPECIFICATION FOR OVERHEAD TRAVELING CRANES								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه	
BK	GCS	PEDCO	120	ME	SP	0009	D01	

شماره صفحه: ۷ از ۱۱

> ISO 8306

Over Head Traveling Cranes and Portal Bridge-Tolerances for Cranes and Trucks.

Mechanisms.

#### 3.3 THE PROJECT DOCUMENTS

•	BK-GNRAL-PEDCO-000-PR-DB-0001	Process Basis of Design
•	BK- GNRAL -PEDCO -000-PR-DC-0001	Process Design Criteria
•	BK- GNRAL - PEDCO -000-EL-DC-0001	Electrical System Design Criteria
•	BK- GNRAL - PEDCO -000-EL-SP-0010	Specification For LV Electro Motors
•	BK- GNRAL - PEDCO -000-PI-SP-0006	Specification For Painting
•	BK- GNRAL - PEDCO -000-EL-SP-0017	Specification For MV Electro Motors
•	BK- GNRAL - PEDCO -000-SA-SP-0002	Specification For Hazardous  Area Classification

#### 3.4 ENVIRONMENTAL DATA

Refer to "Process Basis of Design; Doc. No. BK-GNRAL-PEDCO-000-PR-DB-0001".

#### 4.0 ORDER OF PRECEDENCE

In case of conflict between requirements specified herein and the requirements of any other referenced document, the most Approved stringent requirements of below listed items shall be considered

Purchase order



### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

٠۵٣ - ٠٧٣ - ٩١٨۴

SPECIFICATION FOR OVERHEAD TRAVELING CRANES								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه	
BK	GCS	PEDCO	120	ME	SP	0009	D01	

شماره صفحه : ۸ از ۱۱

- Material Requisition
- Data sheets
- This specification
- Drawings and other reference project specifications
- IPS standards
- International codes and standards

When the terms "Authorized", "Authorization", "Approval" or "Approved" are used in this specification, it shall mean authorization or approval from Client.

#### 5.0 TECHNICAL SPECIFICATION

#### **Acceptability Criteria**

Vendor shall not offer prototype design or a design with less than 2 years of successful operation in similar service.

A reference equipment/ Client list shall be submitted together with proposal. The Vendor may offer alternative designs for Client's consideration and approval.

Obviously the proposed equipment should have similar performances and the supplier will guarantee them.

#### **Deviations**

No deviations from project specifications, this general specification are allowed, without prior written approval of the Client.

#### **Guidelines**

Sub. (Substitution): The IPS standard clause is deleted and replaced by the new clause.

**Del.** (**Deletion**): The IPS standard clause is deleted without any replacement.

Add. (Addition): A new clause with a new number is added.



## احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



SPECIFICATION FOR OVERHEAD TRAVELING CRANES									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه		
BK	GCS	PEDCO	120	ME	SP	0009	D01		

شماره صفحه: ۹ از ۱۱

**Mod.** (**Modification**): Part of the IPS standard clause is modified, and/or a new description and/or condition is added to that clause.

### **AMENDMENT TO IPS-M-GN-350(2)**

### 5. DESIGN, CONSTRUCTION AND INSTALLATION

### 5.1 Design, Construction and Installation (Add.)

#### 5.1.5 (Add.)

Elevation of crane installation shall such that the truck loading/unloading will be performed easily. Height from crane hook to finish floor level shall not be less than following:

Truck (Bogie) height + Highest package height + 1.5m Vertical free board.

#### 5.9 Brakes (Add.)

#### 5.9.1 (Add.)

Brakes shall be DC Electromagnetic and Fail-Safe type.

#### 5.10 Electrical (Mod.)

Electrical motors shall be complied with the project specifications mentioned in References.

#### 5.10.1 (Add.)

The cranes, including all electrical and mechanical parts shall be suitable for installation at area classifications that has been mentioned in related data sheets. The motor and all electrical and control panels of cranes when installed in hazardous area shall be selected explosion proof (Exd for zone 1 and Exe for zone 2) and also related wheels shall be anti-spark type.

#### 5.10.2 (Add.)

The protection of cranes electro motors shall be according to NISOC- E-EL-100(1) Clause 7.5.

#### 5.10.3 (Add.)

All overhead cranes and associated metal structures and equipment shall be suitably connected to the main earthing network of the plant. The crane wheels shall not be used as means of earthing.



### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

۹۱۸۴ - ۲۷۰ - ۲۵۰

SPECIFICATION FOR OVERHEAD TRAVELING CRANES							
پروژه	بسته کاری	صادركننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه
BK	GCS	PEDCO	120	ME	SP	0009	D01

شماره صفحه: ۱۰ از ۱۱

#### 5.10.4 (Add.)

The cables for crane bridge and bridge traveling electro motors shall be selected from festoon type.

#### 5.14 Painting (Sub.)

Surface preparation and painting to be done according to manufacturer standard, client approval on painting system to be taken by manufacturer.

#### 5.16 Site Condition (Add.)

Site condition to be considered according to "BK- GNRAL -PEDCO -000-PR-DC-0001". The equipment shall be designed for the conditions of temperatures, humidity, airborne salt and dust prevailing at site.

#### 5.17 Travelling (Add.)

The crane shall travel the length and width of the shelter as specified in relevant data sheet.

#### 5.18 Material (Add.)

The materials of construction shall be in accordance with applicable ASTM specifications or other approved standards and shall be of suitable grade and quality for required applications. All materials necessary for the proper installation and protection of the equipment shall be included. Supplier shall submit the material certificates for major load holding components of the crane.

#### 6.0 Inspection, Testing and Maintenance

#### 6.2 Testing

#### 6.2.3 (Add.)

The cranes shall be completely assembled in the shop. All motors, controls and machinery shall be connected, and all machinery on the crane shall be operated under its own power at rated voltage and the volts, amperes and watts recorded for each operation.

Electrical circuits and interlocks shall be tested for correct operation and sequence. Crane shall be tested for satisfactory operation motions.



### احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

۹۱۸۴ - ۲۷۰ - ۲۵۰

SPECIFICATION FOR OVERHEAD TRAVELING CRANES								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدر ک	سريال	نسخه	
BK	GCS	PEDCO	120	ME	SP	0009	D01	

شماره صفحه: ۱۱ از ۱۱

#### 6.3 Maintenance

### 6.3.1 (Add.)

The crane shall be designed with facilities for easy inspection and maintenance. Filling and drain plugs on gearboxes shall be easily accessible, and to be provided with the necessary means to avoid spillage.