

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک فعالیت‌های رو زمینی در بسته‌های کاری تحت‌الارض ساخت موقعیت چاه، تأسیسات سرچاهی، خطوط جریانی مربوط به موقعیت W028							 	
	MTO FOR CIVIL WORKS - W028								
شماره پیمان: ۰۵۳ - ۰۷۳ - ۹۱۸۴	پروژه BK	بسته کاری W028	صادرکننده PEDCO	تسهیلات 110	رشته CV	نوع مدرک MT	سریال 0001	نسخه D02	شماره صفحه: ۱ از ۴

طرح نگهداشت و افزایش تولید ۲۷ مخزن

MTO FOR CIVIL WORKS - W028

نگهداشت و افزایش تولید میدان نفتی بینک

D02	DEC.2022	FI	R.Berlouie	M.Fakharian	M.Mehrshad	
D01	JUL.2022	IFI	R.Berlouie	M.Fakharian	M.Mehrshad	
D00	MAY.2022	IFI	R.Berlouie	M.Fakharian	M.Mehrshad	
Rev.	Date	Purpose of Issue / Status	Prepared by:	Checked by:	Approved by:	CLIENT Approval

Class: 3

CLIENT Doc. Number: F8Z-707551

status:

IDC: Inter-Discipline Check

IFC: Issued For Comment

IFA: Issued For Approval

AFD: Approved For Design

AFC: Approved For Construction

AFP: Approved For Purchase

AFQ: Approved For Quotation

IFI: Issued For Information

AB-R: As-Built for CLIENT Review

AB-A: As-Built -Approved

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک فعالیت‌های رو زمینی در بسته‌های کاری تحت‌الارض ساخت موقعیت چاه، تأسیسات سرچاهی، خطوط جریانی مربوط به موقعیت W028							 
	MTO FOR CIVIL WORKS - W028							
	شماره پیمان: ۰۵۳ - ۰۷۳ - ۹۱۸۴	پروژه BK	بسته کاری W028	صادرکننده PEDCO	تسهیلات 110	رشته CV	نوع مدرک MT	
شماره صفحه: ۲ از ۴								

REVISION RECORD SHEET

Page	D00	D01	D02	D03	D04	Page	D00	D01	D02	D03	D04
1	X	X	X			65					
2	X	X				66					
3	X	X				67					
4	X	X				68					
5						69					
6						70					
7						71					
8						72					
9						73					
10						74					
11						75					
12						76					
13						77					
14						78					
15						79					
16						80					
17						81					
18						82					
19						83					
20						84					
21						85					
22						86					
23						87					
24						88					
25						89					
26						90					
27						91					
28						92					
29						93					
30						94					
31						95					
32						96					
33						97					
34						98					
35						99					
36						100					
37						101					
38						102					
39						103					
40						104					
41						105					
42						106					
43						107					
44						108					
45						109					
46						110					
47						111					
48						112					
49						113					
50						114					
51						115					
52						116					
53						117					
54						118					
55						119					
56						120					
57						121					
58						122					
59						123					
60						124					
61						125					
62						126					
63						127					
64						128					



NISOC

تکهداشت و افزایش تولید میدان نفتی بینک
فعالیت‌های رو زمینی در بسته‌های کاری تحت الارض

ساخت موقعیت چاه، تأسیسات سرچاهی، خطوط جریانی
مربوط به موقعیت W028



MTO FOR CIVIL WORKS - W028

شماره پیمان:

۰۵۳ - ۰۷۳ - ۹۱۸۴

پروژه

بسته کاری

صادر کننده

تسهیلات

رشته

نوع مدرک

سر یال

نسخه

شماره صفحه: ۳ از ۴

BK

W028

PEDCO

110

CV

MT

0001

D02

MTO FOR CIVIL WORKS - W028

ITEM	DESCRIPTION	Materials													
		Excavation (m ³)	Embankment (m ³)	Grading (m ²)	Formwork (m ²)	Lean Concrete (m ³)	Concrete (m ³)	masonry wall with cement mortar (m ³)	stone masonry (fair face) (m ³)	Reinforcement (kg)	Iron Cast Plate	Joist (m ²)	Concrete Block (m ³)	Pipe (m.I)	
														6"	12"
1	Wellpad Foundation	1400	-	2610	560	270	760	384.7	94.6	24000	-	-	-	-	-
2	Gas Oil Tank Pad	75	-	175	35	20	55	-	-	2600	-	-	5.6	-	-
3	Septic Tank	140	-	70	16	12	12	-	-	4800	2	40	42	66	-
4	Coral Area	546.7	-	300.16	48.16	23.90	93.048	-	-	3819.6	-	-	-	-	-
5	Treatment Area	222.4	55.8	408.96	57.4	33.52	104.648	-	-	5168	-	-	-	-	-
6	Dewatering Unit	46.5	333.4	264	15	20.60	30	-	-	1200	-	-	-	-	-
7	OBM Waste Pit	254.6	44	165.75	43.7	11.859	57.625	-	-	2881.25	-	-	-	-	-
8	Mud Channel	237	2	162.4	35.28	11.44	20.52	-	-	820.8	-	-	50	-	-
9	Water Channel	2897.85	124.9	19.8	-	-	-	-	-	-	-	-	-	-	-
10	Oil Trap Pit	69.83	61.932	21.16	11.76	0.784	7.112	-	-	284.48	-	-	-	-	-
11	Culvert یک دهانه دو متری (۳دستگاه)	126	-	438.095	818.316	390.56	266.3979	-	-	4638	-	-	-	-	-
12	Conex Foundation	56	-	-	-	14	-	-	-	-	-	-	140	-	-
13	Heli Pad	18	-	144	-	9	13	-	-	880	-	-	141	-	-
14	Drain Pipe	27	3	-	-	-	-	-	-	-	-	-	-	-	30
	TOTAL	6116.88	625.03	4779.33	1640.62	817.66	1419.351	384.7	94.6	51092.13	2	40	378.6	66	30
	TOTAL+5%SURPLUS	6422.72	656.28	5018.29	1722.65	858.54	1490.318	403.935	99.33	53646.7365	2.1	42	397.53	69	32



NISOC

نگهداشت و افزایش تولید میدان نفتی بینک
فعالیت‌های رو زمینی در بسته‌های کاری تحت‌الارض

ساخت موقعیت چاه، تأسیسات سرچاهی، خطوط جریانی

مربوط به موقعیت W028

MTO FOR CIVIL WORKS - W028



شماره پیمان:

۰۵۳ - ۰۷۳ - ۹۱۸۴

پروژه

BK

بسته کاری

W028

صادرکننده

PEDCO

تسهیلات

110

رشته

CV

نوع مدرک

MT

سریال

0001

نسخه

D02

شماره صفحه: ۴ از ۴

MTO FOR CIVIL WORKS - W028

ITEM	DESCRIPTION	Materials					
		Excavation (m ³)	Embankment (m ³)	Grading (m ²)	Geomembrane (m ²)	SubBase (m ³)	Gravel (m ³)
1	Waste Pit + Access Road around	475	4772	2355	1866.8	246.6	-
2	Burn Pit	16125	112	2827.43	-	-	-
3	Water Pool	1320	32	260	934	-	-
4	Access Road (To location, To BurnPit, To HeliPad)	7102	2956	5802	-	870.3	-
5	Well Location	19078	8029	11200	-	-	430.7
6	Diversion Channel	456	-	-	-	-	-
	TOTAL	44556	15901	22444	2801	1117	431
	TOTAL+5%SURPLUS	46783.8	16696	23567	2941	1173	452