

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک							 	
	PROCESS DATA SHEETS FOR GLYCOL TRANSFER PUMPS								
شماره پیمان:	پروژه	بسته کاری	صادر کننده	تجهیزات	رشته	نوع مدرک	سریال	نسخه	شماره صفحه: 1 از 3
053 - 073 - 9184	BK	GCS	PEDCO	120	PR	DT	0021	D04	

طرح نگهداشت و افزایش تولید 27 مخزن

PROCESS DATA SHEETS FOR GLYCOL TRANSFER PUMPS

نگهداشت و افزایش تولید میدان نفتی بینک

D04	JAN.2023	AFC	M.Aryafar	M.Fakharian	M.Mehrshad	
D03	OCT.2022	AFC	M.Aryafar	M.Fakharian	M.Mehrshad	
D02	AUG.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D01	FEB.2022	IFC	M.Aryafar	M.Fakharian	M.Mehrshad	
D00	NOV.2021	IFC	M.Aryafar	M.Fakharian	M.Mehrshad	
Rev.	Date	Purpose of Issue / Status	Prepared by:	Checked by:	Approved by:	CLIENT Approval
Class: 1		CLIENT Doc. Number: F0Z-708765				
status: IDC: Inter-Discipline Check IFC: Issued For Comment IFA: Issued For Approval AFD: Approved For Design AFC: Approved For Construction AFP: Approved For Purchase AFQ: Approved For Quotation IFI: Issued For Information AB-R: As-Built for CLIENT Review AB-A: As-Built -Approved						



NISOC

نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



PROCESS DATA SHEETS FOR GLYCOL TRANSFER PUMPS

شماره پیمان:	پروژه	بسته کاری	صادر کننده	تسهیلات	رشته	نوع مدرک	سریال	نسخه	شماره صفحه: 2 از 3
053 - 073 - 9184	BK	GCS	PEDCO	120	PR	DT	0021	D04	

REVISION RECORD SHEET

Page	D00	D01	D02	D03	D04	Page	D00	D01	D02	D03	D04
1	X	X	X			65					
2	X	X	X			66					
3	X	X	X			67					
4						68					
5						69					
6						70					
7						71					
8						72					
9						73					
10						74					
11						75					
12						76					
13						77					
14						78					
15						79					
16						80					
17						81					
18						82					
19						83					
20						84					
21						85					
22						86					
23						87					
24						88					
25						89					
26						90					
27						91					
28						92					
29						93					
30						94					
31						95					
32						96					
33						97					
34						98					
35						99					
36						100					
37						101					
38						102					
39						103					
40						104					
41						105					
42						106					
43						107					
44						108					
45						109					
46						110					
47						111					
48						112					
49						113					
50						114					
51						115					
52						116					
53						117					
54						118					
55						119					
56						120					
57						121					
58						122					
59						123					
60						124					
61						125					
62						126					
63						127					
64						128					



NISOC

تکداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



PROCESS DATA SHEETS FOR GLYCOL TRANSFER PUMPS

شماره پیمان:

053 - 073 - 9184

پروژه

بسته کاری

صادر کننده

تجهیزات

رشته

نوع مدرک

سریال

نسخه

شماره صفحه: 3 از 3

BK

GCS

PEDCO

120

PR

DT

0021

D04

1	Note		Rev
2	GENERAL DATA		
3	Type		
4	☒ Centrifugal ☐ Positive displacement		
5	Centrifugal ☐ Horizontal ☐ Vertical		
6	Positive displacement ☐ Reciprocating ☐ Rotary ☐ Metering		
7	Item P-2103 A/B	No. of Main/Stand By Units	1 / 1
8	Service Glycol Transfer Pump	Installation (Indoor-Outdoor-Other)	Outdoor
9	Operation ☐ Continuous ☒ Discontinuous ☐ Parallel ☒ Single		
10	Type of Driver	Electrical Motor	
11	CHARACTERISTICS OF HANDLED LIQUID		
12	Type of Handled Liquid	TEG	
13	Pumping Temp.e (Min./Max.)	°C	5 / 50
14	Density at Min. / Norm / Max. Temp.	kg/m³	/ 1115 /
15	Viscosity At Min. Temp.	cP	85.86
16	Vapour Pressure at Max. Pumping Temp.	bara	0
17	Freezing Point / Pour Point	°C	-4.3
18	Dissolved Gas	Yes-No	No
19	Corrosive / Erosive / Hazardous Agents / Flammable	Yes-No	No / No / Yes / No
20	Suspended solids (Type / Dimen. / Vol.%)	mm	N/A / N/A / N/A
21	OPERATING CONDITIONS		
22	Suction Pressure (Min/ Max.)	bara	0.07 / 0.49
23	Discharge Pressure at Rated Capacity	bara	2.07
24	Differential Pressure at Rated Capacity	bar	2.00
25	Capacity (Min. / Normal / Rated)	m³/hr	/ 5 / 5.5
26	Head at Rated Capacity	m	18.3
27	NPSH Available	m	9.9
28	Max Allowable Pressure at Shut-Off	bara	3.10
29	Hydraulic Power	kW	0.3
30	Reacceleration	Yes-No	No
31	Automatic Start-Up	Yes-No	No
32	Start-Up with Delivery Valve ☒ Open ☐ Close		
33	Flow Controlled By ☐ Pressure Controller ☐ Level Controller ☐ Flow Controller ☒ Other		
34	DESIGN CONDITIONS		
35	Design Temperature: Min / Max	°C	5 / 85
36	Design Pressure	bara	3.10
37	MECHANICAL DATA		
38	Contamination of Liquid Handled Allowed	Yes-No	Yes
39	Air Entrainment Allowed	Yes-No	Yes
40	Leaks Allowed	Yes-No	Yes
41	Antifreezing Protection	Yes-No	No
42	Suction Line: Diameter	in	2"
43	Discharge Line: Diameter	in	2"
44	Mat. in Contact with Liq. Handled (Min.)	API 610, Cl. S-8 Note2	
45	Note		
46	1	Deleted	
47	2	(Vendor to confirm)	
48	3	Deleted	
49	4	API Plan 11 shall be considered. (Vendor to confirm)	
50	5	Margin between NPSHA and NPSHR shall not be less than 1 m.	
51	6	Refer to hazardous area classification layout, all instrumentation and electrical devices shall be suitable for: ZONE 2 & Gas group IIA, Temperature class T4	
52	7	For P&ID refer to BK-GCS-PEDCO-120-PR-PI-0014	
53	8	Minimum Design Metal Tem (MDMT)= 5	
54	9	Applicable standard: ISO 5199 and IPS-M-PM-115	

This document is the sole property of NISOC and all information contained herein may neither be reproduced, used, disclosed, transmitted nor in any way made public without permission of the CLIENT.