



NISOC

نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



PROCESS DATA SHEETS FOR GLYCOL DRAIN PUMP

شماره پیمان:

۰۵۳ - ۰۷۳ - ۹۱۸۴

پروژه

BK

بسته کاری

GCS

صادر کننده

PEDCO

تسهیلات

120

رشته

PR

نوع مدرک

DT

سریال

0028

نسخه

D04

شماره صفحه: ۱ از ۳

طرح نگهداشت و افزایش تولید ۲۷ مخزن

PROCESS DATA SHEETS FOR GLYCOL DRAIN PUMP

نگهداشت و افزایش تولید میدان نفتی بینک

D04	JAN.2023	AFC	M.Aryafar	M.Fakharian	M.Mehrshad	
D03	OCT.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D02	AUG.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D01	FEB.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D00	NOV.2021	IFC	M.Aryafar	M.Fakharian	M.Mehrshad	
Rev.	Date	Purpose of Issue / Status	Prepared by:	Checked by:	Approved by:	CLIENT Approval

Class: 1

CLIENT Doc. Number:

F0Z-708772

status:

IDC: Inter-Discipline Check

IFC: Issued For Comment

IFA: Issued For Approval

AFD: Approved For Design

AFC: Approved For Construction

AFP: Approved For Purchase

AFQ: Approved For Quotation

IFI: Issued For Information

AB-R: As-Built for CLIENT Review

AB-A: As-Built -Approved



NISOC

نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



PROCESS DATA SHEETS FOR GLYCOL DRAIN PUMP

شماره پیمان:

۰۵۳ - ۰۷۳ - ۹۱۸۴

پروژه

BK

بسته کاری

GCS

صادر کننده

PEDCO

تسهیلات

120

رشته

PR

نوع مدرک

DT

سریال

0028

نسخه

D04

شماره صفحه: ۲ از ۳

REVISION RECORD SHEET

Page	D00	D01	D02	D03	D04
1	X	X			
2	X	X			
3	X	X		X	
4					
5					
6					
7					
8					
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					

Page	D00	D01	D02	D03	D04
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					
101					
102					
103					
104					
105					
106					
107					
108					
109					
110					
111					
112					
113					
114					
115					
116					
117					
118					
119					
120					
121					
122					
123					
124					
125					
126					
127					
128					



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



PROCESS DATA SHEETS FOR GLYCOL DRAIN PUMP

شماره پیمان:

• 03 - • 73 - 9184

یوژہ

کاری

صادر کنندہ

سهیلات

رشته

مذہب

نوع	
-----	--

سر یا

نسخه

--	--

شماره صفحه: ۳ از ۳

1	Note										Rev
2	GENERAL DATA										
3	Type										
4	☒ Centrifugal ☐ Positive displacement										
5	☒ Centrifugal ☐ Horizontal ☒ Vertical										
6	☒ Positive displacement ☐ Reciprocating ☐ Rotary ☐ Metering										
7	Item P-2104 No. of Main/Stand By Units 1 /0										
8	Service Glycol Drain Pump Installation (Indoor-Outdoor-Other) Outdoor										
9	Operation ☐ Continuous ☒ Discontinuous ☐ Parallel ☒ Single										
10	Type of Driver Electrical Motor										
11	CHARACTERISTICS OF HANDLED LIQUID										
12	Type of Handled Liquid TEG										
13	Pumping Temp.e (Min. / Normal / Max.) °C 5 / 50										
14	Density at Min. / Norm / Max. Temp. kg/m³ / 1115 /										
15	Viscosity At Min. / Max. Temp. cP 85.86 / 25.06										
16	Vapour Pressure at Max. Pumping Temp. bara 0										
17	Freezing Point / Pour Point °C -4.3										
18	Dissolved Gas Yes-No No										
19	Corrosive / Erosive / Hazardous Agents / Flammable Yes-No No / No / Yes / NO										
20	Suspended solids (Type / Dimen. / Vol.%) mm N/A / N/A / N/A										
21	OPERATING CONDITIONS										
22	Suction Pressure (Min/ Max.) barg 0.11 / 0.20										
23	Discharge Pressure at Rated Capacity barg 2										
24	Differential Pressure at Rated Capacity bar 2.00										
5	Capacity (Min. / Normal / Rated) m³/hr / 3 / 3.3 Note 1										
6	Head at Rated Capacity m 18.3										
7	NPSH Available m 10.4										
8	Max Allowable Pressure at Shut-Off barg 5.70										
9	Hydraulic Power kW 0.18										
10	Reacceleration Yes-No No										
11	Automatic Start-Up Yes-No No										
12	Start-Up with Delivery Valve ☒ Open ☐ Close										
13	Flow Controlled By ☐ Pressure Controller ☐ Level Controller ☐ Flow Controller ☒ Other										
14	DESIGN CONDITIONS										
15	Design Temperature: Min / Max °C 5 / 85										
16	Design Pressure barg 5.70										
17	MECHANICAL DATA										
18	Contamination of Liquid Handled Allowed Yes-No No										
19	Air Entrainment Allowed Yes-No No										
20	Leaks Allowed Yes-No Yes										
21	Antifreezing Protection Yes-No No										
22	Suction Line: Diameter -										
23	Discharge Line: Diameter 2"										
24	Mat. in Contact with Liq. Handled (Min.) (API 610, Cl. S-8) Note 3										

Note

26	1	Design (rated) flow rates is 110 % of normal flow rate.
27	2	Deleted
28	3	(Vendor to confirm)
29	4	API Plan 11 shall be considered. (Vendor to confirm)
30	5	Deleted
31	6	Refer to hazardous area classification layout, all instrumentation and electrical devices shall be suitable for: ZONE 1 & Gas group IIB, Temperature class T3
32	7	For P&ID refer to BK-GCS-PEDCO-120-PR-PI-0025
33	8	Minimum Design Metal Tem (MDMT)=5
34	9	Applicable standard: ISO 5199, IPS-M-PM-115 to be mentioned as note.

This document is the sole property of NISOC and all information contained herein may neither be reproduced, used, disclosed, transmitted nor in any way made public without permission of the CLIENT.