

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

· 24 - · 74 - 9114

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT								
CIRCUIT) STUDY REPORT								

پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	EL	RT	0001	D01

شماره صفحه: ۱ از ۸

طرح نگهداشت و افزایش تولید ۲۷ مخزن

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT CIRCUIT) STUDY REPORT

نگهداشت و افزایش تولید میدان نفتی بینک

Rev.	Date	Purpose of Issue/Status	Prepared by:	Checked by:	Approved by:	CLIENT Approval
D00	Jun. 2022	IFC	H.Shakiba	M.Fakharian	M.Mehrshad	
D01	Jan. 2023	IFA	H.Shakiba	M.Fakharian	M.Mehrshad	

Class:1 CLIENT Doc. Number: F0Z-709071

Status:

IDC: Inter-Discipline Check
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction
AFP: Approved For Purchase
AFQ: Approved For Quotation
IFI: Issued For Information
AB-R: As-Built for CLIENT Review

AB-A: As-Built -Approved



· ۵۳ - · ۷۳ - 9 1 1 4

نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT CIRCUIT) STUDY REPORT

 نسخه
 سریال
 نوع مدر ک
 رشته
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 EL
 RT
 0001
 D01

شماره صفحه: ۲ از ۸

REVISION RECORD SHEET

PAGE	D00	D01	D02	D03	D04
1	Х	Х			
2	Х	Х			
3	X				
4	X				
5	X	Χ			
6	X				
7	X				
8	X	X			
9					
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
^=					
38					
39					
40					
41					
42					
43 44	1				
45	-				
46 47					
	-				
48					
49 50	1				

PAGE	D00	D01	D02	D03	D04
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					



· 27 - · 77 - 9114

نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT CIRCUIT) STUDY REPORT

 CIRCOIT) STODY RELIGION

 نسخه
 سریال
 نوع مدرک
 رشته
 تسهیلات
 صادرکننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 EL
 RT
 0001
 D01

شماره صفحه: ۳ از ۸

CONTENTS

1.0	INTRODUCTION	4
2.0	SCOPE	
3.0	NORMATIVE REFERENCES	
3.1		
3.2	International Codes & Standard	5
3.3	Local Codes & Standards International Codes & Standard. The Project Documents.	5
4.0	PLANT MODEL	
5.0	STUDIED CONFIGURATION	6
5.1	Normal Configuration	6
5.2	Worst Case Configuration	6
5.3	EMERGENCY CONFIGURATION	7
6.0	LOAD FLOW STUDY	7
7.0	SHORT CIRCUIT ANALYSIS	7
8.0	MOTOR STARTING ANALYSIS	



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

· ۵۳ - · ۷۳ - 9114

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT									
CIRCUIT) STUDY REPORT									
222.	م تار کار م	21::5.21.2	ت مالادت	4" *	ندې در د کې	flss	نخد		

 نسخه
 سریال
 نوع مدرک
 رشته
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 EL
 RT
 0001
 D01

شم**اره صفحه: ۴** از ۸

1.0 INTRODUCTION

Binak oilfield in Bushehr province is a part of the southern oilfields of Iran, is located 20 km northwest of Genaveh city.

With the aim of increasing production of oil from Binak oilfield, an EPC/EPD Project has been defined by NIOC/NISOC and awarded to Petro Iran Development Company (PEDCO). Also PEDCO (as General Contractor) has assigned the EPC-packages of the Project to "Hirgan Energy - Design and Inspection" JV.

As a part of the Project, a New Gas Compressor Station (adjacent to existing Binak GCS) shall be constructed to gather of 15 MMSCFD (approx.) associated gases and compress & transfer them to Siahmakan GIS.

GENERAL DEFINITION

The following terms shall be used in this document.

CLIENT: National Iranian South Oilfields CLIENT (NISOC)

PROJECT: Binak Oilfield Development - Surface Fcilities; New

Gas Compressor Station

EPD/EPC CONTRACTOR (GC): Petro Iran Development Company (PEDCO)

EPC CONTRACTOR: Joint Venture of : Hirgan Energy – Design & Inspection

(D&I) Companies

VENDOR: The firm or person who will fabricate the equipment or

material.

EXECUTOR: Executor is the party which carries out all or part of

construction and/or commissioning for the project.

THIRD PARTY INSPECTOR (TPI): The firm appointed by EPD/EPC CONTRACTOR (GC)

and approved by CLIENT (in writing) for the inspection

of goods.

SHALL: Is used where a provision is mandatory.

SHOULD: Is used where a provision is advisory only.

WILL: Is normally used in connection with the action by

CLIENT rather than by an EPC/EPD CONTRACTOR,

supplier or VENDOR.

MAY: Is used where a provision is completely discretionary.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

· 24 - · 74 - 9114

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT CIRCUIT) STUDY REPORT									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه		

 نسخه
 سریال
 نوع مدر ک
 رشته
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 EL
 RT
 0001
 D01

شماره صفحه: ۵ از ۸

2.0 SCOPE

This document is prepared to report Load Flow, Motor Starting & Short Circuit Study in New Gas Compressor Station of Binak oilfield.

3.0 NORMATIVE REFERENCES

3.1 Local Codes & Standards

• IPS-E-EL-100 (1) Engineering Standard for Electrical System

3.2 International Codes & Standard

This document shall be shall be produced in accordance with the latest editions of the International Electro technical Commission (IEC) and BS standards



3.3 The Project Documents

•	BK-GNRAL-PEDCO-000-PR-DB-0001	Process Basis of Design
•	BK-GCS-PEDCO-120-EL-LI-0001	Electrical Load List
•	BK-GNRAL-PEDCO-000-EL-DC-0001	Electrical System Design Criteria
•	BK-GCS-PEDCO-120-EL-SL-0001	Overall single line diagram
•	BK-GCS-PEDCO-120-EL-SL-0003	Existent MV Switchgear Expansion Single
		Line Diagram
•	BK-GCS-PEDCO-120-EL-SL-0002	LV Switchgear/MCC Single Line Diagram
•	BK-GCS-PEDCO-120-EL-LI-0002	Electrical Power & Control Cable Schedule

4.0 PLANT MODEL

The model used for the calculations of the distribution network for Binak Oilfield Development gas compressor station units includes:

- The 11KV switchgear expansion fed by two 230/11 kV Transformers and 11KV motors.
- The new 0.4 KV switchgear installation fed by two 11/0.42 kV Transformers.
- Emergency bus bar fed by a 0.4 KV, 500 KW diesel generators



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

۰۵۳ - ۰۷۳ - ۹۱۸۴

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT
CIRCUIT) STUDY REPORT


پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	EL	RT	0001	D01

شم**اره صفحه:**۶ از ۸

5.0 STUDIED CONFIGURATION

5.1 Normal Configuration


In normal configuration bus-tie breaker is normally open, and each section is fed by its own transformer.



Normal Configuration

5.2 Worst Case Configuration

In the worst case condition, or also for maintenance purposes, one transformer can be out of service and whole load feed from the other transformer by closing the bus-tie breaker.



Worst Case Configuration



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

· 27 - · 77 - 9114

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT										
CIRCUIT) STUDY REPORT										
					_					


 نسخه
 سریال
 نوع مدر ک
 رشته
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 EL
 RT
 0001
 D01

شماره صفحه: ۷ از ۸

5.3 Emergency Configuration

In the emergency condition, all transformers are out of service and only emergency loads will be fed from the Diesel generator. The bus-tie breaker "C" is open in this configuration.



Emergency Configuration

6.0 LOAD FLOW STUDY

The load flow study calculates the active and reactive power flow and the bus voltages in different plant configurations. The main goals of the load flow studies are:

- To verify that no cable or transformer is overloaded.
- To check the bus voltages

Result of maximum short circuit currents is reported in Attachment 1, 2 & 3.

7.0 SHORT CIRCUIT ANALYSIS

At this stage, the maximum short circuit values are calculated in worst case operation to verify that the switchgear withstand capacity is higher than the maximum short circuit current. In this configuration the motor contribution for each bus is maximum.

Result of maximum short circuit currents is reported in Attachment 4.

Table below compares the results of the 3ph short circuit studies with the switchgear withstand capacity.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

1118 - 77. - 7D.

ELECTRICAL NETWORK (LOAD FLOW, MOTOR STARTING & SHORT					
CIRCUIT) STUDY REPORT					

پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	EL	RT	0001	D01

شم**اره صفحه:** ۸ از ۸



Voltage Level [kV]	Short Circuit Current [kA] max	Withstand Capacity [kA for 1s]
11	14.2	25
3.3	2.9	25
	26	50

All the switchgears are able to withstand the expected fault currents.

8.0 MOTOR STARTING ANALYSIS

At this stage, the motor starting analysis is considered for below configurations:

- In worst case configuration and when all of continues loads are connected and the 1250 kW 11 kV induction motor (Mtr2) starts with direct insertion, at the same voltage level.

Result of motor starting analysis is reported in Attachment 5.