



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

شماره پیمان:

· 24 - · 74 - 9114

	PMR FOR LOCAL CONTROL STATION (LCS)									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه			
BK	GCS	PEDCO	120	EL	MR	0010	D01			

شماره صفحه: ۱ از ۱۴

طرح نگهداشت و افزایش تولید ۲۷ مخزن

PMR FOR LOCAL CONTROL STATION (LCS)

نگهداشت و افزایش تولید میدان نفتی بینک

D00 Rev.	Jun. 2022 Date	IFI Purpose of Issue/Status	H.Shakiba Prepared by:	M.Fakharian Checked by:	M.Mehrshad Approved by:	Client Approval
D00	Jun. 2022	IFI	H.Shakiba	M.Fakharian	M.Mehrshad	
D01	Jun. 2023	FI	H.Shakiba	M.Fakharian	A.M.Mohseni	

Class:3 Client Doc. Number: F0Z-709345

Status:

IDC: Inter-Discipline Check
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction
AFP: Approved For Purchase
AFQ: Approved For Quotation
IFI: Issued For Information
AB-R: As-Built for Client Review
AB-A: As-Built –Approved



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

PMR FOR LOCAL CONTROL STATION (LCS)

· 24 - · 74 - 9114

	Time Toke 2007/2 001/11/01/ (200)								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه		
BK	GCS	PEDCO	120	EL	MR	0010	D01		

شماره صفحه: ۲ از ۱۴

REVISION RECORD SHEET

					REVISION
PAGE	D00	D01	D02	D03	D04
1	Х	Х			
2	Х	Х			
3	Х				
4	Х				
5	Х	Х			
6	Х	Х			
7	Х	Х			
8	Х				
9	Χ				
10	Х	Х			
11	Х				
12	Х	Х			
13	Х				
14	X				
15	X				
16	X				
17	X				
18	X				
19	X				
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					

DACE	D00	D01	D02	D03	D04
PAGE 51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86	<u> </u>				
	1				-
87	1				-
88	1		-		1
89	1		-		1
90	1				<u> </u>
91	1				<u> </u>
92	1				-
93	-				
94					ļ
95	1				ļ
96	ļ				
97					
98					
99					
100					





احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

شماره پیمان:

· 24 - · 74 - 9114


	PMR FOR LOCAL CONTROL STATION (LCS)									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه			
BK	GCS	PEDCO	120	EL	MR	0010	D01			

شماره صفحه: ۳ از ۱۴

CONTENTS

1.0	INTRODUCTION	4
2.0	GENERAL	5
3.0	REFERENCE / ATTACHED DOCUMENTS	5
4.0	SUBJECT OF THE SUPPLY	6
5.0	LIMITS OF SUPPLY	6
5.1	SCOPE OF SUPPLY	6
5.1.1	MAIN DESCRIPTION	6
5.1.2	Spare parts	7
5.2	EXCLUSIONS	7
5.3	BATTERY LIMITS	7
6.0	INSPECTION AND TESTS	7
7.0	VENDOR DOCUMENTATION REQUIREMENTS & SCHEDULE	7
8.0	UNIT RESPONSIBILITY	8
9.0	GUARANTEE AND WARRANTY	8
10.0	DEVIATION	9
11.0	PRICE BREAKDOWN	9
ATTAC	HMENT 1	10
11.1	LIST OF REFERENCE / APPLICABLE DOCUMENTS	10
ATTAC	HMENT 2	10
11.2	VENDOR DOCUMENTS MIN. REQUIREMENT	10
ATTAC	HMENT 3	13
11.3	DEVIATIONS / EXCEPTIONS TO JOB SPECIFICATION	13
ATTAC	HMENT 4	14
11.4	ALTERNATIVES TO JOB SPECIFICATION	14







شماره پیمان:

. 22 - . 12 - 417

	PMR FOR LOCAL CONTROL STATION (LCS)									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه			
BK	GCS	PEDCO	120	EL	MR	0010	D01			

شماره صفحه: ۴ از ۱۴

1.0 INTRODUCTION

Binak oilfield in Bushehr province is a part of the southern oilfields of Iran, is located 20 km northwest of Genaveh city.

With the aim of increasing production of oil from Binak oilfield, an EPC/EPD Project has been defined by NIOC/NISOC and awarded to Petro Iran Development Company (PEDCO). Also PEDCO (as General Contractor) has assigned the EPC-packages of the Project to "Hirgan Energy - Design and Inspection" JV.

As a part of the Project, a New Gas Compressor Station (adjacent to existing Binak GCS) shall be constructed to gather of 15 MMSCFD (approx.) associated gases and compress & transfer them to Siahmakan GIS.

GENERAL DEFINITION

The following terms shall be used in this document.

CLIENT: National Iranian South Oilfields Company (NISOC)

PROJECT: Binak Oilfield Development – Surface Facilities; New

Gas Compressor Station

EPD/EPC CONTRACTOR (GC): Petro Iran Development Company (PEDCO)

EPC CONTRACTOR: Joint Venture of : Hirgan Energy – Design & Inspection

(D&I) Companies

VENDOR: The firm or person who will fabricate the equipment or

material.

EXECUTOR: Executor is the party which carries out all or part of

construction and/or commissioning for the project.

THIRD PARTY INSPECTOR (TPI): The firm appointed by EPD/EPC CONTRACTOR (GC)

and approved by CLIENT (in writing) for the inspection

of goods.

SHALL: Is used where a provision is mandatory.

SHOULD: Is used where a provision is advisory only.

WILL: Is normally used in connection with the action by

CLIENT rather than by an EPC/EPD CONTRACTOR,

supplier or VENDOR.

MAY: Is used where a provision is completely discretionary.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



۰۵۳	_ •	٧٣	_	٩	۱۸۴	
٠ ω ۱		۲ ۱		٠,	1// 1	

	PMR FOR LOCAL CONTROL STATION (LCS)									
نسخه سریال نوع مدرک رشته تسهیلات صادرکننده بسته کاری پروژه										
BK	GCS	PEDCO	120	EL	MR	0010	D01			

شماره صفحه: ۵ از ۱۴

2.0 GENERAL

- This document presents the item material requisitions for Contractor's use as appropriate.
- This material requisition covers the requirements for the design, manufacturing, testing and supply of LCS as listed below. All equipment/devices/items shall conform to this requisition and all specifications which have been mentioned in attachment 1 of this material requisition.



• The vendor's supply shall include:

No.	Item	Description	Total QTY.
1	Local Control	Consist of Selector Switch, Local / off/ Remote	As per
ı	Station	Ammeter & Push Button & WP/Exd Type	MTO

3.0 REFERENCE / ATTACHED DOCUMENTS

- **a.** Specified documents in attachment 1 shall be considered as a part of this material Requisition.
- **b.** All codes and standards which have been referenced in above mentioned specs shall be considered.
- **c.** In case of any conflict between the contents of this document or any discrepancy between this document and other project documents or reference standards, this issue must be reported to the CLIENT. The final decision in this situation will be made by CLIENT.

d. Deviations

Any exceptions/clarifications to codes/standards and specifications listed in attachment 1 must be clearly stated in a separate dedicated section of the proposal in the format submitted in attachment 3.

The proposed deviations/comments list shall include as minimum:

- Reference for the involved specification, chapter and paragraph.
- Technical justification for the non-compliance.
- Detailed description of the proposed alternative.

If no exceptions or clarifications exist, either for the complete referenced document or an individual paragraph, the supplier shall be considered to be in full compliance with the relevant document.

The supplier may propose materials of equivalent or better quality compared to those indicated in the equipment data sheet. Even these cases shall be duly included/technically supported in the deviations/clarifications list.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

· 24 - · 74 - 9114

PMR FOR LOCAL CONTROL STATION (LCS)								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	1
BK	GCS	PEDCO	120	EL	MR	0010	D01	

شماره صفحه: ۶ از ۱۴

4.0 SUBJECT OF THE SUPPLY

The supplier shall supply LCS for Electrical Motors. The scope of supply is detailed at para. 5. The supplier shall include in the supply, all other equipment/devices/items not listed in the following, but necessary for a good design and a safe operation, taking into account process data and installation conditions such as area classification and climatic conditions.

The grade of shop assembly of the equipment/devices/items supplied shall be at maximum extent to facilitate site erection and pre-commissioning activities.

5.0 LIMITS OF SUPPLY

5.1 SCOPE OF SUPPLY

5.1.1 MAIN DESCRIPTION

LCS for electrical Motors according to "Data Sheets for Local Control Stations (LCS)" & "MTO for LCS" shall be considered.

The supplier shall assume overall responsibility for the design, manufacture, assembly, test and performance of all equipment/devices/items supplied as indicated in this requisition. This shall include, but not be limited to:

- Resolve engineering issues relating to equipment/devices/items within the scope of supply.
- Provide detailed design and documentation of all equipment/devices/items and components within the scope of supply in accordance with attachment 2 of this document.
- Provide all necessary information documents in order to allow the contractor to erect, install and verify the proposed equipment/devices/items.
- Implement a quality assurance plan
- The quality plan applied to the scope of supply shall include:
 - QA/QC organization and procedures that shall be submitted for approval.
 - Plan for HOLD points in the production process proposed to PURCHASER for witness or approval particular activities.
 - Production schedule indicating main quality manufacturing processes, inspection and tests.
 - Qualification of all personnel performing tests to be reviewed by the inspector
 - Supplier shall also provide the description of the following quality activities:





احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



۰۵۳ –	۰۷۳ –	9114
ω 1	, ,	* 17* 1

PMR FOR LOCAL CONTROL STATION (LCS)								l
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	l
BK	GCS	PEDCO	120	EL	MR	0010	D01	l

شماره صفحه: ۷ از ۱۴

- Sub suppliers products quality
- Quality check and identification of the materials and equipment entering in their manufacturing shop.
- · Calibration of test instruments and equipment
- Provide detailed specifications and data sheets.

5.1.2 SPARE PARTS

Following items shall be considered (supplied) and included in the bid documentation:

- Spare parts for commissioning and start-up; a qualified and complete list based on PROJECT SPARE PART SUPPLY PROCEDURE (Doc. No. E&D-QC-SP-1).
- Spare parts for two years operation; a qualified and complete list based on PROJECT SPARE PART SUPPLY PROCEDURE (Doc. No. E&D-QC-SP-1).
- Capital spare parts (as option / if any)

5.2 EXCLUSIONS

The following items are excluded by the supplier scope of supply and will be provided by purchaser:

5.3 BATTERY LIMITS

The battery limits are summarized as follows:

Not Applicable

6.0 INSPECTION AND TESTS

The equipment shall be inspected and tested in accordance with the quality control plan issued by the supplier and approved by the PURCHASER before the award of the order. The QC plan shall at least be according to the PROJECT ITP PROCEDURE (Doc. No. ICE-EID-MI-SP01-Rev01 & ICE-EID-MI-SP02-REV-01) and data sheets (if any).



The supplier shall in any case conduct all the tests required by contractual documents, specifications, codes and standards, manufacturer standard quality system and keep the relevant documentation.

7.0 VENDOR DOCUMENTATION REQUIREMENTS & SCHEDULE

Vendor document shall be according to attachment 2 of this document.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



پیمان:	شماره

, ω		,,ω			. vc
۰۵۳	-	٠ ٧ ١	_ `	() /	۸۲

PMR FOR LOCAL CONTROL STATION (LCS)							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	EL	MR	0010	D01

شماره صفحه: ۸ از ۱۴

- All documents, preliminary or final, are to be stamped and signed by the supplier.
- Failure in dispatch of the required documents shall cause the supply to be considered as unfulfilled.
- PURCHASER's approval does not relieve vendor, in any way, from his obligation to fulfill the requirements of the purchase order documents.
- All vendor drawings and documents shall be in English language.

All drawings and documents are to be identified as per clause 1 "GENERAL DEFINITION"

8.0 UNIT RESPONSIBILITY

VENDOR shall be responsible for the design, engineering, co-ordination, supply, delivery, testing, final check-out and satisfactory operation of the equipment/devices/items. The engineering coordination also includes responsibility for handing and expediting drawings.

Also VENDOR shall be responsible for ensuring that all relevant information and documentation is passed on the sub-suppliers.

9.0 GUARANTEE AND WARRANTY

All material and Equipment/Devices/Items in VENDOR's scope of work/supply shall be guaranteed by VENDOR.

The guarantee period shall be eighteen (18) months from the date of delivery or twelve (12) months from the installation date of each equipment/packages at site

VENDOR shall guarantee the performance of supplied items (if any).

VENDOR shall guarantee that the Equipment/Device/Item is suitable for the operating conditions herein specified, and that all materials and components are free from any defects; verifications of all calculations are in VENDOR's responsibility.

VENDOR shall unconditionally guarantee the materials and workmanship of all material and/or services. If, within the guarantee period, any defects occur which are due to faulty material and/or services included in his scope (design, manufacturing, inspection, testing, supply & etc.), VENDOR shall, at his own expense, repair or adjust the condition, or replace the material and/or services to the complete satisfaction of CLIENT's representative. These repairs, replacement or adjustments shall be made only at such time as will be least detrimental to the operation of the CLIENT's business.

VENDOR warrants promptly repairing or replacing the defective parts in the warranty period.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



ىىمان:	شماره

. 22 - . 12 - . 174

PMR FOR LOCAL CONTROL STATION (LCS)								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	EL	MR	0010	D01	

شماره صفحه: ۹ از ۱۴

Vendor shall ensure a correct and safe operation of the unit, providing all safety protection Devices. Vendor shall be responsible for the safe, reliable, continuous functioning of the Equipment/Devices/Items.

VENDOR is fully responsible for the design of package for correct and safe operation based on project requirement during package life time; therefore, VENDOR shall specify any documents/specifications which may be required for design, manufacture and finalizing of Equipment/Devices/Items to avoid any problems during the package operation at site before P.O; otherwise, VENDOR shall be hold responsible for any corresponding deviation from expectations from the Equipment/Devices/Items.

10.0 DEVIATION

VENDOR's proposal shall be prepared in strict compliance with the requirements set forth in the relevant specifications of tender documents.

VENDOR shall include in his proposal the statement of compliance with the tender documents should VENDOR wish to submit exception to the requirements of tender documents. They shall be submitted for PURCHASER's approval.

11.0 PRICE BREAKDOWN

Breakdown price of following items shall be included in the proposal, as well as total price.

- 1) Material and Fabrication for each Section Separately
- 2) Pre-commissioning & commissioning spare parts (END-QC-SP-1)
- 3) 2 years operational spare parts (END-QC-SP-1)
- 4) Packing & transportation
- 5) Other fee (if any)



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

٠۵٣ - ٠٧٣ - ٩١٨۴

PMR FOR LOCAL CONTROL STATION (LCS)								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	EL	MR	0010	D01	

شماره صفحه: ۱۰ از ۱۴

ATTACHMENT 1

11.1 <u>LIST OF REFERENCE / APPLICABLE DOCUMENTS</u>



No.	Document No.	Document Title			
Proc	ess				
1.	BK-GNRAL-PEDCO-000-PR-DB-0001	Process Basis of Design	D08		
Elect	trical				
2.	BK-GNRAL-PEDCO-000-EL-DC-0001	Electrical System Design Criteria	D02		
3.	BK-GNRAL-PEDCO-000-EL-SP-0008	Specification for Bulk Materials	D04		
4.	BK-GCS-PEDCO-120-EL-DT-0006	Data Sheets for Local Control Stations (LCS)	D02		
5.	-	MTO for LCS			
6.	BK-GCS-PEDCO-120-SA-PY-0002	Hazardous Area Classification Layout			
Gene	eral				
7.	BK-GNRAL-PEDCO-000-QC-PR-0022	Specification for Final Data Book (FDB) Requirements	D00		
8.	BK-GNRAL-PEDCO-000-QC-PR-0045	Packing , Marking , Transportation Procedure	D00		
9.	ICE-EID-MI-SP01-Rev01	دستورالعمل بازرسی، خرید و ساخت کالا	1		
10.	ICE-EID-MI-SP02-Rev01	سطح بازرسی کالا و تجهیزات	-		
11.	E&C-QC-SP-1	دستورالعمل تامین قطعات یدکی راه اندازی و راهبری دو سالانه	-		
12.	BK-GNRAL-PEDCO-000-PI-SP-0006	Specification for Painting			
13.	BK-GNRAL-HD-000-PM-PR-0003	Document Numbering Procedure	G04		

ATTACHMENT 2



11.2 <u>VENDOR DOCUMENTS MIN. REQUIREMENT</u>

		With Bid	TIME SCHEDULE				
Š.		With Bid	For Re	view	Final Issue		
Item	Document	Copies No./Type (7)	Copies No./Type (1)	Solar days (2)	Copies No./Typ e (1)	Calendar days (3)	
	MA	NAGEMENT					
1.	Vendor Document Index and Schedule	4N	6C+E		6C+E		
2.	Organization Brief	3N	6C+E				
3.	Schedule Level 1, 2, 3 & 4 showing Engineering, Procurement, Fabrication, Inspection, Testing, and Delivery Plan.	4N	6C+E		6C+E		



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

۰۵۳ - ۲۷۳ - ۹۱۸۴

PMR FOR LOCAL CONTROL STATION (LCS)								l
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	l
BK	GCS	PEDCO	120	EL	MR	0010	D01	

شماره صفحه: ۱۱ از ۱۴

				TIME S	CHEDULE	TIME SCHEDULE				
ġ.		With Bid	For Review		Final Issue					
Item No.	Document	Copies No./Type (7)	Copies No./Type (1)	Solar days (2)	Copies No./Typ e (1)	Calendar days (3)				
4.	Physically Progress Report (Every 2 Weeks))		6C+E							
5.	Project Organization Chart	3N	6C+E							
6.	Reference List	3N								
7.	Vendor Catalogue	3N								
8.	Sub-vendors list									
		QUALITY								
9.	Quality Assurance Manual /Quality Management System Certificate (according to latest rev. of ISO)	4N			6C+E					
10.	Preliminary Inspection and Test Plan	4N								
11.	Inspection and Test Plan		6C+E		6C+E					
		HSE								
12.	HSE Procedure		6C+E		6C+E					
	ENG	GINEERING								
13.	Wiring & Terminal Diagram		6C+E		6C+E					
14.	Data Sheet for LCS		6C+E		6C+E					
15.	Outline Drawing for LCS		6C+E		6C+E					
16.	Name Plate Drawing for LCS		6C+E		6C+E					
17.	Foundation Detail for LCS		6C+E		6C+E					
	PRO	CUREMENT								
18.	List of Sub-Suppliers (table giving: part of equipment, tag no., sub-supplier reference)(5.1.3)	4N			6C+E					
19.	Unpriced copy of sub-orders		6C+E							
	MANU	JFACTURING								
20.	Surface Preparation and Painting Procedures		6C+E		6C+E					
	1	TESTING								
21.	Factory Acceptance Test (FAT) Procedure		6C+E		6C+E					



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

· 24 - · 74 - 9114

PMR FOR LOCAL CONTROL STATION (LCS)								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	EL	MR	0010	D01	

شماره صفحه: ۱۲ از ۱۴

			TIME SCHEDULE				
ġ.		With Bid	For Review		Final Issue		
Item No.	Document	Copies No./Type (7)	Copies No./Type (1)	Solar days (2)	Copies No./Typ e (1)	Calendar days (3)	
	RECORDS, REP	ORTS & CERTII	FICATES				
22.	Type Test Certificate		6C+E		6C+E		
	INS	TALLATION					
23.	Sub-Assembly Documentation		6C+E		6C+E		
24.	Sub-Assembly Drawings		6C+E		6C+E		
25.	Erection/Installation Manual (if required)		6C+E		6C+E		
26.	Handling, Transportation & Storage Instructions & Preservation		6C+E		6C+E		
27.	Unpacking & Inspection Instructions		6C+E		6C+E		
28.	Packing List		6C+E				
29.	Sub-Assembly Documentation						
30.	Sub-Assembly Drawings		6C+E		6C+E		
	OPERATION	N & MAINTENAI	NCE				
31.	Operating Instructions		6C+E		6C+E		
32.	Maintenance Instructions (if required)		6C+E		6C+E		
33.	Commissioning & Start-up Manual		6C+E		6C+E		
34.	List of Spare Parts Commissioning & Start-up	4N	6C+E		6C+E		
35.	List of Spare Parts 2 Years Operation	4N	6C+E		6C+E		
36.	List of Special Tools	4N	6C+E		6C+E		
37.	Software Manual (incl. Troubleshooting)		6C+E		6C+E		
38.	Function Test Procedure		6C+E		6C+E		
39.	Operating Instructions		6C+E		6C+E		
40.	Maintenance Instructions (if required)		6C+E		6C+E		
		OTHERS					
41.	All others documents (if required) will be listed in the order		6C+E				



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

· ۵۳ - · ۷۳ - 9 1 1 4

PMR FOR LOCAL CONTROL STATION (LCS)							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	EL	MR	0010	D01

شماره صفحه: ۱۳ از ۱۴

Item No.	Document	With Bid	TIME SCHEDULE			
		With Bid	For Review		Final Issue	
		Copies No./Type (7)	Copies No./Type	Solar days (2)	Copies No./Typ e (1)	Calendar days (3)

NOTES:

- (1) N= Number of document, C=Copy, E=Electronic Copy
- (2) Starting from date of order placement
- (3) Starting from reception of documentation without comments
- (4) First issue of the document is subjected to the release of payment milestone as per purchase order
- (5) Calendar days after reception of drive data
- (6) Prior to testing
- (7) One copy each bid copy
- (8) List of Documents Will be Finalized in Vendor Document index and Schedule

ATTACHMENT 3

11.3 <u>DEVIATIONS / EXCEPTIONS TO JOB SPECIFICATION</u>

Requisition No.:
Description:
Equipment No.:

Item No.	Description of proposed exception	Recommended revision to job specification	Reason for proposed exception	Effect on base proposal if CONTRACTOR rejects exception





احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

PMR FOR LOCAL CONTROL STATION (LCS) شماره پیمان: بسته کاری صادر کننده تسهيلات رشته نوع مدرك نسخه پروژه سريال · 27 - · 77 - 9114 BK GCS PEDCO 120 EL MR 0010 D01

شماره صفحه: ۱۴ از ۱۴

ATTACHMENT 4

Requisition No.:

Description:

11.4 ALTERNATIVES TO JOB SPECIFICATION

E	Equipment No.:							
	Item No.	Job Specification No. & Paragraph No.	Requirements of Job Specification	Description of Proposed Alternative	Reason for Proposed Alternative			