

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک							 	
	DATA SHEETS FOR CORROSION COUPON/ PROBE								
شماره پیمان: 053 - 073 - 9184	پروژه BK	بسته کاری GCS	صادرکننده PEDCO	تسهیلات 120	رشته IN	نوع مدرک DT	سریال 0014	نسخه D03	شماره صفحه: 1 از 11

طرح نگهداشت و افزایش تولید 27 مخزن

DATA SHEETS FOR CORROSION COUPON/ PROBE

نگهداشت و افزایش تولید میدان نفتی بینک

D03	AUG.2023	IFA	P.Hajisadeghi	M.Fakharian	A.M.Mohseni	
D02	MAR.2023	IFA	P.Hajisadeghi	M.Fakharian	M.Mehrshad	
D01	NOV.2022	IFA	P.Hajisadeghi	M.Fakharian	M.Mehrshad	
D00	MAR.2022	IFC	P.Hajisadeghi	M.Fakharian	M.Mehrshad	
Rev.	Date	Purpose of Issue / Status	Prepared by:	Checked by:	Approved by:	CLIENT Approval

Class: 1

CLIENT Doc. Number: F9Z-708935

status:

IDC: Inter-Discipline Check

IFC: Issued For Comment

IFA: Issued For Approval

AFD: Approved For Design

AFC: Approved For Construction

AFP: Approved For Purchase

AFQ: Approved For Quotation

IFI: Issued For Information

AB-R: As-Built for CLIENT Review

AB-A: As-Built -Approved



NISOC

نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



DATA SHEETS FOR CORROSION COUPON/ PROBE

شماره پیمان:

053 - 073 - 9184

نسخه	سریال	نوع مدرک	رشته	تسهیلات	صادرکننده	بسته کاری	پروژه
D03	0014	DT	IN	120	PEDCO	GCS	BK

شماره صفحه: 2 از 11

REVISION RECORD SHEET

Page	D00	D01	D02	D03	D04
1	X	X	X	X	
2	X	X	X	X	
3	X	X	X		
4	X	X		X	
5	X	X		X	
6	X	X	X	X	
7	X	X	X	X	
8	X	X	X	X	
9		X	X	X	
10		X	X	X	
11		X	X	X	
12					
13					
14					
15					
16					
17					
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39					
40					
41					
42					
43					
44					
45					
46					
47					
48					
49					
50					
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					

Page	D00	D01	D02	D03	D04
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96					
97					
98					
99					
100					
101					
102					
103					
104					
105					
106					
107					
108					
109					
110					
111					
112					
113					
114					
115					
116					
117					
118					
119					
120					
121					
122					
123					
124					
125					
126					
127					
128					



NISOC

نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



DATA SHEETS FOR CORROSION COUPON/ PROBE

شماره پیمان:

053 - 073 - 9184

پروژه

BK

بسته کاری

GCS

صادر کننده

PEDCO

تسهيلات

120

رشته

IN

نوع مدرک

DT

سریال

0014

نسخه

D03

شماره صفحه: 3 از 11

Table of Contents:

DESCRIPTION	P&ID NUMBER	SHEET NUMBER
COVER		1
REVISION RECORD SHEET		2
TABLE OF CONTENTS		3
REFERENCE		4
GENERAL NOTES		5
CC (1): CC-2101 CC-2102 CC-2211	BK-GCS-PEDCO-120-PR-PI-0002 BK-GCS-PEDCO-120-PR-PI-0003 BK-GCS-PEDCO-120-PR-PI-0004 (1 of 2)	6
CC (2): CC-2112 CC-2141 CC-2271	BK-GCS-PEDCO-120-PR-PI-0005 BK-GCS-PEDCO-120-PR-PI-0012 BK-GCS-PEDCO-120-PR-PI-0022	7
CC (3): CC-2151 CC-2162 -	BK-GCS-PEDCO-120-PR-PI-0013 BK-GCS-PEDCO-120-PR-PI-0014	8
CP (1): CP-2101 CP-2102 CP-2211	BK-GCS-PEDCO-120-PR-PI-0002 BK-GCS-PEDCO-120-PR-PI-0003 BK-GCS-PEDCO-120-PR-PI-0004 (1 of 2)	9
CP (2): CP-2112 CP-2141 CP-2271	BK-GCS-PEDCO-120-PR-PI-0005 BK-GCS-PEDCO-120-PR-PI-0012 BK-GCS-PEDCO-120-PR-PI-0022	10
CP (3): CP-2151	BK-GCS-PEDCO-120-PR-PI-0013	11



NISOC

نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



DATA SHEETS FOR CORROSION COUPON/ PROBE

شماره پیمان:

053 - 073 - 9184

پروژه

BK

بسته کاری

GCS

صادر کننده

PEDCO

تسهیلات

120

رشته

IN

نوع مدرک

DT

سریال

0014

نسخه

D03

شماره صفحه: 4 از 11

REFERENCE DOCUMENTS :

Specification For Instrumentation

Process Basis Of Design

Piping Material Specification

Hazardous Area Classification Layout

Instrument & Control System Design Criteria

Mechanical Data Sheets For Lean Glycol Storage Tank

Symbol & Legend For PFD and P&ID

P&ID - Gas Compression Inlet Gas Pipeline (Binak)

P&ID - Gas Compression Inlet Gas Pipeline (Golkhari)

P&ID - Slug Catcher System

P&ID - Gas Compression Inlet Knock Out Drum

P&ID - 1st Stage Gas Compression Suction Drums

P&ID - 1st Stage Gas Compression Compressors

P&ID - 1st Stage Gas Compression Air Coolers

P&ID - 2nd Stage Gas Compression Suction Drums

P&ID - 2nd Stage Gas Compression Compressors

P&ID - 2nd Stage Gas Compression Air Coolers

P&ID - 2nd Stage Gas Compression Discharge Drum

P&ID - Gas Compression Dehydration Package

P&ID - Lean Glycol Storage Tank

P&ID - Instrument & Plant Air System

P&ID - Nitrogen Generation System

P&ID - Close Drain System

P&ID - Corrosion Inhibitor Package

P&ID - Methanol Injection Package

P&ID - LP Flare System

P&ID - Oily Water Sewer

P&ID - Fuel Gas System

P&ID - Diesel Oil System

P&ID - Potable Water System

P&ID - Glycol Sump Drum

P&ID - Fire Water Network

P&ID - Total Flooding System For Extension of Existing Elect. Building

BK-GNRAL-PEDCO-000-IN-SP-0001

BK-GNRAL-PEDCO-000-PR-DB-0001

BK-GCS-PEDCO-120-PI-SP-0001

BK-GCS-PEDCO-120-SA-PY-0002

BK-GCS-PEDCO-120-IN-DC-0002

BK-GCS-PEDCO-120-ME-DT-0016

BK-GCS-PEDCO-120-PR-PI-0001

BK-GCS-PEDCO-120-PR-PI-0002

BK-GCS-PEDCO-120-PR-PI-0003

BK-GCS-PEDCO-120-PR-PI-0004

BK-GCS-PEDCO-120-PR-PI-0005

BK-GCS-PEDCO-120-PR-PI-0006

BK-GCS-PEDCO-120-PR-PI-0007

BK-GCS-PEDCO-120-PR-PI-0008

BK-GCS-PEDCO-120-PR-PI-0009

BK-GCS-PEDCO-120-PR-PI-0010

BK-GCS-PEDCO-120-PR-PI-0011

BK-GCS-PEDCO-120-PR-PI-0012

BK-GCS-PEDCO-120-PR-PI-0013

BK-GCS-PEDCO-120-PR-PI-0014

BK-GCS-PEDCO-120-PR-PI-0015

BK-GCS-PEDCO-120-PR-PI-0016

BK-GCS-PEDCO-120-PR-PI-0017

BK-GCS-PEDCO-120-PR-PI-0018

BK-GCS-PEDCO-120-PR-PI-0019

BK-GCS-PEDCO-120-PR-PI-0020

BK-GCS-PEDCO-120-PR-PI-0021

BK-GCS-PEDCO-120-PR-PI-0022

BK-GCS-PEDCO-120-PR-PI-0023

BK-GCS-PEDCO-120-PR-PI-0024

BK-GCS-PEDCO-120-PR-PI-0025

BK-GCS-PEDCO-120-SA-PI-0001

BK-GCS-PEDCO-120-SA-PI-0002

D03



NISOC

نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



DATA SHEETS FOR CORROSION COUPON/ PROBE

شماره پیمان:	پروژه	بسته کاری	صادر کننده	تسهیلات	رشته	نوع مدرک	سریال	نسخه	شماره صفحه: 5 از 11
053 - 073 - 9184	BK	GCS	PEDCO	120	IN	DT	0014	D03	

GENERAL NOTES:

- Licensed software for probes and training Courses for End User engineering department shall be considered by vendor.
- One set of retriever tool kit and service valve and also other part necessary for mounting of all corrosion coupon and probes shall be provided by vendor. This set of retriever and service valve is common to all CC/CP's fittings. Also any calibration set or special tools for test and installation shall be provided by vendor, as minimum on set portable corrosion meter for local monitoring of probes to be considered.

- Environmental Condition For Field Instrumentation of BINAK Complex Shall Be Considered As Per The Following:

Maximum ambient temperature: 50 (°C)
Minimum ambient temperature: -5 (°C)
Maximum steel surface exposed to sun: 85 (°C)
Maximum summer dry bulb: - (°C)
DB/RH for Summer HVAC Design: 41 °C / 61 %
DB FOR Winter HVAC Design: 6 °C

Relative Humidity:

- Maximum Design relative humidity (%): 100
- Minimum Design relative humidity (%): 0

- Training Courses for Installation, Calibration, ... of corrosion transmitters shall be considered by vendor.
- Considering the fluid corrosibility, the Element material shall be in accordance with pipe material.
- All recommendations of IPS-I-TP-802 and NACE RP0775 for corrosion monitoring devices and accessories installation shall be followed by vendor.
- Service valve & retriever system to be have below specification:
 - Suitable connection for 2" Access fitting
 - Isolating Valve
 - Drain Plug
 - Pressure Gauge
 - Retriever/Service Valve Seal Kit
 - Retriever/Service valve Repair Kit
 - Diverter Hose Assembly, Retainer Clamp, Safety Hammer, Head Bar, Back Pressure Pump
 - To be suitable for 40 barg design pressure B38 (suitable for high pressure) and 85° C design temperature.
- Mounting Position for Gas services should be at 12 O'clock Position for easy maintenance.
- Wetted part material shall be according to NACE MR 01-175 where required as per piping material standard.
- Regarding protection of pipeline transportation system, ISO 15589 standards to be followed.

D03

- Electrical Resistance (ER) or Linear Polarization Resistance (LPR) methods shall be used in corrosion probes. Ultrasonic Examination, Acoustic Emission and other methods may be used individually or in combination with other methods if the Vendor advises. No local electrical power exists for these probes.

One Portable meter (shall be provided by vendor (To measure the Resistance of the probe periodically). This meter is common to all CP's fittings. Also any calibration set or special tools for test and installation shall be provided by vendor.

- Tag plate as per Specification for Instrumentation, shall be stainless steel 304 SS (VTC). Following details shall be engraved on them:

- Tag Number
- Range Limit
- Service
- Manufacture Model

- As per Mechanical Data Sheets For Lean Glycol Storage Tank Doc. No. "BK-GCS-PEDCO-120-ME-DT-0016_D02", the elevation of CC flange on TK-2102 (from center of flange to ground level) is 1200mm. This elevation to be considered by vendor during retriever system selection

D03

 NISOC		نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک						 		
		DATA SHEETS FOR CORROSION COUPON/ PROBE								
شماره پیمان: 053 - 073 - 9184		پروژه	بسته کاری	صادر کننده	تجهیزات	رشته	نوع مدرک	سریال	نسخه	شماره صفحه: 6 از 11 D03
		BK	GCS	PEDCO	120	IN	DT	0014	D03	

GENERAL	1	TAG NO	CC-2101	CC-2102	CC-2111
	2	P&ID NO.	BK-GCS-PEDCO-120-PR-PI-0002-D06	BK-GCS-PEDCO-120-PR-PI-0003-D06	BK-GCS-PEDCO-120-PR-PI-0004 (1 of 2)-D06
	3	SERVICE	TO INLET K.O. DRUM (V-2105)	TO SLUG CATCHER (V-2104)	AFTER SLUG CATCHER DRUM (V-2104) TO INLET K.O. DRUM (V-2105)
	4	LINE NO.	GAS-111-0001-AN07-6"-PT	GAS-111-0001-FN07-8"-PT	GAS-111-0019-AN07-8"-PT
	5	LINE SIZE / SCHEDULE	6" , SCH.80 (Note 4)	8" , SCH.100 (Note 4)	8" , SCH.60 (Note 4)
	6	LINE/EQUIPMENT MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
	7	PIPING CLASS	AN07 (Note 4)	FN05 (Note 4)	AN07 (Note 4)
	8	AREA CLASSIFICATION	N/A	N/A	N/A
	9	NACE COMPLIANCE (as per NACE MR0175/ISO 15156)	Required	Required	Required
PROCESS DATA (NOTE 1)	10	FLUID	GAS/Liquid	GAS/Liquid	GAS/Liquid
	11	PHASE	2 phase (Water/Vapour)	2 phase (Water/Vapour)	2 phase (Water/Vapour)
	12	DESIGN PRESSURE (barg)	18.2	90	18.2
	13	OPERATING. PRESSURE (barg)	7.5	7.5	5.3
	14	DESIGN TEMPERATURE (°C)	85	85	85
	15	MIN DESIGN METAL TEMPERATURE (°C)	5	5	5
	16	OPERATING TEMPERATURE (°C)	46.11/26.67	32/15.5	31.86/15.35
	17	MAX FLOW (Kg/hr)	7220.4	12395.9308	12395.9308
	18	NORMAL FLOW (Kg/hr)	6564	11269.028	11269.028
	19	MEAN VELOCITY (m/s)	14.68	9.9	15.79
	20	VISCOSITY (cP)	0.01	0.01	-
	21	DENSITY (kg/m3)	6.66	6.21 ~1000	6.16
	22	PIPING CORROSION ALLOWANCE (mm)	6	6	6
	23	WATER CUT	-	-	-
PROBE & TRANSMITTER	24	RATE OF CO2 CONTENT (SUM/WIN)	0.0345/0.0167 mole fraction in gas phase	0.0301/0.0296 mole fraction in gas phase	0.0562/0.0296 mole fraction in gas phase
	25	RATE OF CHLORIDE CONTENT	-	-	-
	26	VELOCITY	16.15	16.15	17.17
	27	PROBE TYPE	N/A	N/A	N/A
	28	PROBE INSERTION LENGTH	N/A	N/A	N/A
	29	PROBE HOLDER	N/A	N/A	N/A
	30	MATERIAL	N/A	N/A	N/A
	31	MOUNTING POSITION	N/A	N/A	N/A
	32	ENCLOSURE MATERIAL	N/A	N/A	N/A
	33	MEASURING RANGE	N/A	N/A	N/A
	34	OUTPUT SIGNAL	N/A	N/A	N/A
	35	COMMUNICATION PROTOCOL	N/A	N/A	N/A
	36	POWER SUPPLY	N/A	N/A	N/A
	37	ACCURACY	N/A	N/A	N/A
COUPON	38	INTEGRAL INDICATOR	N/A	N/A	N/A
	39	Ex PROTECTION	N/A	N/A	N/A
	40	INGRESS PROTECTION	N/A	N/A	N/A
	41	CABLE ENTRY	N/A	N/A	N/A
	42	-			
	43	COUPON TYPE	Ladder Strip(VTA)	Ladder Strip(VTA)	Ladder Strip(VTA)
	44	COUPON MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
	45	COUPON HOLDER (Note 6)	Yes	Yes	Yes
ACCESS FITTING (Note 5 & Note 6)	46	HOLDER MATERIAL	316 S.S as minimum	316 S.S as minimum	316 S.S as minimum
	47	HOLDER LENGTH	VTA	VTA	VTA
	48	COUPON INSERTION LENGTH	VTA	VTA	VTA
	49	WETTED PART MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
	50	STYLE	Retrievable (VTC)	Retrievable (VTC)	Retrievable (VTC)
	51	PROCESS CONNECTION	2", Flare Weld Type	2", Flare Weld Type	2", Flare Weld Type
OTHER	52	MOUNTING POSITION	at 12'O Clock (Note 8 in General Note)	at 12'O Clock (Note 8 in General Note)	at 12'O Clock (Note 8 in General Note)
	53	BRANCH STANDOUT LENGTH	(Note 2)	(Note 2)	(Note 2)
	54	FITTING PLUG	Solid Plug	Solid Plug	Solid Plug
	55	MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
	56	PROTECTIVE COVER	Required	Required	Required
	57	RETRACTABLE TOOL	Required (Note 3)	Required (Note 3)	Required (Note 3)
	58	SERVICE VALVE	Required (Note 3)	Required (Note 3)	Required (Note 3)
	59	MANUFACTURE	will be finalized later	will be finalized later	will be finalized later
	60	MODEL NO.	will be finalized later	will be finalized later	will be finalized later
	61	TAG PLATE (General Note 12)	Required	Required	Required
	62	WAKE FREQUENCY STANDARD (NOTE 2)	Required as per ASME PTC	Required as per ASME PTC	Required as per ASME PTC

NOTES :

VTA : VENDOR TO ADVISE VTC : VENDOR TO CONFIRM N/A : NOT APPLICABLE

(1) All process data will be finalized later

(2) Wake frequency analysis (stress calculation) according to ASME Power Test Code 19.3 shall be done & submitted by vendor.

(3) One set of retriever and service valve is common to all CC's fittings.

(4) Piping class, pipe schedule and materials related to Piping Material Specification, will be finalized after confirmation of this document.

(5) High pressure access fitting to be supplied by vendor.

(6) Length of stem holder for installation in 120 °clock due to liquid service, to be the way that measure the corrosion at the bottom of line.

 NISOC		نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک						 		
		DATA SHEETS FOR CORROSION COUPON/ PROBE								
شماره پیمان:		پروژه	بسته کاری	صادر کننده	تهیه کننده	رشته	نوع مدرک	سریال	نسخه	شماره صفحه: 7 از 11 D03
053 - 073 - 9184		BK	GCS	PEDCO	120	IN	DT	0014	D03	
GENERAL	1	TAG NO			CC-2112		CC-2141		CC-2271	
	2	P&ID NO.			BK-GCS-PEDCO-120-PR-PI-0005-D06		BK-GCS-PEDCO-120-PR-PI-0012-D06		BK-GCS-PEDCO-120-PR-PI-0022-D06	
	3	SERVICE			AFTER INLET KNOCK OUT DRUM (V-2105)		ABOVE THE GAS COMPRESSION DISCHARGE DRUM (V-2103)		ABOVE THE FUEL GAS K.O. DRUM (V-2205)	
	4	LINE NO.			GAS-111-0025-AN07-10"-PT		GAS-111-0066-FN05-6"-PT		FLG-112-0110-AN07-4"-PT	
	5	LINE SIZE / SCHEDULE			10" , SCH.40 (Note 4)		6" , SCH.80 (Note 4)		2" , SCH.160 (Note 4)	
	6	LINE/EQUIPMENT MATERIAL			ASTM A106 Gr.B (Note 4)		ASTM A106 Gr.B (Note 4)		ASTM A106 Gr.B (Note 4)	
	7	PIPING CLASS			AN07 (Note 4)		FN05 (Note 4)		AN07 (Note 4)	
	8	AREA CLASSIFICATION			N/A		N/A		N/A	
	9	NACE COMPLIANCE (as per NACE MR0175/ISO 15156)			Required		Required		Required	
PROCESS DATA (NOTE 1)	10	FLUID			GAS		GAS		FUEL GAS	
	11	PHASE			1 phase (Vapour)		1 phase (Vapour)		1 phase (Vapour)	
	12	DESIGN PRESSURE (barg)			18.2		90		18.2	
	13	OPERATING. PRESSURE (barg)			5.1		53.9		4.9	
	14	DESIGN TEMPERATURE (°C)			85		85		85	
	15	MIN DESIGN METAL TEMPERATURE (°C)			5		5		5	
	16	OPERATING TEMPERATURE (°C)			36.92/19.02		59.89/59.90		36.7	
	17	MAX FLOW (Kg/hr)			19616.421		18977.739		556.38	
	18	NORMAL FLOW (Kg/hr)			17833.11		17252.49		505.8	
	19	MEAN VELOCITY (m/s)			16.31		4.34		10.87	
	20	VISCOSITY (cP)			0.011		0.01		0.01	
	21	DENSITY (kg/m3)			5.96		59.17		5.96	
	22	PIPING CORROSION ALLOWANCE (mm)			6		3		6	
	23	WATER CUT			-		-		-	
	24	RATE OF CO2 CONTENT (SUM/WIN)			0.0316/0.0252 mole fraction in gas phase		0.0318/0.0252 mole fraction in gas phase		0.0316/0.0252 mole fraction in gas phase	
25	RATE OF CHLORIDE CONTENT			-		-		-		
26	VELOCITY			17.94		4.76		11.24		
PROBE & TRANSMITTER	27	PROBE TYPE			N/A		N/A		N/A	
	28	PROBE INSERTION LENGTH			N/A		N/A		N/A	
	29	PROBE HOLDER			N/A		N/A		N/A	
	30	MATERIAL			N/A		N/A		N/A	
	31	MOUNTING POSITION			N/A		N/A		N/A	
	32	ENCLOSURE MATERIAL			N/A		N/A		N/A	
	33	MEASURING RANGE			N/A		N/A		N/A	
	34	OUTPUT SIGNAL			N/A		N/A		N/A	
	35	COMMUNICATION PROTOCOL			N/A		N/A		N/A	
	36	POWER SUPPLY			N/A		N/A		N/A	
	37	ACCURACY			N/A		N/A		N/A	
	38	INTEGRAL INDICATOR			N/A		N/A		N/A	
	39	Ex PROTECTION			N/A		N/A		N/A	
	40	INGRESS PROTECTION			N/A		N/A		N/A	
	41	CABLE ENTRY			N/A		N/A		N/A	
	42									
	COUPON	43	COUPON TYPE			Ladder Strip(VTA)		Ladder Strip(VTA)		Ladder Strip(VTA)
44		COUPON MATERIAL			ASTM A106 Gr.B (Note 4)		ASTM A106 Gr.B (Note 4)		ASTM A106 Gr.B (Note 4)	
45		COUPON HOLDER (Note 6)			Yes		Yes		Yes	
46		HOLDER MATERIAL			316 S.S as minimum		316 S.S as minimum		316 S.S as minimum	
47		HOLDER LENGTH			VTA		VTA		VTA	
48		COUPON INSERTION LENGTH			VTA		VTA		VTA	
49		WETTED PART MATERIAL			ASTM A106 Gr.B (Note 4)		ASTM A106 Gr.B (Note 4)		ASTM A106 Gr.B (Note 4)	
50		STYLE			Retrievable (VTC)		Retrievable (VTC)		Retrievable (VTC)	
ACCESS FITTING (Note 5 & Note 6)	51	PROCESS CONNECTION			2", Flare Weld Type		2", Flare Weld Type		2", Flare Weld Type(Note7)	
	52	MOUNTING POSITION			at 12'O Clock (Note 8 in General Note)		at 12'O Clock (Note 8 in General Note)		at 12'O Clock (Note 8 in General Note)	
	53	BRANCH STANDOUT LENGTH			(Note 2)		(Note 2)		(Note 2)	
	54	FITTING PLUG			Solid Plug		Solid Plug		Solid Plug	
	55	MATERIAL			ASTM A106 Gr.B (Note 4)		ASTM A106 Gr.B (Note 4)		ASTM A106 Gr.B (Note 4)	
	56	PROTECTIVE COVER			Required		Required		Required	
	57	RETRACTABLE TOOL			Required (Note 3)		Required (Note 3)		Required (Note 3)	
	58	SERVICE VALVE			Required (Note 3)		Required (Note 3)		Required (Note 3)	
OTHER	59	MANUFACTURE			will be finalized later		will be finalized later		will be finalized later	
	60	MODEL NO.			will be finalized later		will be finalized later		will be finalized later	
	61	TAG PLATE (General Note 12)			Required		Required		Required	
	62	WAKE FREQUENCY STANDARD (NOTE 2)			Required as per ASME PTC		Required as per ASME PTC		Required as per ASME PTC	
NOTES : VTA : VENDOR TO ADVISE VTC : VENDOR TO CONFIRM N/A : NOT APPLICABLE (1) All process data will be finalized later (2) Wake frequency analysis (stress calculation) according to ASME Power Test Code 19.3 shall be done & submitted by vendor. (3) One set of retriever and service valve is common to all CC's fittings. (4) Piping class, pipe schedule and materials related to Piping Material Specification, will be finalized after confirmation of this document. (5) High pressure access fitting to be supplied by vendor. (6) Length of stem holder for installation in 12O'clock due to liquid service, to be the way that measure the corrosion at the bottom of line. (7) Pipe shall be expanded to 4" for CC installation (expansion size shall be confirmed by vendor).										



نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



DATA SHEETS FOR CORROSION COUPON/ PROBE

شماره پیمان:

053 - 073 - 9184

نسخه	سرال	نوع مدرک	رشته	تهیلات	صادرکننده	بسته کاری	پروژه
D03	0014	DT	IN	120	PEDCO	GCS	BK

شماره صفحه: 8 از 11

GENERAL	1	TAG NO	CC-2151	CC-2162	D03
	2	P&ID NO.	BK-GCS-PEDCO-120-PR-PI-0013-D06	BK-GCS-PEDCO-120-PR-PI-0014-D06	
	3	SERVICE	AFTER DEHYDRATION PACKAGE (PK-2101)	LEAN GLYCOL STORAGE TANK (TK-2102)	
	4	LINE NO.	GAS-111-0179-FN05-6"-PT	-	
	5	LINE SIZE / SCHEDULE	6" , SCH.80 (Note 4)	-	
	6	LINE/EQUIPMENT MATERIAL	ASTM A106 Gr.B (Note 4)	A-283 GR.C	
	7	PIPING CLASS	FN05 (Note 4)	AN04 (Note 4)	
	8	AREA CLASSIFICATION	N/A	N/A	
	9	NACE COMPLIANCE (as per NACE MR0175/ISO 15156)	Required	-	
PROCESS DATA (NOTE 1)	10	FLUID	GAS	LIQUID	
	11	PHASE	1 phase (Vapour)	1 phase (Liquid)	
	12	DESIGN PRESSURE (barg)	90	full of liquid +160 mbarg/-7 mbarg	
	13	OPERATING. PRESSURE (barg)	52.9	0.1	
	14	DESIGN TEMPERATURE (°C)	130	85	
	15	MIN DESIGN METAL TEMPERATURE (°C)	5	5	
	16	OPERATING TEMPERATURE (°C)	59.40/59.36	AMB	
	17	MAX FLOW (Kg/hr)	18887.9	5500	
	18	NORMAL FLOW (Kg/hr)	17170.8	5000	
	19	MEAN VELOCITY (m/s)	4.408	0.65	
	20	VISCOSITY (cP)	0.011	0.54	
	21	DENSITY (kg/m3)	58.06	988.2	
	22	PIPING CORROSION ALLOWANCE (mm)	3	3	
	23	WATER CUT	-	-	
	24	RATE OF CO2 CONTENT (SUM/WIN)	0.0319/0.0253 mole fraction in gas phase	0.0319/0.0253 mole fraction in gas phase	
PROBE & TRANSMITTER	25	RATE OF CHLORIDE CONTENT	-	-	
	26	VELOCITY	4.85	0.56	
	27	PROBE TYPE	N/A	N/A	
	28	PROBE INSERTION LENGTH	N/A	N/A	
	29	PROBE HOLDER	N/A	N/A	
	30	MATERIAL	N/A	N/A	
	31	MOUNTING POSITION	N/A	N/A	
	32	ENCLOSURE MATERIAL	N/A	N/A	
	33	MEASURING RANGE	N/A	N/A	
	34	OUTPUT SIGNAL	N/A	N/A	
	35	COMMUNICATION PROTOCOL	N/A	N/A	
	36	POWER SUPPLY	N/A	N/A	
	37	ACCURACY	N/A	N/A	
	38	INTEGRAL INDICATOR	N/A	N/A	
	39	Ex PROTECTION	N/A	N/A	
COUPON	40	INGRESS PROTECTION	N/A	N/A	
	41	CABLE ENTRY	N/A	N/A	
	42	-			
	43	COUPON TYPE	Ladder Strip(VTA)	Strip	
	44	COUPON MATERIAL	ASTM A106 Gr.B (Note 4)	A-283 GR.C	
	45	COUPON HOLDER (Note 6)	Yes	Yes	
	46	HOLDER MATERIAL	316 S.S as minimum	316 S.S as minimum	
ACCESS FITTING (Note 5)	47	HOLDER LENGTH	VTA	VTA	
	48	COUPON INSERTION LENGTH	VTA	VTA	
	49	WETTED PART MATERIAL	ASTM A106 Gr.B (Note 4)	A-283 GR.C	
	50	STYLE	Retrievable (VTC)	Retrievable (VTC)	
	51	PROCESS CONNECTION	2", Flare Weld Type	2", Flange 300RF	
	52	MOUNTING POSITION	at 12'O Clock (Note 8 in General Note)	Vessel Side Mounted	
	53	BRANCH STANDOUT LENGTH	(Note 2)	(Note 2)	
	54	FITTING PLUG	Solid Plug	Solid Plug	
	55	MATERIAL	ASTM A106 Gr.B (Note 4)	A-283 GR.C	
	56	PROTECTIVE COVER	Required	Required	
OTHER	57	RETRACTABLE TOOL	Required (Note 3)	Required (Note 3)	
	58	SERVICE VALVE	Required (Note 3)	Required (Note 3)	
	59	MANUFACTURE	will be finalized later	will be finalized later	
	60	MODEL NO.	will be finalized later	will be finalized later	
	61	TAG PLATE (General Note 12)	Required	Required	
	62	WAKE FREQUENCY STANDARD (NOTE 2)	Required as per ASME PTC	Required as per ASME PTC 19.3	

NOTES :

VTA : VENDOR TO ADVISE

VTC : VENDOR TO CONFIRM

N/A : NOT APPLICABLE

- (1) All process data will be finalized later
- (2) Wake frequency analysis (stress calculation) according to ASME Power Test Code 19.3 shall be done & submitted by vendor.
- (3) One set of retriever and service valve is common to all CC's fittings.
- (4) Piping class, pipe schedule and materials related to Piping Material Specification, will be finalized after confirmation of this document.
- (5) High pressure access fitting to be supplied by vendor.
- (6) Length of stem holder for installation in 120° clock due to liquid service, to be the way that measure the corrosion at the bottom of line.

 NISOC		نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک								
		DATA SHEETS FOR CORROSION COUPON/ PROBE								
شماره پیمان:		پروژه	بسته کاری	صادر کننده	تهیه کننده	رشته	نوع مدرک	سریال	نسخه	شماره صفحه: 9 از 11 D03
053 - 073 - 9184		BK	GCS	PEDCO	120	IN	DT	0014	D03	

GENERAL	1	TAG NO	CP-2101	CP-2102	CP-2111
	2	P&ID NO.	BK-GCS-PEDCO-120-PR-PI-0002-D06	BK-GCS-PEDCO-120-PR-PI-0003-D06	BK-GCS-PEDCO-120-PR-PI-0004-D06(1 of 2)
	3	SERVICE	TO INLET K.O. DRUM (V-2105)	TO SLUG CATCHER (V-2104)	AFTER SLUG CATCHER DRUM (V-2104) TO INLET K.O. DRUM (V-2105)
	4	LINE NO.	GAS-111-0001-AN07-6"-PT	GAS-111-0001-FN07-8"-PT	GAS-111-0019-AN07-8"-PT
	5	LINE SIZE / SCHEDULE	6" , SCH.80 (Note 4)	8" , SCH.100 (Note 4)	8" , SCH.60 (Note 4)
	6	LINE/EQUIPMENT MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
	7	PIPING CLASS	AN07 (Note 4)	FN05 (Note 4)	AN07 (Note 4)
	8	AREA CLASSIFICATION	Zone 2, IIB T4	N/A	Zone 2, IIB T4
	9	NACE COMPLIANCE (as per NACE MR0175/ISO 15156)	Required	Required	Required
PROCESS DATA (NOTE 1)	10	FLUID	GAS/Liquid	GAS/Liquid	GAS/Liquid
	11	PHASE	2 phase (Water/Vapour)	2 phase (Water/Vapour)	2 phase (Water/Vapour)
	12	DESIGN PRESSURE (barg)	18.2	90	18.2
	13	OPERATING PRESSURE (barg)	7.5	7.5	5.3
	14	DESIGN TEMPERATURE (°C)	85	85	85
	15	MIN DESIGN METAL TEMPERATURE (°C)	5	5	5
	16	OPERATING TEMPERATURE (°C)	46.11/26.67	32/15.5	31.86/15.35
	17	MAX FLOW (Kg/hr)	7220.4	12395.9308	12395.9308
	18	NORMAL FLOW (Kg/hr)	6564	11269.028	11269.028
	19	MEAN VELOCITY (m/s)	14.68	9.9	15.79
	20	VISCOSITY (cP)	0.01	0.01	-
	21	DENSITY (kg/m3)	6.66	6.21 ~1000	6.16
	22	PIPING CORROSION ALLOWANCE (mm)	6	6	6
	23	WATER CUT	-	-	-
	PROBE & TRANSMITTER	24	RATE OF CO2 CONTENT (SUM/WIN)	0.0345/0.0167 mole fraction in gas phase	0.0301/0.0296 mole fraction in gas phase
25		RATE OF CHLORIDE CONTENT	-	-	-
26		VELOCITY	16.15	16.15	17.17
27		PROBE TYPE	VTA	VTA	VTA
28		PROBE INSERTION LENGTH	VTA	VTA	VTA
29		PROBE HOLDER	Yes	Yes	Yes
30		MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
31		MOUNTING POSITION	Top of line	Top of line	Top of line
32		ENCLOSURE MATERIAL	VTA	VTA	VTA
33		MEASURING RANGE	VTA	VTA	VTA
34		OUTPUT SIGNAL	(Note 11 in General Note)	(Note 11 in General Note)	(Note 11 in General Note)
35		COMMUNICATION PROTOCOL	(Note 11 in General Note)	(Note 11 in General Note)	(Note 11 in General Note)
36		POWER SUPPLY	(Note 11 in General Note)	(Note 11 in General Note)	(Note 11 in General Note)
37		ACCURACY	(Note 11 in General Note)	(Note 11 in General Note)	(Note 11 in General Note)
38		INTEGRAL INDICATOR	No	No	No
COUPON	39	Ex PROTECTION	Eex "ia"	Eex "ia"	Eex "ia"
	40	INGRESS PROTECTION	IP 65	IP 65	IP 65
	41	CABLE ENTRY	ISO M20 x 1.5	ISO M20 x 1.5	ISO M20 x 1.5
	42	STYLE	Retrievable Type (VTC)	Retrievable Type (VTC)	Retrievable Type (VTC)
	43	COUPON TYPE	N/A	N/A	N/A
	44	COUPON MATERIAL	N/A	N/A	N/A
	45	COUPON HOLDER (Note 6)	N/A	N/A	N/A
	46	HOLDER MATERIAL	N/A	N/A	N/A
	47	HOLDER LENGTH	N/A	N/A	N/A
	48	COUPON INSERTION LENGTH	N/A	N/A	N/A
ACCESS FITTING (Note 5 & Note 6)	49	-	N/A	N/A	N/A
	50	STYLE	N/A	N/A	N/A
	51	PROCESS CONNECTION	2", Flare Weld Type	2", Flare Weld Type	2", Flare Weld Type
	52	MOUNTING POSITION	at 12'O Clock (Note 8 in General Note)	at 12'O Clock (Note 8 in General Note)	at 12'O Clock (Note 8 in General Note)
	53	BRANCH STANDOUT LENGTH	(Note 2)	(Note 2)	(Note 2)
	54	FITTING PLUG	Hollow Plug	Hollow Plug	Hollow Plug
	55	MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
	56	PROTECTIVE COVER	Required	Required	Required
OTHER	57	RETRACTABLE TOOL	Required (Note 3)	Required (Note 3)	Required (Note 3)
	58	SERVICE VALVE	Required (Note 3)	Required (Note 3)	Required (Note 3)
	59	MANUFACTURE	will be finalized later	will be finalized later	will be finalized later
	60	MODEL NO.	will be finalized later	will be finalized later	will be finalized later
	61	TAG PLATE (General Note 12)	Required	Required	Required
	62	WAKE FREQUENCY STANDARD (NOTE 2)	Required as per ASME PTC	Required as per ASME PTC	Required as per ASME PTC

NOTES : VTA : VENDOR TO ADVISE VTC : VENDOR TO CONFIRM N/A : NOT APPLICABLE

(1) All process data will be finalized later

(2) Wake frequency analysis (stress calculation) according to ASME Power Test Code 19.3 shall be done & submitted by vendor.

(3) One set of retriever and service valve is common to all CC's fittings.

(4) Piping class, pipe schedule and materials related to Piping Material Specification, will be finalized after confirmation of this document.

(5) High pressure access fitting to be supplied by vendor.

(6) Length of stem holder for installation in 12O'clock due to liquid service, to be the way that measure the corrosion at the bottom of line.



نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تو اکم گاز در ایستگاه جمع آوری سنک



DATA SHEETS FOR CORROSION COUPON/ PROBE

بماره پیمان:

053 - 073-9184

نسخه	سریال	نوع مدرک	رشته	تسهیلات	صادر کننده	بسته کاری	پروژه
D03	0014	DT	IN	120	PEDCO	GCS	BK

شماره صفحه: 10 از 11

D03

GENERAL	1	TAG NO	CP-2112	CP-2141	CP-2271
	2	P&ID NO.	BK-GCS-PEDCO-120-PR-PI-0005-D06	BK-GCS-PEDCO-120-PR-PI-0012-D06	BK-GCS-PEDCO-120-PR-PI-0022-D06
	3	SERVICE	AFTER INLET KNOCK OUT DRUM (V-2105)	ABOVE THE GAS COMPRESSION DISCHARGE DRUM (V-2103)	ABOVE THE FUEL GAS K.O. DRUM (V-2205)
	4	LINE NO.	GAS-111-0025-AN07-10"-PT	GAS-111-0066-FN05-6"-PT	FLG-112-0110-AN07-4"-PT
	5	LINE SIZE / SCHEDULE	10" , SCH.40 (Note 4)	6" , SCH.80 (Note 4)	2". SCH.160 (Note 4)
	6	LINE/EQUIPMENT MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
	7	PIPING CLASS	AN07 (Note 4)	FN05 (Note 4)	AN07 (Note 4)
	8	AREA CLASSIFICATION	Zone 2,IIB T4	Zone 2,IIB T4	N/A
	9	NACE COMPLIANCE (as per NACE MR0175/ISO 15156)	Required	Required	Required
PROCESS DATA (NOTE 1)	10	FLUID	GAS	GAS	FUEL GAS
	11	PHASE	1 phase (Vapour)	1 phase (Vapour)	1 phase (Vapour)
	12	DESIGN PRESSURE (barg)	18.2	90	18.2
	13	OPERATING. PRESSURE (barg)	5.1	53.9	4.9
	14	DESIGN TEMPERATURE (°C)	85	85	85
	15	MIN DESIGN METAL TEMPERATURE (°C)	5	5	5
	16	OPERATING TEMPERATURE (°C)	36.92/19.02	59.89/59.90	36.7
	17	MAX FLOW (Kg/hr)	19616.421	18977.739	556.38
	18	NORMAL FLOW (Kg/hr)	17833.11	17252.49	505.8
	19	MEAN VELOCITY (m/s)	16.31	4.34	10.87
	20	VISCOSITY (cP)	0.011	0.01	0.01
	21	DENSITY (kg/m3)	5.96	59.17	5.96
	22	PIPING CORROSION ALLOWANCE (mm)	6	3	6
	23	WATER CUT	-	-	-
PROBE & TRANSMITTER	24	RATE OF CO2 CONTENT (SUM/WIN)	0.0316/0.0252 mole fraction in gas phase	0.0318/0.0252 mole fraction in gas phase	0.0316/0.0252 mole fraction in gas phase
	25	RATE OF CHLORIDE CONTENT	-	-	-
	26	VELOCITY	17.94	4.76	11.24
	27	PROBE TYPE	VTA	VTA	VTA
	28	PROBE INSERTION LENGTH	VTA	VTA	VTA
	29	PROBE HOLDER	Yes	Yes	Yes
	30	MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
	31	MOUNTING POSITION	Top of line	Top of line	Top of line
	32	ENCLOSURE MATERIAL	VTA	VTA	VTA
	33	MEASURING RANGE	VTA	VTA	VTA
	34	OUTPUT SIGNAL	(Note 11 in General Note)	(Note 11 in General Note)	(Note 11 in General Note)
	35	COMMUNICATION PROTOCOL	(Note 11 in General Note)	(Note 11 in General Note)	(Note 11 in General Note)
	36	POWER SUPPLY	(Note 11 in General Note)	(Note 11 in General Note)	(Note 11 in General Note)
	37	ACCURACY	(Note 11 in General Note)	(Note 11 in General Note)	(Note 11 in General Note)
COUPON	38	INTEGRAL INDICATOR	No	No	No
	39	Ex PROTECTION	Eex "ia"	Eex "ia"	Eex "ia"
	40	INGRESS PROTECTION	IP 65	IP 65	IP 65
	41	CABLE ENTRY	ISO M20 x 1.5	ISO M20 x 1.5	ISO M20 x 1.5
	42	STYLE	Retrievable Type (VTC)	Retrievable Type (VTC)	Retrievable Type (VTC)
	43	COUPON TYPE	N/A	N/A	N/A
	44	COUPON MATERIAL	N/A	N/A	N/A
	45	COUPON HOLDER (Note 6)	N/A	N/A	N/A
	46	HOLDER MATERIAL	N/A	N/A	N/A
	47	HOLDER LENGTH	N/A	N/A	N/A
ACCESS FITTING (Note 5 & Note 6)	48	COUPON INSERTION LENGTH	N/A	N/A	N/A
	49	-	N/A	N/A	N/A
	50	STYLE	N/A	N/A	N/A
	51	PROCESS CONNECTION	2", Flare Weld Type	2", Flare Weld Type	2", Flare Weld Type(Note7)
	52	MOUNTING POSITION	at 12'O Clock (Note 8 in General Note)	at 12'O Clock (Note 8 in General Note)	at 12'O Clock (Note 8 in General Note)
	53	BRANCH STANDOUT LENGTH	(Note 2)	(Note 2)	(Note 2)
	54	FITTING PLUG	Hollow Plug	Hollow Plug	Hollow Plug
	55	MATERIAL	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)	ASTM A106 Gr.B (Note 4)
OTHER	56	PROTECTIVE COVER	Required	Required	Required
	57	RETRACTABLE TOOL	Required (Note 3)	Required (Note 3)	Required (Note 3)
	58	SERVICE VALVE	Required (Note 3)	Required (Note 3)	Required (Note 3)
	59	MANUFACTURE	will be finalized later	will be finalized later	will be finalized later
	60	MODEL NO.	will be finalized later	will be finalized later	will be finalized later
	61	TAG PLATE (General Note 12)	Required	Required	Required
	62	WAKE FREQUENCY STANDARD (NOTE 2)	Required as per ASME PTC	Required as per ASME PTC	Required as per ASME PTC

NOTES :

VT A : VENDOR TO ADVISE

VTC : VENDOR TO CONFIRM

N/A : NOT APPLICABLE

- (1) All process data will be finalized later
- (2) Wake frequency analysis (stress calculation) according to ASME Power Test Code 19.3 shall be done & submitted by vendor.
- (3) One set of retriever and service valve is common to all CC's fittings.
- (4) Piping class, pipe schedule and materials related to Piping Material Specification, will be finalized after confirmation of this document.
- (5) High pressure access fitting to be supplied by vendor.
- (6) Length of stem holder for installation in 120° clock due to liquid service, to be the way that measure the corrosion at the bottom of line.
- (7) Pipe shall be expanded to 4" for CC installation (expansion size shall be confirmed by vendor).

 NISOC		نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک						 		
		DATA SHEETS FOR CORROSION COUPON/ PROBE								
شماره پیمان:		پروژه	بسته کاری	صادر کننده	تهیهات	رشته	نوع مدرک	سریال	نسخه	شماره صفحه: 11 از 11
053 - 073 - 9184		BK	GCS	PEDCO	120	IN	DT	0014	D03	

GENERAL	1	TAG NO	CP-2151	D03	
	2	P&ID NO.	BK-GCS-PEDCO-120-PR-PI-0013-D06		
	3	SERVICE	AFTER DEHYDRATION PACKAGE (PK-2101)		
	4	LINE NO.	GAS-111-0179-FN05-6"-PT		
	5	LINE SIZE / SCHEDULE	6" , SCH.80 (Note 4)		
	6	LINE/EQUIPMENT MATERIAL	ASTM A106 Gr.B (Note 4)		
	7	PIPING CLASS	FN05 (Note 4)		
	8	AREA CLASSIFICATION	Zone 2,IIB T4		
	9	NACE COMPLIANCE (as per NACE MR0175/ISO 15156)	Required		
PROCESS DATA (NOTE 1)	10	FLUID	GAS		
	11	PHASE	1 phase (Vapour)		
	12	DESIGN PRESSURE (barg)	90		
	13	OPERATING PRESSURE (barg)	52.9		
	14	DESIGN TEMPERATURE (°C)	130		
	15	MIN DESIGN METAL TEMPERATURE (°C)	5		
	16	OPERATING TEMPERATURE (°C)	59.40/59.36		
	17	MAX FLOW (Kg/hr)	18887.9		
	18	NORMAL FLOW (Kg/hr)	17170.8		
	19	MEAN VELOCITY	4.408		
	20	VISCOSITY (cP)	0.011		
	21	DENSITY (kg/m3)	58.06		
	22	PIPING CORROSION ALLOWANCE (mm)	6		
	23	WATER CUT	-		
	PROBE & TRANSMITTER	24	RATE OF CO2 CONTENT (SUM/WIN)	0.0319/0.0253 mole fraction in gas phase	
25		RATE OF CHLORIDE CONTENT	-		
26		VELOCITY	4.85		
27		PROBE TYPE	VTA		
28		PROBE INSERTION LENGTH	VTA		
29		PROBE HOLDER	Yes		
30		MATERIAL	ASTM A106 Gr.B (Note 4)		
31		MOUNTING POSITION	Top of line		
32		ENCLOSURE MATERIAL	VTA		
33		MEASURING RANGE	VTA		
34		OUTPUT SIGNAL	(Note 11 in General Note)		
35		COMMUNICATION PROTOCOL	(Note 11 in General Note)		
36		POWER SUPPLY	(Note 11 in General Note)		
37		ACCURACY	(Note 11 in General Note)		
COUPON		38	INTEGRAL INDICATOR	No	
	39	Ex PROTECTION	Eex "ia"		
	40	INGRESS PROTECTION	IP 65		
	41	CABLE ENTRY	ISO M20 x 1.5		
	42	STYLE	Retrievable Type (VTC)		
	43	COUPON TYPE	N/A		
	44	COUPON MATERIAL	N/A		
	45	COUPON HOLDER (Note 6)	N/A		
	46	HOLDER MATERIAL	N/A		
	47	HOLDER LENGTH	N/A		
ACCESS FITTING (Note 5 & Note 6)	48	COUPON INSERTION LENGTH	N/A		
	49	-	N/A		
	50	STYLE	N/A		
	51	PROCESS CONNECTION	2", Flare Weld Type		
	52	MOUNTING POSITION	at 12'O Clock (Note 8 in General Note)		
	53	BRANCH STANDOUT LENGTH	(Note 2)		
	54	FITTING PLUG	Hollow Plug		
OTHER	55	MATERIAL	ASTM A106 Gr.B (Note 4)		
	56	PROTECTIVE COVER	Required		
	57	RETRACTABLE TOOL	Required (Note 3)		
	58	SERVICE VALVE	Required (Note 3)		
	59	MANUFACTURE	will be finalized later		
	60	MODEL NO.	will be finalized later		
	61	TAG PLATE (General Note 12)	Required		
	62	WAKE FREQUENCY STANDARD (NOTE 2)	Required as per ASME PTC 19.3		

NOTES :	VTA : VENDOR TO ADVISE	VTC : VENDOR TO CONFIRM	N/A : NOT APPLICABLE
(1) All process data will be finalized later (2) Wake frequency analysis (stress calculation) according to ASME Power Test Code 19.3 shall be done & submitted by vendor. (3) One set of retriever and service valve is common to all CC's fittings. (4) Piping class, pipe schedule and materials related to Piping Material Specification, will be finalized after confirmation of this document. (5) High pressure access fitting to be supplied by vendor. (6) Length of stem holder for installation in 120 °clock due to liquid service, to be the way that measure the corrosion at the bottom of line.			