



نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

CALCULATION NOTE FOR CONTROL VALVE SIZING

نسخه	سریال	نوع مدرک	رشته	تسهیلات	صادرکننده	بسته کاری	پروژه
D08	0006	CN	PR	120	PEDCO	GCS	BK

شماره صفحه: 1 از 7

طرح نگهداشت و افزایش تولید 27 مخزن

CALCULATION NOTE FOR CONTROL VALVE SIZING

نگهداشت و افزایش تولید میدان نفتی بینک

D08	FEB.2024	AFD	M.Aryafar	M.Fakharian	S.Faramarzpour	
D07	OCT.2023	AFD	M.Aryafar	M.Fakharian	S.Faramarzpour	
D06	AUG.2023	AFD	M.Aryafar	M.Fakharian	A.M.Mohseni	
D05	APR.2023	AFC	M.Aryafar	M.Fakharian	A.Mohseni	
D04	DEC.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D03	JUL.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D02	APR.2022	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D01	DEC.2021	IFA	M.Aryafar	M.Fakharian	M.Mehrshad	
D00	SEP.2021	IFC	M.Aryafar	M.Fakharian	Sh.Ghalikar	
Rev.	Date	Purpose of Issue/Status	Prepared by:	Checked by:	Approved by:	Client Approval

Class: 2

CLIENT Doc. Number: F0Z-708744

Status:

IDC: Inter-Discipline Check
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction
AFP: Approved For Purchase
AFQ: Approved For Quotation
IFI: Issued For Information
AB-R: As-Built for CLIENT Review
AB-A: As-Built -Approved



نگهداشت و افزایش تولید میدان نفتی بینک
سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

CALCULATION NOTE FOR CONTROL VALVE SIZING

نسخه	سریال	نوع مدرک	رشته	تسهیلات	صادرکننده	بسته کاری	پروژه
D08	0006	CN	PR	120	PEDCO	GCS	BK

شماره صفحه: 2 از 7

REVISION RECORD SHEET

PAGE	D00	D01	D02	D03	D04	D05	D06	D07	D08
1	X	X	X	X	X	X	X	X	X
2	X	X	X	X	X	X	X	X	X
3	X	X				X			
4	X	X							
5	X								
6	X	X	X		X	X	X		X
7	X	X	X		X	X	X		
8	X		X		X	X	X		X
9	X		X		X	X			
10	X		X			X			
11	X		X			X			
12	X		X			X			
13	X		X			X			
14	X		X			X			
15	X		X			X			
16									
17									
18									
19									
20									
21									
22									
23									
24									
25									
26									
27									
28									
29									
30									
31									
32									
33									
34									
35									
36									
37									
38									
39									
40									
41									
42									
43									
44									
45									
46									
47									
48									
49									
50									
51									
52									
53									
54									
55									
56									
57									
58									
59									
60									
61									
62									
63									
64									
65									

PAGE	D00	D01	D02	D03	D04	D05	D07	D08
66								
67								
68								
69								
70								
71								
72								
73								
74								
75								
76								
77								
78								
79								
80								
81								
82								
83								
84								
85								
86								
87								
88								
89								
90								
91								
92								
93								
94								
95								
96								
97								
98								
99								
100								
101								
102								
103								
104								
105								
106								
107								
108								
109								
110								
111								
112								
113								
114								
115								
116								
117								
118								
119								
120								
121								
122								
123								
124								
125								
126								
127								
128								
129								
130								

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک																									
شماره پیمان: 053 – 073 – 9184	<table><tr><th colspan="8">CALCULATION NOTE FOR CONTROL VALVE SIZING</th></tr><tr><th>پروژه</th><th>بسته کاری</th><th>صادرکننده</th><th>تسهیلات</th><th>رشته</th><th>نوع مدرک</th><th>سریال</th><th>نسخه</th></tr><tr><td>BK</td><td>GCS</td><td>PEDCO</td><td>120</td><td>PR</td><td>CN</td><td>0006</td><td>D08</td></tr></table>	CALCULATION NOTE FOR CONTROL VALVE SIZING								پروژه	بسته کاری	صادرکننده	تسهیلات	رشته	نوع مدرک	سریال	نسخه	BK	GCS	PEDCO	120	PR	CN	0006	D08	شماره صفحه : 3 از 7
CALCULATION NOTE FOR CONTROL VALVE SIZING																										
پروژه	بسته کاری	صادرکننده	تسهیلات	رشته	نوع مدرک	سریال	نسخه																			
BK	GCS	PEDCO	120	PR	CN	0006	D08																			

CONTENTS

1.0	INTRODUCTION	4
2.0	SCOPE	5
3.0	NORMATIVE REFERENCES.....	5
3.1	LOCAL CODES AND STANDARD	5
3.2	INTERNATIONAL CODES AND STANDARDS	5
3.3	THE PROJECT DOCUMENTS.....	5
3.4	ENVIRONMENTAL DATA	5
3.5	ORDER OF PRECEDENCE	5
4.0	ABBREVIATIONS	5
5.0	CONTROL VALVE SIZING	6
5.1	SOFTWARE	6
5.2	CASE STUDY	6
5.3	SIZING	6
5.4	DETAILS OF CALCULATION RESULT	7
	ATTACHMENT 1	7

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک							
شماره پیمان:	CALCULATION NOTE FOR CONTROL VALVE SIZING							شماره صفحه : 4 از 7
053 – 073 – 9184	پروژه	بسته کاری	صادرکننده	تسهیلات	رشته	نوع مدرک	سریال	
	BK	GCS	PEDCO	120	PR	CN	0006	
							D08	

1.0 INTRODUCTION

Binak oilfield in Bushehr province is a part of the southern oilfields of Iran, is located 20 km northwest of Genaveh city.

With the aim of increasing production of oil from Binak oilfield, an EPC/EPD Project has been defined by NIOC/NISOC and awarded to Petro Iran Development Company (PEDCO). Also PEDCO (as General Contractor) has assigned the EPC-packages of the Project to "Hirgan Energy - Design and Inspection" JV.

As a part of the Project, a New Gas Compressor Station (adjacent to existing Binak GCS) shall be constructed to gather of 15 MMSCFD (approx.) associated gases and compress & transfer them to Siahmakan GIS.

GENERAL DEFINITION

The following terms shall be used in this document.

CLIENT:	National Iranian South Oilfields Company (NISOC)
PROJECT:	Binak Oilfield Development – Surface Facilities; New Gas Compressor Station
EPD/EPC CONTRACTOR (GC):	Petro Iran Development Company (PEDCO)
EPC CONTRACTOR:	Joint Venture of : Hirgan Energy – Design & Inspection(D&I) Companies
VENDOR:	The firm or person who will fabricate the equipment or material.
EXECUTOR:	Executor is the party which carries out all or part of construction and/or commissioning for the project.
THIRD PARTY INSPECTOR (TPI):	The firm appointed by EPC CONTRACTOR and approved by GC & CLIENT (in writing) for the inspection of goods.
SHALL:	Is used where a provision is mandatory.
SHOULD:	Is used where a provision is advisory only.
WILL:	Is normally used in connection with the action by CLIENT rather than by an EPC/EPD CONTRACTOR, supplier or VENDOR.
MAY:	Is used where a provision is completely discretionary.

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک																									
شماره پیمان: 053 – 073 – 9184	<table><tr><th colspan="8">CALCULATION NOTE FOR CONTROL VALVE SIZING</th></tr><tr><th>پروژه</th><th>بسته کاری</th><th>صادرکننده</th><th>تسهیلات</th><th>رشته</th><th>نوع مدرک</th><th>سریال</th><th>نسخه</th></tr><tr><td>BK</td><td>GCS</td><td>PEDCO</td><td>120</td><td>PR</td><td>CN</td><td>0006</td><td>D08</td></tr></table>	CALCULATION NOTE FOR CONTROL VALVE SIZING								پروژه	بسته کاری	صادرکننده	تسهیلات	رشته	نوع مدرک	سریال	نسخه	BK	GCS	PEDCO	120	PR	CN	0006	D08	شماره صفحه : 5 از 7
CALCULATION NOTE FOR CONTROL VALVE SIZING																										
پروژه	بسته کاری	صادرکننده	تسهیلات	رشته	نوع مدرک	سریال	نسخه																			
BK	GCS	PEDCO	120	PR	CN	0006	D08																			

2.0 SCOPE

The purpose of this document is to provide report for sizing of all control valves used in Gas Compressor station of Binak Plant.

3.0 NORMATIVE REFERENCES

3.1 Local Codes and Standard

IPS-E-IN-160	Engineering Standard for Control Valves
IPS-M-IN-160	Material Standard for Control Valves
IPS-E-PR-830	Process design of valves and control valves

3.2 International Codes and Standards

API RP 553	Refinery Valves and Accessories for Control and Safety Instrumented Systems
------------	---

3.3 The Project Documents

BK-GCS-PEDCO-120-PR-PF-0001	Process Flow Diagram (PFD)
BK-GNRL-PEDCO-000-PR-DB-0001	Process Basis of Design
BK-GNRL-PEDCO-000-PR-DC-0001	Process Design Criteria

3.4 ENVIRONMENTAL DATA

Refer to "Process Basis of Design"; Doc. No. Process Basis of Design BK-00-HD-000-PR-DB-0001

3.5 Order of Precedence

In case of any conflict between the contents of this document or any discrepancy between this document and other project documents or reference standards, this issue must be reported to the CLIENT. The final decision in this situation will be made by CLIENT.

4.0 ABBREVIATIONS

NISOC:	National Iranian South Oil Company
PFD:	Process Flow Diagram
P&ID:	Piping and Instrumentation Diagram

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک																									
شماره پیمان: 053 – 073 – 9184	<table><tr><th colspan="8">CALCULATION NOTE FOR CONTROL VALVE SIZING</th></tr><tr><th>پروژه</th><th>بسته کاری</th><th>صادرکننده</th><th>تسهیلات</th><th>رشته</th><th>نوع مدرک</th><th>سریال</th><th>نسخه</th></tr><tr><td>BK</td><td>GCS</td><td>PEDCO</td><td>120</td><td>PR</td><td>CN</td><td>0006</td><td>D08</td></tr></table>	CALCULATION NOTE FOR CONTROL VALVE SIZING								پروژه	بسته کاری	صادرکننده	تسهیلات	رشته	نوع مدرک	سریال	نسخه	BK	GCS	PEDCO	120	PR	CN	0006	D08	شماره صفحه : 6 از 7
CALCULATION NOTE FOR CONTROL VALVE SIZING																										
پروژه	بسته کاری	صادرکننده	تسهیلات	رشته	نوع مدرک	سریال	نسخه																			
BK	GCS	PEDCO	120	PR	CN	0006	D08																			

5.0 CONTROL VALVE SIZING

5.1 Software

- The software using for sizing control valves is Fisher.

5.2 Case Study

Three cases have been considered for control valve sizing:

- Case 1: Minimum operating flow is equal to 30% of normal operating flow (the lowest flow rate between two case,(summer / winter) considered as normal flow).
- Case 2: Normal operating flow.
- Case 3: Maximum operating flow is equal to 110% of normal operating flow. (the highest flow rate between two case (summer / winter) considered as normal flow).

Note: It should be noted that the special conditions, related to each control valve is taken into account.



5.3 SIZING

The below table contains the details sizing for the control vales that installed in GCS.

Table 5.1: Control Valve Sizing result										
NO	LINE SIZE	Valve No.	Normal Flow Rate Kg/hr	Normal Upstream Pressure (Barg)	Normal Downstream Pressure (Barg)	Calculated CV Min/Nor/Max	% Opening	Calculated SIZE (in)	Selected SIZE (in)	P&ID
1	6	FCV-2101	6564.1	6.5	5.5	28.43/95.15/104.85	39~65	4	4	BK-GCS-PEDCO-120-PR-PI-0002
2	8	FCV-2102	11269.0	6.5	5.5	50.13/166.85/188.06	33~63	6	6	BK-GCS-PEDCO-120-PR-PI-0003
3	3	FCV-2111	7158.0	19.5	18.5	3.43/9.81/10.80	35~69	2	2	BK-GCS-PEDCO-120-PR-PI-0004(2/2)
4	2	LCV-2114	1017.8	5.3	1.0	0.186/0.619/0.681	32~72	1.5	1.5	BK-GCS-PEDCO-120-PR-PI-0005
5	6	PCV-2135 A/B/C	8664.0	54.1	0.5	2.75/10.132/11.145	25~54	4	4	BK-GCS-PEDCO-120-PR-PI-0011(1,2,3 OF 3)
6	6	PCV-2151	17170.8	52.9	51.9	26.124/87.64/96.547	37~64	4	4	BK-GCS-PEDCO-120-PR-PI-0013(1/3)
7	4	PCV-2152	17170.8	52.9	0.5	5.956/21.585/26.114	35~68	3	3	BK-GCS-PEDCO-120-PR-PI-0013(1/3)
8	1.5	PCV-2201	38.8	9.0	4.5	0.077/0.255/0.281	43~65	1	1	BK-GCS-PEDCO-120-PR-PI-0015(1/2)
9	2	PCV-2211	38.6	8.0	7.5	0.204/0.684/0.752	35~75	1.5	1.5	BK-GCS-PEDCO-120-PR-PI-0016(1/2)
10	3	PCV-2272	505.8	5.1	4.9	5.206/17.423/19.182	41~78	2	2	BK-GCS-PEDCO-120-PR-PI-0022
11	1	PRV-2161	15.4	0.05	0.0	0.601/2.49/2.739	27 ~ 61	1	1	BK-GCS-PEDCO-120-PR-PI-0014
12	1	PRV-2162	17.9	7.5	0.01	0.058/0.160/0.176	48~74	1	1	BK-GCS-PEDCO-120-PR-PI-0014
13	2	PRV-2201	118.9	9.0	8.0	0.427/1.425/1.853	25~52	1.5	1.5	BK-GCS-PEDCO-120-PR-PI-0015(2/2)
14	1	PRV-2291	4.5	7.5	0.01	0.005/0.032/0.035	40~70	1	1	BK-GCS-PEDCO-120-PR-PI-0025
15	1	PRV-2292	6.9	0.05	0.00	0.119/ 1.122/ 1.234	31~72	1	1	BK-GCS-PEDCO-120-PR-PI-0025

NOTE 1:Control Valve Size Will Be Considered Based On Letter No. 02/2294/127226 (attachment no.2)

NOTE 2: Control Valve Size Will Be Finalized By Vendor

 NISOC	نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک																									
شماره پیمان: 053 - 073 - 9184	<table><tr><th colspan="8">CALCULATION NOTE FOR CONTROL VALVE SIZING</th></tr><tr><th>نسخه</th><th>سریال</th><th>نوع مدرک</th><th>رشته</th><th>تسهیلات</th><th>صادرکننده</th><th>بسته کاری</th><th>پروژه</th></tr><tr><td>D08</td><td>0006</td><td>CN</td><td>PR</td><td>120</td><td>PEDCO</td><td>GCS</td><td>BK</td></tr></table>	CALCULATION NOTE FOR CONTROL VALVE SIZING								نسخه	سریال	نوع مدرک	رشته	تسهیلات	صادرکننده	بسته کاری	پروژه	D08	0006	CN	PR	120	PEDCO	GCS	BK	شماره صفحه : 7 از 7
CALCULATION NOTE FOR CONTROL VALVE SIZING																										
نسخه	سریال	نوع مدرک	رشته	تسهیلات	صادرکننده	بسته کاری	پروژه																			
D08	0006	CN	PR	120	PEDCO	GCS	BK																			

5.4 DETAILS OF CALCULATION RESULT



ATTACHMENT 1

(SOFTWARE RESULT)

ATTACH MENT2

Letter No. 02/2294/127226