



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

شماره پیمان: 9184 – 073 – 053

PMR FOR F&G SYSTEM								l
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	IN	MR	0003	D01	

شماره صفحه: 1 از 20

طرح نگهداشت و افزایش تولید 27 مخزن

PMR FOR F&G SYSTEM

نگهداشت و افزایش تولید میدان نفتی بینک

						,
D01	JUL. 2024	IFI	P.Hajisadeghi	M.Fakharian	M.Sadeghian	
D00	AUG. 2023	IFI	P.Hajisadeghi	M.Fakharian	A.M.Mohseni	
Rev.	Date	Purpose of Issue/Status	Prepared by:	Checked by:	Approved by:	CLIENT Approval

Class: 3 CLIENT Doc. Number: F0Z-709271

Status:

IDC: Inter-Discipline Check
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction
AFP: Approved For Purchase
AFQ: Approved For Quotation
IFI: Issued For Information
AB-R: As-Built for CLIENT Review
AB-A: As-Built —Approved



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



، پیمان:	شماره
----------	-------

053 - 073 - 9184

PMR FOR F&G SYSTEM							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	IN	MR	0003	D01

شماره صفحه: 2 از 20

REVISION RECORD SHEET

PAGE	D00	D01	D02	D03	D04
1	Х	Х			
2	Х	X			
3	X	X			
4	X	Х			
5	X	Х			
<u>6</u>		X			
<u>7</u> 8	X				
9	X	Х			
10	X	Χ			
11	Х				
12	X				
13	Х	X			
14	X	X			
15	X	X			
16 17	X	X			
18	^	X			
19					
20					
21					
22					
23					
24					
25					
26					
27					
28 29					
30					
31					
32					
33					
34					
35					
36					
37					
38					
39 40					
40 41					
42					
43					
44					
45					
46					
47	-				
48					
<u>49</u>					
<u>50</u>	1				
51 52	-				
53	1				
54					
55	İ				
56					
57					
58					
59	-				
60					
61				1	-
62					
63 64	1				
65	1				-

PAGE	D00	D01	D02	D03	D04
66					
67					
68 69					
70					
71					
72					
73 74					
75					
76					
77					
<u>78</u>					
79 80					
81					
82					
83					
84 or	1		-		-
85 86			<u> </u>		
87					
88					
89					
90 91					
91					
93					
94					
95					
96 97					
98					
99					
100					
101					
102 103					
104					
105					
106					
107					
108 109					
110					
111					
112			-		_
113 114			 		
115					
116					
117			ļ		
118	1		-		-
119 120			 		
121					
122					
123			1		ļ
124			-		_
125 126			-		
126			t		t
128					
129					
130					L





احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

:	پیمان:	شماره
053 – 073 –	918	4

PMR FOR F&G SYSTEM							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	IN	MR	0003	D01

شماره صفحه: 3 از 20

CONTENTS

1.0	INTRODUCTION	4
2.0	GENERAL	5
3.0	REFERENCE / ATTACHED DOCUMENTS	5
4.0	SUBJECT OF THE SUPPLY	5
5.0	LIMITS OF SUPPLY	6
5.1 5.2	THE VENDOR'S SCOPE OF ENGINEERING	
5.1.1	Spare parts	8
5.1.2	OTHER ITEMS	9
5.3 5.4 5.5	EXCLUSIONS	9
6.0	INSPECTION AND TESTS	9
7.0	VENDOR DOCUMENTATION REQUIREMENTS & SCHEDULE	10
8.0	VENDOR RESPONSIBILITY	10
9.0	GUARANTEE AND WARRANTY	11
10.0	DEVIATION	11
11.0	PRICE BREAKDOWN	12
ATTAC	CHMENT 1	13
ATTAC	CHMENT 2	14
VEN	IDOR DOCUMENTS MIN. REQUIREMENT	14
ATTAC	CHMENT 3	19
ATTAC	CHMENT 4	20



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



	شماره پیمان:
053	073_9184

PMR FOR F&G SYSTEM							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	IN	MR	0003	D01

شماره صفحه: 4 از 20

1.0 INTRODUCTION

Binak oilfield in Bushehr province is a part of the southern oilfields of Iran, is located 20 km northwest of Genaveh city .

With the aim of increasing production of oil from Binak oilfield, an EPC/EPD Project has been defined by NIOC/NISOC and awarded to Petro Iran Development Company (PEDCO). Also PEDCO (as General Contractor) has assigned the EPC-packages of the Project to "Hirgan Energy - Design and Inspection" JV.

As a part of the Project, a New Gas Compressor Station (adjacent to existing Binak GCS) shall be constructed to gather of 15 MMSCFD (approx.) associated gases and compress & transfer them to Siahmakan GIS.

GENERAL DEFINITION

The following terms shall be used in this document.

D01

CLIENT: National Iranian South Oilfields Company (NISOC)

PROJECT: Binak Oilfield Development – Surface Facilities; New

Gas Compressor Station.

EPD/EPC CONTRACTOR (GC): Petro Iran Development Company (PEDCO)

EPC CONTRACTOR/PURCHSER: Joint Venture of: Hirgan Energy – Design & Inspection

(D&I) Companies

VENDOR: The firm or person who will fabricate or supply the

equipment or material.

SUB VENDOR: The firm or person who will have a direct contract with

the Vendor or another Subvendor to perform a part or

parts of the Work

EXECUTOR: Executor is the party which carries out all or part of

construction and/or commissioning for the project.

THIRD PARTY INSPECTOR (TPI): The firm appointed by EPD/EPC CONTRACTOR

(GC) and approved by CLIENT (in writing) for the

inspection of goods.

SHALL: Is used where a provision is mandatory.

SHOULD: Is used where a provision is advisory only.

WILL: Is normally used in connection with the action by

CLIENT rather than by an EPC/EPD CONTRACTOR,

or VENDOR.

MAY: Is used where a provision is completely discretionary.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

PMR FOR F&G SYSTEM							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سر يال	نسخه
BK	GCS	PEDCO	120	IN	MR	0003	D01

شماره صفحه: 5 از 20

2.0 GENERAL

- This document presents the item material requisitions for Contractor's use as appropriate.
- This material requisition covers the requirements for the design, manufacturing, testing and supply of FACP as listed in section 4. All equipment/devices/items shall conform to this requisition and all specifications which have been mentioned in attachment 1 of this material requisition.

3.0 REFERENCE / ATTACHED DOCUMENTS

- a. Specified documents in attachment 1 shall be considered as a part of this material Requisition.
- **b.** All codes and standards which have been referenced in above mentioned specs shall be considered.
- **c.** In case of any conflict between the contents of this document or any discrepancy between this document and other project documents or reference standards, this issue must be reported to the CLIENT. The final decision in this situation will be made by CLIENT.
- d. Deviations

Any exceptions/clarifications to codes/standards and specifications listed in attachment 1 must be clearly stated in a separate dedicated section of the proposal in the format submitted in attachment 3.

The proposed deviations/comments list shall include as minimum:

- Reference for the involved specification, chapter and paragraph.
- Technical justification for the non-compliance.
- Detailed description of the proposed alternative.

If no exceptions or clarifications exist, either for the complete referenced document or an individual paragraph, the VENDOR shall be considered to be in full compliance with the relevant document.

The VENDOR may propose materials of equivalent or better quality compared to those indicated in the equipment data sheet. Even these cases shall be duly included/technically supported in the deviations/clarifications list.

4.0 SUBJECT OF THE SUPPLY

Vendor scope of works and services are design, modifying, inspection, testing & delivery of required F&G system and FACP equipment for connecting to building detectors. The vendor shall include in the supply, all other equipment/devices/items not listed in the following, but necessary for a good design and a safe operation, taking into account process data and installation conditions such as area classification and climatic conditions.

The grade of shop assembly of the equipment/devices/items supplied shall be at maximum extent to facilitate site erection and pre-commissioning activities.

The vendor's supply shall include:



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

PMR FOR F&G SYSTEM							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	IN	MR	0003	D01

شماره صفحه: 6 از 20

No.	Item	Description	QTY. (Set)
1.	F&G SYS. and Marshalling cabinet	F&G System (including marshaling and system cabinets) for signals of GCS, SIL 3 PLC Based AS Per BK-GNRAL-PEDCO-000-IN-SP-0012 Doc No:" BK-GNRAL-PEDCO-000-IN-SP-0012" & I/O List For F&G Systems Doc No:" BK-GCS-PEDCO-120-IN-LI-0004"	1
2.	FACP	Fire Alarm Control Panel For GCS Area Buildings.	1
3.	F&G Matrix Panel	Fire & Gas Matrix Panel for GCS Area Buildings As Per Data Sheets For ESD Console/F&G Matrix Panel	1
4.	F&G Engineering/Operator Workstation	F&G Engineering/Operator Workstation with 32" LED/LCD Monitor & Required accessories including required HMI software and Software Licenses.	1
5.	Other required accessories	Accessories like cabinets, power supplies (if required), terminals, ducts, wires, relays and barriers, and other in GCS Area Buildings based on the project documents specially reference documents listed in the attachment 1.	1
6.	LAPTOP	F&G maintenance Laptop as per project Specification including required software and Software Licenses	
7.	Software license	All required software licenses shall be prepared as per attached document.	1

5.0 LIMITS OF SUPPLY

5.1 THE VENDOR'S SCOPE OF ENGINEERING



Scope of Engineering services includes all items specified in documents, mentioned in "LIST OF REFRENCE / APPLICABLE DOCUMENTS included in Attachment 1, but not limited to the followings:



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



;	پیمان:	شماره
053 – 073 –	918	4

PMR FOR F&G SYSTEM								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	IN	MR	0003	D01	

شماره صفحه: 7 از 20

- Design, Engineering and Documentation Drawings, documentation and certification in accordance with section 8.0 of this requisition
- Project management including coordination with all Package Suppliers/Vendors and other subsystems Vendors.
- Systems' hardware engineering studies including:
 - System sizing
 - System architecture specification
 - System cabinets design and arrangement
 - Etc.
- Systems' software engineering including:
 - F&G System functional design specifications
 - I/O segregation and assignment
 - Control strategy and typical I/O loop specification
 - F&G System communication interface database definition
 - Specification of communication interfaces with other subsystems including coordination with subsystems' Vendors
 - Standard, graphic displays and report definition
 - Ftc
- Marshaling cabinets' engineering studies
- Distribution cabinets' engineering studies
- F&G Matrix engineering studies
- F&G System Marshaling / Distribution cabinets and F&G Matrix hardware and software factory acceptance tests.
- System integration tests (including wiring and logic/function test as per BK-GNRAL-PEDCO-000-IN-SP-0003)
- On site erection supervision, pre-commissioning, commissioning and start up assistance.
- F&G System Engineer daily assistance (on site).
- F&G System hardware technician daily assistance (on site).
- Training for F&G System shall be according to project documents (BK-GNRAL-PEDCO-000-IN-SP-0003)
- Transportation to Site (including insurance)
- Packing, marking, preparation for shipment, and delivery

5.2 SCOPE OF SUPPLY

The VENDOR shall assume overall responsibility for the design, manufacture, assembly, test and performance of all equipment/devices/items supplied as indicated in this requisition. This shall include, but not be limited to:

- Resolve engineering issues relating to equipment/devices/items within the scope of supply.
- Provide detailed design and documentation of all equipment/devices/items and components within the scope of supply in accordance with attachment 2 of this document.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:
053 - 073 - 9184

PMR FOR F&G SYSTEM							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سر يال	نسخه
BK	GCS	PEDCO	120	IN	MR	0003	D01

شماره صفحه: 8 از 20

- Provide all necessary information documents in order to allow the contractor to erect, install and verify the proposed equipment/devices/items.
- · Implement a quality assurance plan
- The quality plan applied to the scope of supply shall include:
 - QA/QC Organization Chart and procedures that shall be submitted for approval.
 - Plan for HOLD points in the production process proposed to CLIENT/EPC CONTRACTOR for witness or approval particular activities.
 - Production schedule indicating main quality manufacturing processes, inspection and tests.
 - Qualification of all personnel performing tests to be reviewed by the inspector
 - Vendor shall also provide the description of the following quality activities:
 - Sub vendors' products quality
 - Quality check and identification of the materials and equipment entering in their manufacturing shop.
- · Calibration of test instruments and equipment
- · Provide detailed specifications and data sheets.
- The VENDOR shall take the full responsibility for the whole package control/protection system and shall be responsible for SAT and commissioning of the package.

5.1.1 SPARE PARTS

- The Vendor shall provide certain quantities of consumable for the installation, precommissioning, commissioning, Start-up and up to the end of the guarantee period.
- The quantities shall be estimated by Vendor and shall be based upon the Vendor's experience. The following two periods shall be taken into account:
 - Pre-commissioning and commissioning period where the consumption of consumable is greater
 - Normal use of the System
- The VENDOR shall provide lists of recommended spare parts, which shall include the original part numbers with prices for commissioning, start-up and two years operation. All spare parts shall be identified individually.
- Spare parts for commissioning and start-up; a qualified and complete list based on PROJECT SPARE PART SUPPLY PROCEDURE (Doc. No. E&C-QC-SP-1).
- Spare parts for two years operation; a qualified and complete list based on PROJECT SPARE PART SUPPLY PROCEDURE (Doc. No. E&C-QC-SP-1).
- The VENDOR shall be able to provide spares back up and support for the plant life of at least 20 years.
- SPIR form shall be approved by CLIENT prior to procurement.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:
053 - 073 - 9184

PMR FOR F&G SYSTEM							
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	IN	MR	0003	D01

شماره صفحه: 9 از 20

5.1.2 OTHER ITEMS

· Name plate

5.3 EXCLUSIONS

No exclusion is applicable.

5.4 BATTERY LIMITS

No battery limit is applicable.

5.5 OTHER ITEMS



- Special tools required for installation and maintenance (a qualified and complete list has to be included in the bid documentation)
- Noise acoustic protection and relevant ancillaries in order to match with max. noise level requirements (if necessary)
- Spreader bars for lifting of the panels (if necessary)
- Name plate
- Earthing plate
- Painting of all cabinet in accordance with "Specification for Control Panels and System Cabinets Doc. No. BK-GNRAL-PEDCO-000-IN-SP-0011"
- Preparation for shipment
- Packing for sea freight transportation
- Shop inspections and testing as per specification
- Free access to manufacturing plants for the PURCHASER's inspectors
- Certificates or declarations of conformance (as required) Daily rate for erection supervision (separate price)
- Daily rate for commissioning and start-up supervision (separate price)
- Training for customer's personnel (refer to BK-GNRAL-PEDCO-000-IN-SP-0003)
- All required meeting at Vendor shop/office including but not limited to:
 - KOM
 - Technical/Clarification meeting
 - Pre-Inspection Meeting

6.0 INSPECTION AND TESTS

The equipment shall be inspected and tested in accordance with the Inspection &Test plan (ITP) issued by the vendor and approved by the CLIENT and EPC CONTRACTOR before the award of the order. The Inspection & Test plan (ITP) shall be at least according to the Commodity



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان: 9184 – 053 – 053

PMR FOR F&G SYSTEM								
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	IN	MR	0003	D01	

شماره صفحه: 10 از 20

Procurement and Manufacturing Inspection Instruction (Docs. Nos. ICE-EID-MI-SP01-Rev01), Inspection Level of Commodity and Equipment (Docs. Nos. ICE-EID-MI-SP02-Rev01) and Data Sheets. The vendor shall in any case conduct all the tests required by contractual documents, specifications, codes and standards, manufacturer standard quality system and keep the relevant documentation. All required manufacturing and function test/inspection also Factory Acceptance Test /Site Acceptance Test and Quality Assurance requirements shall be considered in vendor responsibility as per project specification.

7.0 VENDOR DOCUMENTATION REQUIREMENTS & SCHEDULE

- Vendor document shall be according to attachment 2 of this document.
- All documents, preliminary or final, are to be stamped and signed by the VENDOR.
- Failure in dispatch of the required documents shall cause the supply to be considered as unfulfilled.
- EPC CONTRACTOR 's approval does not relieve vendor, in any way, from his obligation to fulfill the requirements of the purchase order documents.
- All vendor drawings and documents shall be in English language.

All drawings and documents are to be identified as per clause 1 "GENERAL DEFINITION"

8.0 VENDOR RESPONSIBILITY



VENDOR shall be responsible for the design, engineering, co-ordination, supply, delivery, testing, final check-out and satisfactory operation of the equipment/devices/items. The engineering coordination also includes responsibility for handing and expediting drawings.

Preparation of complete final book, Training courses (as per BK-GNRAL-PEDCO-000-IN-SP-0003) and assistance during Pre-Commissioning/Commissioning/Startup are also in VENDOR responsibility as per project specification.

Also, VENDOR shall be responsible for ensuring that all relevant information and documentation is passed on the sub-VENDORs.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان: 9184 – 053 – 053

 PMR FOR F&G SYSTEM

 سریال
 نوع مدر ک
 رشته
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 IN
 MR
 0003

شماره صفحه: 11 از 20

نسخه

D01

9.0 GUARANTEE AND WARRANTY

All material and Equipment/Devices/Items in VENDOR's scope of work/supply shall be guaranteed by VENDOR.

The guarantee period shall be eighteen (18) months from the date of delivery or twelve (12) months from the installation date of each equipment/packages at site

VENDOR shall guarantee the performance of supplied items.

VENDOR shall guarantee that the Equipment/Device/Item is suitable for the operating conditions herein specified, and that all materials and components are free from any defects; verifications of all calculations are in VENDOR's responsibility.

VENDOR shall unconditionally guarantee the materials and workmanship of all material and/or services. If, within the guarantee period, any defects occur which are due to faulty material and/or services included in his scope (design, manufacturing, inspection, testing, supply & etc.), VENDOR shall, at his own expense, repair or adjust the condition, or replace the material and/or services to the complete satisfaction of CLIENT's representative. These repairs, replacement or adjustments shall be made only at such time as will be least detrimental to the operation of the CLIENT's business.

VENDOR warrants promptly repairing or replacing the defective parts in the warranty period.

Vendor shall ensure a correct and safe operation of the unit, providing all safety protection Devices.

Vendor shall be responsible for the safe, reliable, continuous functioning of the Equipment/Devices/Items.

VENDOR is fully responsible for the design of package for correct and safe operation based on project requirement during package life time; therefore, VENDOR shall specify any documents/specifications which may be required for design, manufacture and finalizing of Equipment/Devices/Items to avoid any problems during the package operation at site before P.O; otherwise, VENDOR shall be hold responsible for any corresponding deviation from expectations from the Equipment/Devices/Items.

10.0 DEVIATION

VENDOR's proposal shall be prepared in strict compliance with the requirements set forth in the relevant specifications of tender documents.



نگهداشت و افزایش تولید میدان نفتی بینک

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

پروژه

BK

GCS

PMR FOR F&G SYSTEM بسته کاری صادر كننده تسهيلات PEDCO

سر يال نسخه رشته نوع مدرك 120 IN MR 0003 D01 شماره صفحه: 12 از 20

VENDOR shall include in his proposal the statement of compliance with the tender documents should VENDOR wish to submit exception to the requirements of tender documents. They shall be submitted for CLIENT's approval.

11.0 PRICE BREAKDOWN

Breakdown price of following items shall be included in the proposal, as well as total price.

- 1) Material and Fabrication for each Section Separately
- 2) Pre-commissioning & commissioning spare parts (E&C-QC-SP-1)
- 3) 2 years operational spare parts (E&C-QC-SP-1)
- 4) Packing & transportation



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



	پیمان.	اره
053 – 073	-918	4

PMR FOR F&G SYSTEM								ĺ
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	
BK	GCS	PEDCO	120	IN	MR	0003	D01	

شماره صفحه: 13 از 20

ATTACHMENT 1



LIST OF REFERENCE / APPLICABLE DOCUMENTS

No.	Document No. Document Title		Rev.
Instr	ument		
1.	BK-GNRAL-PEDCO-000-IN-SP-0012	Specification For Fire & Gas System	D03
2.	BK-GCS-PEDCO-120-IN-DC-0001	Fire & Gas Detection Design Criteria	D06
3.	BK-GCS-PEDCO-120-IN-DG-0009	F&G Cause and Effect Diagram for Process Area	D03
4.	BK-GCS-PEDCO-120-IN-DG-0010	F&G Cause and Effect Diagram for Building	D01
5.	BK-GCS-PEDCO-120-IN-DG-0008	Instrument & F&G Junction Box Termination Diagram	D03
6.	BK-GCS-PEDCO-120-IN-LI-0009	Instrument /F&G Cable List	D03
7.	BK-GCS-PEDCO-120-IN-LI-0004	I/O List For F&G Systems	D04
8.	BK-GCS-PEDCO-120-IN-LI-0005	Panels & Junction Box List	D04
9.	BK-GCS-PEDCO-120-IN-BD-0001	Control/F&G SYSTEM/F&G System Block Diagram Configuration	D08
10.	BK-GCS-PEDCO-120-IN-PY-0001	Control Room Layout & Arrangement Drawing	D04
11.	BK-GCS-PEDCO-120-IN-DT-0017	Data Sheets For F&G SYSTEM Console/F&G Matrix Panel	D03
12.	BK-GCS-PEDCO-120-IN-PY-0005	F&G Location Layout for Process Area	D03
13.	BK-GCS-PEDCO-120-IN-PY-0006	F&G Location Layout for Buildings	D02
		Process	
14.	BK-GNRAL-PEDCO-000-PR-DB-0001	Process Basis of Design	D08
15.	BK-GCS-PEDCO-120-PR-PH-0002	Control Philosophy	D02
		General	
16.	ICE-EID-MI-SP01-Rev01	دستورالعمل بازرسی، خرید و ساخت کالا	D01
17.	ICE-EID-MI-SP02-Rev01	دستورالعمل انتخاب سطح بازرسی کالا و تجهیزات	D01
18.	E&C-QC-SP-1	دستورالعمل تامین قطعات یدکی راه اندازی وراهبری دو سالانه	D00
19.	BK-GNRAL-PEDCO-000-QC-PR-0022	Specification For Final Data Book (FDB) Requirements	D00
20.	BK-GNRAL-PEDCO-000-QC-PR-0045	Packing, Marking, Transportation Procedure	D00

**NOTE: THE LATEST REVISION OF PROJECT DOCUMENT IN ATTACHMENT 1 TO BE CONSIDERED AS REFERENCE BY VENDOR.



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک




شماره پیمان: 9184 – 073 – 053

	PMR FOR F&G SYSTEM									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سر يال	نسخه			
BK	GCS	PEDCO	120	IN	MR	0003	D01			

شماره صفحه: 14 از 20

ATTACHMENT 2

VENDOR DOCUMENTS MIN. REQUIREMENT



		WITH BID		AFTER ORDERING					
NO.	DESCRIPTION	Q./TYPE (1)	Q./TYPE (1)	DELIVERY DATE (2)	PURPOSE (3)	FINAL ISSUE	FINAL INSPECTION (4)		
		MANAGE	MENT						
1	Vendor Document Index and Schedule	4N	6C+E	2W	Α	6C+E	X		
2	Organization Brief	4N	6C+E	2W	1	6C+E			
3	Schedule Level 1, 2, 3 & 4 showing Engineering, Procurement, Fabrication, Inspection, Testing, and Delivery Plan.	4N	6C+E	3W	А	6C+E	X		
4	Physically Progress Report (Every 2 Weeks))		6C+E	2W					
5	Project Organization Chart	4N	6C+E	2W			X		
6	Reference List	4N	6C+E	2W	1	6C+E			
7	Vendor Catalogue	4N	6C+E	2W	I	6C+E	X		
		QUAL	ITY						
8	Quality Assurance Manual /Quality Management System Certificate / Quality Control Plan (according to latest rev. of ISO)	4N	6C+E		А	6C+E			
9	Preliminary Inspection and Test Plan	4N	6C+E						
10	Inspection and Test Plan	4N	6C+E	3W	А	6C+E			
		HSI	Ē						
11	HSE Procedure		6C+E	4W	А	6C+E	X		
		ENGINE	ERING						
12	VENDOR Document Schedule	4N	6C+E	4W	А	6C+E	X		
13	Power Consumption List	4N	6C+E	4W	А	6C+E	X		
14	Detailed Devices Catalogues	4N	6C+E	4W	Α	6C+E	X		



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان: 9184 – 073 – 053

پروژه

BK

 PMR FOR F&G SYSTEM

 نسخه سریال نوع مدر ک رشته سیبلات صادر کننده بسته کاری

 GCS
 PEDCO
 120
 IN
 MR
 0003
 D01

شماره صفحه: 15 از 20

		WITH BID		AFTER OF	RDERING		AT THE FINAL
NO.	DESCRIPTION	Q./TYPE (1)	Q./TYPE (1)	DELIVERY DATE (2)	PURPOSE (3)	FINAL ISSUE	INSPECTION (4)
15	Equipment List and Cabinet Bill Of Material		6C+E	4W	Α	6C+E	X
16	Control System Software Catalogue	4N	6C+E	4W	Α	6C+E	X
17	Software System - Specifications		6C+E	4W	Α	6C+E	
18	Hardware System - Specifications		6C+E	4W	А	6C+E	
19	Loop Diagrams		6C+E	4W	Α	6C+E	Х
20	I/O assignment		6C+E	4W	Α	6C+E	
21	Graphic Pages printout		6C+E	4W	Α	6C+E	Х
22	System Architecture and Network	4N	6C+E	4W	Α	6C+E	X
23	Cable Termination's/Connection Diagrams		6C+E	4W	А	6C+E	Х
24	Panel/F&G SYSTEM Console Layout		6C+E	4W	Α	6C+E	X
25	Power Distribution Diagram		6C+E	4W	А	6C+E	X
26	System Software/logic printout		6C+E	4W	Α	6C+E	X
27	Earthing Diagram		6C+E	4W	А	6C+E	
28	Reliability/Availability/FEMA Report		6C+E	4W	А	6C+E	
29	MODBUS Mapping List		6C+E	4W	А	6C+E	Х
		PROCUR	EMENT				
30	List of Sub-Vendors (table giving: part of equipment, tag no., sub-vendor reference)	4N	6C+E	4W	Α	6C+E	
31	Unpriced copy of sub-orders	4N	6C+E	4W	1	-	
32	Packing Spec. / Shipping Schedule	4N	6C+E	4W	I	-	
33	Weight List/ Shipping List	4N	6C+E	4W	1	6C+E	
34	Mechanical & Performance Guarantees	4N	6C+E	4W	1	-	
		TESTI	NG				
35	Manufacturing, Test & Inspection Procedures	4N	6C+E	4W	А	6C+E	X
36	Performance & Functional Test Procedure		6C+E	4W	A	6C+E	X
37	Factory Acceptance Test (FAT) Procedure		6C+E	4W	А	6C+E	X



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

PMR FOR F&G SYSTEM

053 - 073 - 9184

	FINIT FOR FAG STSTEIN									
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه			
BK	GCS	PEDCO	120	IN	MR	0003	D01			

شماره صفحه: 16 از 20

		WITH BID		AFTER OF	RDERING		AT THE FINAL
NO.	DESCRIPTION	Q./TYPE (1)	Q./TYPE (1)	DELIVERY DATE (2)	PURPOSE (3)	FINAL ISSUE	INSPECTION (4)
38	Site Acceptance Test (SAT) Procedure		6C+E	4W	А	6C+E	X
	RECORDS	, REPORTS	& CERT	FICATES			
39	Material Conformity Certificate		6C+E	4W	1	6C+E	X
40	Testing Authority Approval Certificate		6C+E	4W	I	6C+E	Х
41	Hazardous Area Certificates.		6C+E	4W	I	6C+E	Х
42	Conformity Certificates (subvendor/equipment)		6C+E	4W	_	6C+E	×
43	Material Certificates Identification Diagram. (cross-reference material location; certificates for critical components)		6C+E	4W	Ī	6C+E	X
44	FAT Test Report / Certificates		6C+E	4W	Α	6C+E	
45	Pre-FAT Report		6C+E	4W	А	6C+E	
46	Performance Test Report / Certificates		6C+E	4W	Α	6C+E	X
47	Material Test Certificates		6C+E	4W	İ	6C+E	X
48	Surface Preparation & Coating Reports		6C+E	4W	А	6C+E	
49	Test & Inspection Reports		6C+E	4W	Α	6C+E	
50	Rust Prevention Report		6C+E	4W	Α	6C+E	
51	IP Certificate		6C+E	4W	Α	6C+E	
52	EX Certificate		6C+E	4W	Α	6C+E	
53	Conformity Certificates (sub- VENDOR/equipment)		6C+E	4W	А	6C+E	
		INSTALL	ATION				
54	Sub-Assembly Documentation		6C+E	4W	Α	6C+E	
55	Sub-Assembly Drawings		6C+E	4W	А	6C+E	
56	Erection/Installation Manual (if required)		6C+E	4W	Α	6C+E	
57	Handling, Transportation & Storage Instructions	4N	6C+E	4W	А	6C+E	
58	Unpacking & Inspection Instructions		6C+E	4W	А	6C+E	
59	Name Plate Documents		6C+E	4W	Α	6C+E	
60	Preliminary Packing List		6C+E	4W	А	6C+E	
61	Packing List		6C+E	4W	А	6C+E	







شماره پیمان: 9184 – 073 – 053

	PMR FOR F&G SYSTEM									
نسخه سریال نوع مدرک رشته تسهیلات صادر کننده بسته کاری پروژه										
BK	GCS	PEDCO	120	IN	MR	0003	D01			

شماره صفحه: 17 از 20

		WITH BID		AFTER OF	RDERING		AT THE FINAL
NO.	DESCRIPTION	Q./TYPE (1)	Q./TYPE (1)	DELIVERY DATE (2)	PURPOSE (3)	FINAL ISSUE	INSPECTION (4)
	OPER	ATION & M	AINTENA	NCE			
62	Operating Instructions		6C+E	4W	Α	6C+E	
63	Maintenance Instructions		6C+E	4W	Α	6C+E	
64	Commissioning & Start-up Manual		6C+E	4W	Α	6C+E	
65	List of Spare Parts Commissioning & Start-up	4N	6C+E	4W	A	6C+E	
66	List of Spare Parts 2 Years Operation	4N	6C+E	4W	Α	6C+E	
67	List of Special Tools	4N	6C+E	4W	Α	6C+E	
68	Consumables List		6C+E	4W	А	6C+E	
		OTHE	RS				
69	Vendor Final Book Index		6C+E	4W	Α	6C+E	X
70	Vendor Final Book		6C+E	4W	А	6C+E	X
71	All others documents (if required) will be listed in the order		6C+E	4W	Α	6C+E	

NOTES:

- *** The electronic file (Native/PDF) and Hardcopy version shall be provided in all stages by vendor.
- (1) Q: QUANTITY, TYPE: C = COPY, R = REPRODUCIBLE, P = POLYESTER, M = MICROFILM, E = ELECTRONIC, N = NUMBER OF DOCUMENT
- (2) W = CONSECUTIVE CALENDAR WEEK, M = CONSECUTIVE CALENDAR MONTH
- (3) A = FOR APPROVAL I = FOR INFORMATION
- (4) X = DOCUMENTS TO BE SUBMITTED AT THE FINAL INSPECTION
- (5) MECHANICAL CATALOGUE INCLUDING FINAL DRAWINGS/DOCUMENTS, UNPRICED PURCHASE ORDER & SUB- PURCHASE ORDER, MAINTENANCE DOSSIER ETC.
- (6) ALL DOCUMENTS AND/OR DRAWINGS FOR THIS PROJECT SHALL ALSO BE SUBMITTED IN THE ELECTRONIC FILES BY

USING THE FOLLOWING SOFTWARE.

MS OFFICE WORD 2013 OR UPPER VERSION (ENGLISH) FOR WORD PROCESSING MS OFFICE EXCEL 2013 OR UPPER VERSION (ENGLISH) FOR SPREAD SHEET AUTO CAD 2005 (ENGLISH) FOR DRAWING

(7) IN ORDER TO DESIGN AND MANUFACTURE THE INSTRUMENTS, VENDOR SHALL CONSIDER THE SEISMIC FACTOR,







شماره پیمان:

053 - 073 - 9184

	PMR FOR F&G SYSTEM										
پروژه	بسته کاری	صادر كننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه				
BK	GCS	PEDCO	120	IN	MR	0003	D01				

شماره صفحه: 18 از 20

		WITH BID		AFTER O	RDERING		AT THE FINAL
NO.	DESCRIPTION	Q./TYPE (1)	Q./TYPE (1)	DELIVERY DATE (2)	PURPOSE (3)	FINAL ISSUE	INSPECTION (4)

SUITABLE FOR SEISMIC UBC 97 ZONE 4, AND THE RESULTS SHALL BE PROVIDED BY VENDOR.

- (8) LIST OF DOCUMENTS WILL BE FINALIZED IN VPIS.
- (9) List of documents will be finalized in VDIS (Vendor Document Index and Schedule).





احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

PMR FOR F&G SYSTEM									
053 - 073 - 9184	پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سريال	نسخه	شماره صفحه : 19 از 20
000 070 0101	BK	GCS	PEDCO	120	IN	MR	0003	D01	

ATTACHMENT 3

Requisition No.:

Equipment No.:

Description:

DEVIATIONS / EXCEPTIONS TO JOB SPECIFICATION

Item No.	Description of proposed exception	Recommended revision to job specification	Reason for proposed exception	Effect on base proposal if CONTRACTOR rejects exception





احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

ث ملیم بیمان :			DMD	FOR F&G	SVSTE	:M			
شماره پیمان: 9184 – 073 – 053	پروژه	بسته کاری	ا۱۷۱۱ مادر کننده	تسهيلات	رشته	نوع مدرک	سريال	نسخه	شماره صفحه: 20 از 20
000-070-9104	BK	GCS	PEDCO	120	IN	MR	0003	D01	

ATTACHMENT 4

ALTERNATIVES TO JOB SPECIFICATION

Requisition No.:
Description:
Equipment No.:

Item No.	Job Specification No. & Paragraph No.	Requirements of Job Specification	Description of Proposed Alternative	Reason for Proposed Alternative