

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

053 - 073 - 9184

TBE FOR LV SWITCHGEAR, MC	CC & LV CAPACITOR BANK
---------------------------	------------------------

پروژه	بسته کاری	صادر کننده	رشته تسهيلات		نوع مدرك	سريال	نسخه
BK	GCS	PEDCO	120	EL	TB	0002	D01

شماره صفحه: 1 از 18

طرح نگهداشت و افزایش تولید 27 مخزن

TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK

نگهداشت و افزایش تولید میدان نفتی بینک

Date	Purpose of Issue/Status	Prepared by:	Checked by:	Approved by:	Client Approval
ı. 2024	IFI	M.Pourdasht	M.Fakharian	M.Sadeghian	
r. 2025	IFI	M.Fahimi	M.Fakharian	S.Faramarzpour	
_					

Class:3 Client Doc. Number: F0Z-709330

Status:

IDC: Inter-Discipline Check
IFC: Issued For Comment
IFA: Issued For Approval
AFD: Approved For Design
AFC: Approved For Construction
AFP: Approved For Purchase
AFQ: Approved For Quotation
IFI: Issued For Information
AB-R: As-Built for Client Review
AB-A: As-Built –Approved



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:

TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK

053 - 073 - 9184

	_		, -			_		ı
پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرك	سر يال	نسخه	
BK	GCS	PEDCO	120	EL	TB	0002	D01	

شماره صفحه: 2 از 18

REVISION RECORD SHEET

				r	REVISION
PAGE	D00	D01	D02	D03	D04
1	Х	Х			
2	Х	Х			
3	Х	Х			
4	Х	X			
5	Х				
6	X	X			
7	Х	Х			
8	Х	Х			
9	Х	Х			
10	Х	Х			
11	Х	Χ			
12	Х	Х			
13	Х	Х			
14	Х	Х			
15	Х	Χ			
16	Х	Х			
17	Χ	Χ			
18					
19					
20					
21					
22					
23					
24					
25					
26					
27					
28					
29					
30					
31					
32					
33					
34					
35					
36	ļ				
37	ļ				
38	ļ				
39	ļ				
40	ļ				
41	<u> </u>			ļ	
42	ļ				
43	<u> </u>			ļ	
44	ļ				
45	ļ				
46	ļ				
47	<u> </u>			ļ	
48	ļ				
49	ļ				
50					

PAGE	D00	D01	D02	D03	D04
51					
52					
53					
54					
55					
56					
57					
58					
59					
60					
61					
62					
63					
64					
65					
66					
67					
68					
69					
70					
71					
72					
73					
74					
75					
76					
77					
78					
79					
80					
81					
82					
83					
84					
85					
86					
87					
88					
89					
90					
91					
92					
93					
94					
95					
96	1				
97	1				
98					
99					
100					



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:			TBE FOR LV S	SWITCHGEAR, MCC &	LV CAPACITOR BAN	IK		
053 - 073 – 9184	پروژه	بسته کاری	صادركننده	تسهيلات	رشته	نوع مدرک	سر يال	نسخه
000 - 070 - 3104	ВК	GCS	PEDCO	120	EL	ТВ	0002	D01

شماره صفحه: 3 از 18

			TBE for LV S	witchge	ar					
MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002)	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
Item	Description									
1. (General									
1.1	Name of Project / Plant	Binak Oilfield in Bushehr Province	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.2	Reference Doc.	 IPS-M-EL-143(3) LV Switchgear/MCC Single Line Diagram (BK-GCS-PEDCO-120-EL-SL-0002) Specification For LV Switchgear & Motor Control Centers (BK-GNRAL-PEDCO-000- EL-SP-0001) Electrical Typical Schematic Diagrams For LV Panel (BK-GCS-PEDCO-120-EL-DG-0002) Electrical System Design Criteria (BK-GNRAL-PEDCO-000-EL-DC-0001) Process Basis of Design (BK-GNRAL-PEDCO-000-PR-DB-0001) 	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.3	Manufacturer of Cubicles	By Vendor	Ista Noavaran Niroo Co	A	Pars Tableau	A	Taban Tablo Co	A	Runin Sanat Gostar	A
1.4	Manufacturer Type No./Country Origin	By Vendor	Sivacon 8PT / Siemens	A	Normabloc-Iran	A	Sivacon 8pt	A	Sivacon 8pt	С
1.5	Standard	IEC60439, IEC60947, IPS-M-EL-143(3)	IEC61439-1, IEC60947, IPS-M-EL-143(3)	A	Confirmed	A	Confirmed	A	Confirmed	A
1.6	Type Of Cubicle - Fixed/ With draw able	With Draw Able	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.7	Rated Voltage & Variation	400 VAC & ± 10%	400 VAC & ± 5%	A	Confirmed	A	Confirmed	A	Confirmed	A
1.8	Rated Frequency & Variation	50 HZ & ± 5%	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.9	Service Voltage	400 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.10	Number Of Phases	3PH + PE + N	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.11	Number of Cubicles (With Spare)	By Vendor	18	A	21	A	26	A	20	A
1.12	Number of Bus Sections	3	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.13	Power Frequency (One Min)	1.89 KV (ACC to Table 8 of IEC 61439-1)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.14	Impulse Withstand	6 KV (ACC to Table G.1 of IEC 61439-1)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.15	Rated Normal Current of Bus bars	2000 A	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:		TBE FOR LV	SWITCHGEAR, MCC &		ık	
	 . IT 17	- 111 Al -		4		

 السخه سريال
 نيخه سريال
 نوع مدر ک نوع مدر ک الله عليات
 صادر کننده
 سادر کننده

شماره صفحه: 4 از 18

			TBE for LV S	witchge	ar					
MR Item	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002) Description	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
1.16	Rated Short Current of Bus bars	50 KA	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.17	Rated Peak Withstand Current	125 KA	Based IEC 61439-1 Table 7 (Peak current) is considered 105kA	A	Confirmed	A	Confirmed	A	Confirmed	A
1.18	Rated Short Time Duration	1 SEC.	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.19	System Earthing	Solidly Earthed At Transformer Neutral Point	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.20	Voltage of Control Circuit	Incoming/Tie: 110 VDC Outgoing: 230 VAC (by Isolation Transformer for each Cubicle, According to BK-GCS-PEDCO-120-EL-SL-0002	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.21	Incoming Feeder Signaling Circuit	110 VDC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.22	Motor & Heater Outgoing Feeder Signaling Circuit	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.23	Distribution Outgoing Feeder Signaling Circuit	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.24	Panel Light Auto. Door Micro Switch Operated	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.25	Internal Safety Interlocks	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2. 1	Environmental Conditions (Process Basis Desi	gn, BK-GNRAL-PEDCO-000-PR-DB-0001)				•				
2.1	Installation	Indoor, Safe Area	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.2	Max. Ambient Temperature	52 °C	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.3	Min. Ambient Temperature	5 °C	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.4	Relative Humidity (Max.)	100%	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.5	Climate	Corrosive, Hot Atmosphere	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.6	Altitude Above Sea Level	12.5 m	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3. (Cubicle Construction									
3.1	Enclosure	Metal Clad	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.2	Indoor / Outdoor	Indoor	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:			TBE FOR LV S	TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK								
شماره پیمان:	پروژه	بسته کاری	صادر كننده	تسهيلات	رشته	نوع مدرك	سريال					

 استه سریال
 نیخه
 سریال
 نیخه
 سریال
 سریال

شماره صفحه: 5 از 18

TBE for LV Switchgear

MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002)	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
Item	Description									
3.3	Type of Installation	Floor Standing	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.4	Bus Bar Material	Hard Drown, High Conductivity Copper	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.5	Main Bus Bar Insulation Material	Flame Retardant, Non Hygroscopic Insulation Material	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.6	Bus Bar color	L1: Red , L2: Yellow , L3: Blue , N: Black	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.7	Shape of Main Bus Bars	By Vendor	Based on Siemens Standard	A	Acc To Tech Offer	С	2*80*10 Per phase	A	After contract	A
3.8	Neutral Bus Bar Cross Section	By Vendor	Based on Siemens Standard	A	Acc To Tech Offer	C	1*80*10	A	After contract	A
3.9	Type / Material of Main Bus Bar Supporting Insul ators	By Vendor	Based on Siemens Standard	A	Acc To Tech Offer	С	1*80*10	A	After contract	A
3.10	Bus Bar Joints	Silver Plated	Confirmed	A	Confirmed	A	Tin plated (Main busbar, not only joint)	С	Confirmed	A
3.11	Bus Bar Identification	By Vendor	Based on Siemens Standard	A	Acc To Tech Offer	C	Label	A	After contract	A
3.12	Bus Bar Arrangement (Single / Duplicate)	By Vendor	Based on Siemens Standard	A	Acc To Tech Offer	С	Duplicate	A	After contract	A
3.13	Phase Bus Bar Cross Section	By Vendor	Based on Siemens Standard	A	Acc To Tech Offer	C	2*80*10 Per phase	A	After contract	A
3.14	Earth Bus Bar Cross Section	By Vendor	Based on Siemens Standard	A	Acc To Tech Offer	С	1*40*10	A	After contract	A
3.15	Bus bar Cooling Method	Air Natural	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.16	Rear / Front Access	Front Access	Rear Access (limited space in the switchgear room)	A	Confirmed	A	Rear Access (limited space in the switchgear room)	A	Confirmed	A
3.17	Incomings / Outgoings To/From The Switchgear (Bus-Duct/Cable)	Incomings: Cable Outgoings: Cable	Confirmed Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.18	Top / Bottom Entry	Cable: Bottom	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.19	Degree of Protection	IP42	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.20	Min. Cubicle Sheet & Door Thickness For Enclosure	2 mm	Confirmed	A	Confirmed	A	2 mm for body enclosure	С	Confirmed	A
3.21	Tropic Design	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.22	Provision For Extension at Each End of Switchgear	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.23	Paint Color Shade	Ral 7032 (Light Grey)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A





احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

تماره پیمان: TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK

ا نسخه سريال نوع مدرک رشته تسهيلات صادر کننده بسته کاری پروژه BK GCS PEDCO 120 EL TB 0002 D01

شماره صفحه: 6 از 18

			TBE for LV S	witchge	ar					
MR Item	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002) Description	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
3.24	Thickness of Paint Coating	60 – 80 Micron	Confirmed	A	Confirmed	A	Confirmed	A	80-120 Micron	A
	Circuit Breaker (ACB)	00 00 1330							00 120 1110101	
4.1	Manufacturer / Country	By Vendor	ABB/SIEMENS West	A	Schneider	Ι Δ	ABB	Δ.	Schneider	Δ.
	·	•	Europe			A		A		A
4.2	Manufacturer Type No.	By Vendor	3WL/3VA/Emax	A	NW/NT	A	Emax	A	NW/NT	A
4.3	Type Of Main CB (Air / Vacuum / Others)	Air	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.4	No. of Poles in Main ACB	4 Pole	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.5	Rated Insulation Voltage	1000 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.6	Rated Operating Voltage	400 VAC	Confirmed	Α	Confirmed	A	Confirmed	A	Confirmed	A
4.7	Rated Current	By Vendor, Based on Load List (BK-GCS-PEDCO-120-EL-LI-0001)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.8	Rated Breaking Current *	50 KA	Confirmed	Α	Confirmed	A	Confirmed	A	Confirmed	A
4.9	Rated Making Current *	125 KA	Based on IEC 61439-1: 105kA	A	Confirmed	A	Confirmed	A	Confirmed	A
4.10	S/C Withstanding Time	1 SEC.	Confirmed	Α	Confirmed	A	Confirmed	A	Confirmed	A
4.11	Closing Time	By Vendor	5-10 s	A	Acc To Catalog	A	5-10 s	A	After contract	С
4.12	Tripping Time	By Vendor	40 ms	A	Acc To Catalog	A	40 ms	A	After contract	C
4.13	Rated Electrical Life	By Vendor	10000	A	Acc To Catalog	A	10000	A	After contract	C
4.14	Power Consumption of Closing Coil	By Vendor	5~10W	A	Acc To Catalog	A	5~10W	A	After contract	С
4.15	Power Consumption of Tripping Coil	By Vendor	5~10W	A	Acc To Catalog	A	5~10W	A	After contract	С
4.16	Power Consumption of Spring Charging Motor	By Vendor	60~90W	A	Acc To Catalog	A	60~90W	A	After contract	С
4.17	Spring Charge Motor Voltage Supply	110 VDC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.18	No. of Circuit Breaker Operating With Charged Spring	5	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.19	Anti-Pumping Feature	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.20	Shutters	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



									┙
شماره پیمان:			TBE FOR LV S	SWITCHGEAR, MCC &	LV CAPACITOR BAN	ık			
053 - 073 - 9184	پروژه	بسته کاری	صادركننده	تسهيلات	رشته	نوع مدرک	سر يال	نسخه	
000 070 0101	BK	GCS	PEDCO	120	EL	ТВ	0002	D01	Ì

شماره صفحه : 7 از 18

	TBE for LV Switchgear										
MR Item	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002) Description	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status	
4.21	Additional Auxiliary Contacts	By Vendor	If Required	A	Acc To Catalog	A	By Aux Relay	A	Refer to technical proposal	A	
4.22	Closed/Open Position Indication	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
4.23	Charged/Discharged Spring Indication	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
5.]	МССВ										
5.1	Manufacturer of MCCB	By Vendor	ABB/SIEMENS west Europe	A	Schneider	A	ABB	A	Schneider	A	
5.2	Rated Insulation Voltage	1000 VAC	690/1000 VAC	A	Confirmed	A	Confirmed	A	Confirmed	A	
5.3	Rated Operating Voltage	400 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
5.4	Rated Current	According to "BK-GCS-PEDCO-120-EL-SL-0002"	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
5.5	NO. of Poles	3 Pole	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
6.]	MPCB										
6.1	Manufacturer of Switch-Fuse	By Vendor	SIEMENS /ABB	A	Schneider	A	ABB	A	Schneider	A	
6.2	Rated Insulation Voltage	1000 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
6.3	Rated Operating Voltage	400 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
6.4	Rated Current	According to "BK-GCS-PEDCO-120-EL-SL-0002"	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
6.5	NO. of Poles	3 Pole	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7.	Contactor										
7.1	Manufacturer Country	By Vendor	ABB/Siemens	A	Schneider	A	ABB	A	Schneider	A	
7.2	Manufacturer Type No.	By Vendor	3RT/AF	A	LC	A	AC3	A	LC1D	A	
7.3	Type of Contactor (Air / Vacuum)	Air/AC3	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7.4	Rated Insulation Voltage	1000 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7.5	Rated Operating Voltage	400 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7.6	Rated Current	By Vendor, Based On SLD	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:		TBE FOR LV S	SWITCHGEAR, MCC &	LV CAPACITOR BAN	1K

 اسخه سریال
 نیخه سریال
 نیخه سریال
 نوع مدرک
 رشته
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 EL
 TB
 0002
 D01

شماره صفحه: 8 از 18

			TBE for LV S	witchge	ar					
MR Item	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002) Description	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
7.7	Closing Time	By Vendor	4~70mS	A	Acc To Catalog	A	4~70mS	A	After contract	A
7.8	Tripping Time	By Vendor	3~5mS	A	Acc To Catalog	A	3~5mS	A	After contract	A
7.9	Power Consumption of Elec. Bobbin	By Vendor	2W	A	Acc To Catalog	A	2W	A	After contract	A
7.10	Rated Electrical Life	By Vendor	15000	A	Acc To Catalog	A	15000	A	After contract	A
7.11	Rated Short Circuit Life	By Vendor	20000	A	Acc To Catalog	A	20000	A	After contract	A
7.12	Elect. Bobbin Voltage Supply	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
7.13	Utilization Category	By Vendor	AC3	A	AC3	A	AC3	A	After contract	A
7.14	RC Element	Where Is Applicable	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
7.15	NO. of Poles	3 Pole	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
8.	Thermal Relays									
8.1	Manufacturer Country	By Vendor	ABB/Siemens	A	Schneider	A	ABB	A	Schneider	A
8.2	Manufacturer Type No.	By Vendor	3RB/RT	A	LRD	A	Thermal	A	LRD	A
8.3	Rated Operating Voltage	400 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
8.4	Single Phasing Protection	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
8.5	Thermal Relay Adjustable Range	By Vendor (ACC to Coordination type 2) , According to "BK-GCS-PEDCO-120-EL-SL- 0002"	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
8.6	Thermal Relay Reset Feature	Yes Via a Door Mounted Push-Button	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
9.	PT'S-FIXED TYPE									
9.1	Manufacturer Country	By Vendor	Zafar/ Azmoon Trans	A	Azmoon Trans	A	Azmoon Trans	A	Azmoon Trans	A
9.2	Rated Operating Voltage	400/√3 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
9.3	Rated Secondary Voltage	$110/\sqrt{3} \text{ VAC}$, $230/\sqrt{3} \text{ VAC}$	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
9.4	Accuracy Class	Measuring : 1 Protection : 3P	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
9.5	Burden	By Vendor	5 VA	A	20 VA	A	15 VA	A	50 VA	A



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:		TBE FOR LV	SWITCHGEAR, MCC &	LV CAPACITOR BAN	IK

 اسخه سریال
 نیخه سریال
 نیخه سریال
 نیخه سریال
 سریال
 سریال
 نیخه سریال
 سریال</t

شماره صفحه: 9 از 18

			TBE for LV S	witchge	ar					
MR Item	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002) Description	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
9.6	Single-Phase / Three-Phase	3 Phase	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
9.7	Rated Voltage Factor	By Vendor	At detail stage	A	Acc To Catalog	A	230	A	After contract	A
10.	CTs									
10.1	Manufacturer Country	By Vendor	Mag Electric	A	Mag Electric	A	Mag Electric	A	Novin Harris	С
10.2	Rated Operating Voltage	400 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
10.3	Rated Primary Current	By Vendor, Based on SLD	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
10.4	Rated Secondary Current	1 A	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
10.5	Insulation Class	By Vendor	Е	A	F	A	F	A	F	A
10.6	Accuracy Class	Measuring: 1 Protection: 5P10	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
11.	Protection									
11.1	Manufacturer Country	By Vendor	Siemens	A	Schneider	A	Schneider	A	Schneider	A
11.2	Manufacturer Designation No.	By Vendor	Reyrolle	A	Eassergy	A	Eassergy	A	Eassergy	A
11.3	Type of Protection Relays For Incomers/Tie	Multi-Function, Microprocessor Based	7SR	A	Р3	A	Р3	A	P3	A
11.4	No. of Contacts	MIN. 4	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
11.5	Contact Rating Current	5 A	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
11.6	Auto Diagnostic & Self Supervision	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
11.7	Serial Link Communication Port	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
12.	Measuring & Control System									
12.1	Manufacturer of Indicators / Country	By Vendor	Ziegler	A	Schneider	A	Schneider	A	BEW	С
12.2	Accuracy Class Of Indicators	CL.1	Confirmed	A	Confirmed	A	Confirmed	A	1.5	С
12.3	Manufacturer of Selector Switch	By Vendor	TRS	A	KAVEH	A	Trs / Raad	A	Schneider	A
12.4	Manufacturer of Push Buttons	By Vendor	Schneider/Raad	A	Schneider	A	Raad	С	Schneider	A



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:			TBE FOR LV S	SWITCHGEAR, MCC &	LV CAPACITOR BAN	NK	
053 - 073 - 9184	پروژه	بسته کاری	صادر كننده	تسهيلات	رشته	نوع مدرک	
000 070 0101							

 نسخه
 سریال
 نوع مدر ک
 رشته
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 EL
 TB
 0002
 D01

شماره صفحه : 10 از 18

			TBE for LV S	witchge	ear					
MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002) Description	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
Item	•	D. V. I			0.11		D 1	G	0.11	
12.5	Manufacturer of Indication Lamps	By Vendor	Schneider/Raad	A	Schneider	A	Raad	С	Schneider	A
12.6	Manufacturer of Terminals	By Vendor	Raad	A	Raad	A	Raad	A	Raad	A
12.7	Manufacturer of AUX. Relays	By Vendor	Omron	A	Weidmueller	A	Omron	A	Weidmueller	A
12.8	Remote Control Indication / Alarm / Inter trip / ET C.	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
12.9	Mimic Diagram	Not Applicable	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
12.10	Size of Control Wiring	2.5 mm2 for CT'S 1.5 mm2 for Other	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
12.11	Ammeter / Voltmeter Manufacture	By Vendor	Ziegler	A	BEW	C	BEW	C	BEW	С
12.12	Ammeter / Voltmeter Class	CL.1	CL: 1.5	С	Confirmed	A	Confirmed	A	1.5	С
12.13	Ammeter / Voltmeter range	According to "BK-GCS-PEDCO-120-EL-SL-0 002"	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
12.14	Multi Meters Manufacture	By Vendor	Schneider	A	Schneider	A	DM6200 Schneider	A	Schneider	A
12.15	Multi Meters Class	CL.0.5	Confirmed	A	Confirmed	A	Confirmed	A	1	С
13. I	Miscellaneous									
13.1	Routine Tests Foreseen	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
13.2	Type Tests Foreseen	No, If Certified	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
13.3	Two Years Op. & Comis. Spare Parts Proposed	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
13.4	Special Tools	Yes, If Required	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
13.5	Accessories	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
13.6	Mimic Diagram for Each Cubicle	Yes for Incoming	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
13.7	Dimension of One Cubicle (H X W X D)	By Vendor	Acc. to arrangement layout based on front or rear access	A	Acc. to arrangement layout based on front or rear access	A	Acc. to arrangement layout based on front or rear access	A	Acc. to arrangement layout based on front or rear access	A
13.8	Overall Dimension (H X W X D)	By Vendor	After Detail Desig	A	Acc. to arrangement layout based on front or rear access	A	Acc. to arrangement layout based on front or rear access	A	Acc. to arrangement layout based on front or rear access	A
13.9	Weight of One Cubicle	By Vendor	250~320 Kg per cel	A	250~320 Kg per cel	A	250~320 Kg per cel	A	250~320 Kg per cel	A



نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض

شرکت توریزاران HIRGAN ENERGY

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

تماره پیمان: TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK

ا نسخه سريال نوع مدر ک رشته تسهيلات صادر کننده بسته کاری پروژه BK GCS PEDCO 120 EL TB 0002 D01

شماره صفحه : 11 از 18

			TBE for LV S	witchge	ar					
MR Item	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002) Description	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
13.10	Total Weight of Cubicles	By Vendor	After Detail Desig	A	After Detail Desig	A	After Detail Desig	A	After Detail Desig	A
13.11	Time Schedule Prepared	By Vendor	Based on Offer	A	Confirmed	A	After P.O	A	After contract	A
13.12	Delivery Time	By Vendor	120 Day	A	Confirmed	С	3months	A	After contract	С
13.13	Any Deviations From Spec.	By Vendor	Based on Offer	С	Confirmed	С	As Attached	С	Refer To Technical Proposal	С
14.	Accessories								Порози	
14.1	Illumination (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.2	Lifting Lugs (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.3	Space Heater With Thermostat (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.4	C.B. Position Indicator	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.5	Door Key (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.6	C.B. Charging / Retracting (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.7	Voltage and Current Test Block for Protection Rel ays (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.8	Lamp Test Facility (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Based On SLD	С
14.9	Automatic Shutter (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.10	Floor Frame (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.11	C.B. Transfer Trolley (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.12	Name Plate & Front Tag & Rear Side Tag (Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
14.13	Telescopic Rotary Handle for MCCB(Y/N)	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
15.	Mechanical Interlock									
15.1	Door Shall Not Able To Open When C.B. Is Closed	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
15.2	Impossibility of C.B. Rack-In / Rack-Out When C. B. Is Closed	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
15.3	Padlock for C.B.	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A



HIRGAN ENERGY

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

شماره پیمان: TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK نوع مدرك بسته کاری صادر كننده تسهيلات پروژه سريال 053 - 073 - 9184 GCS PEDCO TB BK 120 EL 0002 D01

شماره صفحه : 12 از 18

	TBE for LV Switchgear									
MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002)	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runin Sanat	Status
Item	Description									
15.4	MCCB Open / Close From Closed Door Through Lockable Telescopic Rotary Handle	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
16. l	Panel Space Heater Technical Data									
16.1	Voltage	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
16.2	Power Consumption	By Vendor	100 W	A	80 W	A	100W	A	60 W	A
17. l	Panel Light Technical Data									·
17.1	Type No.	By Vendor	LED	A	LED	A	LED	A	LED	A
17.2	Voltage	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
17.3	Power Consumption	By Vendor	8 W	A	5 W	A	8 W	A	5 W	A

Status Legends:

A=Acceptable

N=Not Acceptable

N/A=Not Applicable

INA=Information Not Available

C=Clarification is Required

CA= Conditionally Acceptable

M = Requirement is Mandatory



نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK

ا نسخه سريال نوع مدر ک رشته تسهيلات صادر کننده بسته کاری پروژه BK GCS PEDCO 120 EL TB 0002 D01

شماره صفحه: 13 از 18

			TBE for 1	LV Capa	acitor Bank					
MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002)	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runnin Sanat	Status
Item	Description									
1. G	eneral Information									
1.1	Quantity	1 Set for Each LV Switchgear (Note 2)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.2	Tag Numbers	CB01 & CB02	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.3	Applicable Standards	IEC 60831 IPS-M-EL-181(2) IPS-M-EL-143(3)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.4	Applicable Document	BK-GNRAL-PEDCO-000-EL-SP-0012 BK-GCS-PEDCO-120-EL-CN-0011 BK-GNRAL-PEDCO-000-EL-SP-0001	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
1.5	Manufacturer's Name	By Vendor	Ista Noavaran Niroo Co	A	Pars Tableau	A	Taban Tablo	A	Runnin Sanat	A
2. E	nvironmental Conditions (Process Basis Design	n, BK-GNRAL-PEDCO-000-PR-DB-00	01)							
2.1	Location	Binak Oilfield in Bushehr Province	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.2	Hazardous Area Classification	Safe	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.3	Max. Outdoor Ambient Temperature	50°C	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.4	Minimum Indoor Ambient Temp.	-5°C	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.5	Maximum Indoor Relative Humidity	100%	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.6	Altitude (Above Sea Level)	12.5 m	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.7	Seismic Factor	Zone 3	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
2.8	Installation	Indoor	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3. E	lectrical Data									
3.1	System Voltage	400V AC ±10%	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.2	System Frequency	50 Hz ±5%	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.3	No. of Phases	3	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.4	Control Voltage	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.5	Space Heater Voltage	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A



نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض





احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK

 نسخه
 سریال
 نوع مدرک
 رشته
 تسهیلات
 صادر کننده
 بسته کاری
 پروژه

 BK
 GCS
 PEDCO
 120
 EL
 TB
 0002
 D01

شماره صفحه : 14 از 18

	TBE for LV Capacitor Bank									
MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002)	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runnin Sanat	Status
Item	Description	215 A	G . C . 1		G . C . 1		G . C . 1		G . C . 1	
3.6	Bus-Bar Rated Current	315A	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.7	Short Time Withstand Current	50 kA, 1 Sec.	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.8	Bus-Bars Material	Heat Shrink Copper	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
3.9	Bus-Bars Joints	Silver Plated	Confirmed	A	Confirmed	A	Tin plated (Main busbar, not only joint)	A	Confirmed	A
4. Eı	nclosure Data									
4.1	Enclosure Type	Free Standing/Fixed Type / Front Access	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.2	Degree of Protection	IP 42	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.3	Cable Entry	Bottom (by Cable Gland)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.4	Type & Size of Power Cable	According to "BK-GCS-PEDCO-120- EL-CN-0003" (4C×120 mm2 CU/XLPE/SWA/PVC)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.5	Control Cable	2×(5C× 4 mm2) for Current & Voltage Sample	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.6	Material	Painted Sheet Steel	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.7	Color	RAL 7032	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.8	Dimensions (HxWxD)	By Vendor	At detail stage	A	At detail stage	A	2200*800*800	A	At detail stage	A
4.9	Sheet Steel Thickness (Body/Frame)	2mm/2.5mm	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
4.10	Weight	By Vendor	300 ~ 350 Kg	A	300 ~ 350 Kg	A	300 ~ 350 Kg	A	300 ~ 350 Kg	A
5. Ca	apacitors									
5.1	Capacitor Manufacturer/Model No./Year	By Vendor	PKC	A	Hydra	С	FARAKOH/; IFASA/ SABAKHAZEN	A	Palayesh Nirou	A
5.2	Rating of each Capacitor Bank	140Kvar = 1x20Kvar Fix + 6x20Kvar	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A
5.3	Capacitor Bank Rated Current	By Vendor	At detail stage	A	At detail stage	A	At detail stage	A	At detail stage	A
5.4	Capacitor Bank Rated Voltage	440V	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:	TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK										
053 - 073 - 9184	پروژه	بسته کاری	صادر كننده	تسهيلات	رشته	نوع مدرک	سر يال	نسخه			
000 070 0101	ВК	GCS	PEDCO	120	EL	ТВ	0002	D01			

شماره صفحه : 15 از 18

	TBE for LV Capacitor Bank										
MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002)	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runnin Sanat	Status	
Item	Description										
5.5	Capacitor Bank Connection Type	Delta	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
5.6	Capacitor Unit Temp. Category	-5/D	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
5.7	Capacitor Unit Case Material	Aluminum	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
5.8	Capacitor Unit Discharge time (to 75V)	<3 Minutes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
6. C	ontrol Unit (Regulator)										
6.1	Manufacturer / Type	By Vendor	PKC	A	PKC	A	Schneider	A	Palayesh Nirou	A	
6.2	Mode of Operation	Automatic & Manual	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
6.3	Number of Steps	5 Steps	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
6.4	Selector Switch	Auto/Off/Manual Selector Switch For Each Step	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7. F	uses										
7.1	Manufacturer / Type	By Vendor	ETI	A	Pichaz	A	Pichaz	A	ETI	A	
7.2	Rated Current	1.5 times of Capacitor Rated Current	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7.3	Inrush Current	100 times of Capacitor Rated Current	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7.4	Rated Voltage	500V	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7.5	Service Voltage	400V±10%	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
7.6	Rated Frequency	50Hz±5%	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
8. C	ontactors										
8.1	Manufacturer / Type	By Vendor	Siemens	A	Schneider	A	RK / LIFASA	A	schneider	A	
8.2	Rated Voltage	690V AC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
8.3	Service Voltage	400V AC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
8.4	Coil Voltage	230 VAC (Note 2)	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
8.5	Duty	AC6-b	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	



نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض



احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK

نسخه سریال نوع مدر ک رشته تسهیلات صادر کننده بسته کاری پروژه BK GCS PEDCO 120 EL TB 0002 D01

شماره صفحه : 16 از 18

	TBE for LV Capacitor Bank										
MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002)	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runnin Sanat	Status	
Item	Description										
9. In	coming Circuit Breaker										
9.1	Manufacturer / Type	By Vendor	ABB / Siemens	A	Schneider	A	ABB	A	schneider	A	
9.2	Туре	MCCB, 4Pole, Fixed Type	Confirmed	A	Confirmed	A	Confirmed	A	3 Pole	A	
9.3	Rated Current	315A	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
9.4	Rated Short Circuit Breaking Current	50 kA	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
9.5	Rated Insulation Voltage	1000 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
9.6	Service Voltage	400V	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
9.7	Internal Protections	49, 50, 51	Confirmed	A	Confirmed	A	49 & 50	A	49 & 50	A	
9.8	Voltage Protection	230 VAC	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
9.9	Trip and Status aux. switches	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
10. V	oltmeter with Selector Switch										
10.1	Manufacturer / Type	By Vendor	Ziegler	A	BEW	C	Voltmeter: BEW Selectoe: TRS	С	BEW	C	
10.2	Operating Range	0 -500V	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
10.3	Accuracy Class	1.5	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
11. A	ccessories										
11.1	Panel Lighting & Space Heater with Thermostat/Hygrostat	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
11.2	Door Key	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
11.3	Gland Plate	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
11.4	Terminal Lugs	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
11.5	Commissioning Spare Parts	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
11.6	Two Year Operation Spare Parts	Yes	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
11.7	Routine Test	Witnessed and Report	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	



المركة تبديتواما^ن HIRGAN ENERGY

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک

TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK

 اسخه سریال
 نیخه سریال
 نیخه سریال
 نیخه سریال
 سریال
 سریال
 نیخه سریال
 سریال</t

شماره صفحه : 17 از 18

	TBE for LV Capacitor Bank										
MR	PMR For LV Switchgear, MCC & LV Capacitor Bank (BK-GCS-PEDCO-120-EL-MR-0002)	Purchaser Requirement	Ista Noavaran Niroo	Status	Pars Tableau	Status	Taban Tablo Shargh	Status	Runnin Sanat	Status	
Item	Description										
11.8	Type Test CERTIFICATE	Certificat	Confirmed	A	Confirmed	A	Confirmed	A	Confirmed	A	
12. In	12. Inrush Reactor										
12.1	Inrush Reactor Requied (Y/N)	By Vendor	PKC / Zafar / Azmoon	A	PKC	A	Farakoh	A	PKC	A	
12.2	Inductance (mH)	By Vendor	At detail stage	A	At detail stage	A	At detail stage	A	At detail stage	A	
12.3	Туре	By Vendor	At detail stage	A	At detail stage	A	At detail stage	A	At detail stage	A	

Status Legends:

A=Acceptable

N=Not Acceptable

N/A=Not Applicable

INA=Information Not Available

C=Clarification is Required

CA= Conditionally Acceptable

M = Requirement is Mandatory



نگهداشت و افزایش تولید میدان نفتی بینک سطح الارض

احداث ردیف تراکم گاز در ایستگاه جمع آوری بینک



شماره پیمان:	TBE FOR LV SWITCHGEAR, MCC & LV CAPACITOR BANK										
L	پروژه	بسته کاری	صادر کننده	تسهيلات	رشته	نوع مدرک	سر يال	نسخه			
	BK	GCS	PEDCO	120	EL	ТВ	0002	D01			

شماره صفحه: 18 از 18

Conclusion Table:

Item	Equipment	Ista Noavaran Niroo	Pars Tableau	Taban Tablo Shargh	Runin Sanat Gostar
1	LV MCC Switchgear	Acceptable	Acceptable	Acceptable	Acceptable
2	LV Capacitor Bank	Acceptable	Acceptable	Acceptable	Acceptable

Conclusion Note:

- 1- The maximum design temperature of LV switchgear is 40 °C.
- 2- Protection relay is not acceptable on the C.B (Built-in type), Protection relay shall be externally type.